

Haryana Government Gazette EXTRAORDINARY

Published by Authority

© Govt. of Haryana

No. 173–2020/Ext.] CHANDIGARH, WEDNESDAY, NOVEMBER 18, 2020 (KARTIKA 27, 1942 SAKA)

हरियाणा सरकार

नगर तथा ग्राम आयोजना विभाग

तथा

शहरी स्थानीय निकाय विभाग

अधिसूचना

दिनांक 18 नवम्बर, 2020

संख्या सी.सी.पी. (एन.सी.आर.) वाई.एन.आर./डी.डी.पी.—2041/2020/1542.— चूंकि, दिनांक 06 मार्च, 1965 तथा 29 मई, 1997 को अधिसूचित नियंत्रित क्षेत्रों के लिए 6.88 लाख की अनुमानित जनसंख्या हेतू हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग अधिसूचना संख्या सी.सी.पी. (एन.सी.आर.)/वाई.सी.ए.—1/2005/36, दिनांक 14 जनवरी, 2005 द्वारा यमुनानगर जगाधरी की प्रारूप विकास योजना—2021 ए.डी. राजपत्र में प्रकाशित की गई थी। विकास योजना प्रस्तावित दादूपूर—नलवी नहर के संरेखण को शामिल करने हेतु संशोधित किया गया था, चूंकि यह नहर विकास योजना में प्रस्तावित सेक्टरों के बीच में से होकर गुजर रही थी। इसके अतिरिक्त, जनसंख्या सघनता, जनसंख्या अनुमानों तथा नहर मुहानों के समुपयोजन के अनुसार प्रकाशित विकास योजना में सुधार की गुंजाइश है। तद्नुसार, इसे 2021 तक 11,50,000 व्यक्तियों की जनसंख्या को समायोजित करने के लिए संशोधित किया गया है। संशोधित प्रारूप विकास योजना—2021 ए.डी. हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग अधिसूचना संख्या सी.सी.पी.(एन.सी.आर.)/वाई.सी.ए.—1/आर.डी.डी.पी./ 2006/3588, दिनांक 7 दिसम्बर, 2006 द्वारा राजपत्र में प्रकाशित हुई थी।

तथा चूंकि, उपरोक्त संशोधित प्रारूप विकास योजना 2021 ईस्वी को, समय–समय पर, हुए निम्नलिखित क्रम विकासों के कारण अंतिम रूप नहीं दिया जा सका थाः–

- (क) यमुनानगर—जगाधरी की नगर—परिषद के इर्द—गिर्द हरियाणा सरकार राजपत्र, अधिसूचना संख्या सी.सी.पी. (एन.सी.आर.)वाई. एन.(ए.सी.ए.—III)ए/2007/422, दिनांक 9 फरवरी, 2007 द्वारा अतिरिक्त नियंत्रित क्षेत्र— III अधिसूचित किया गया था;
- (ख) हरियाणा सरकार शहरी स्थानीय विभाग, अधिसूचना संख्या 18/2/2010—3 क1, दिनांक 17 मार्च, 2010 द्वारा नगरनिगम, यमुनानगर की अधिसूचना;
- (ग) सेक्टर सघनता 80 व्यक्ति प्रति एकड़ से 100 व्यक्ति प्रति एकड़ तथा 100 व्यक्ति प्रति एकड़ से 120 व्यक्ति प्रति एकड़ की वृद्धि करने हेतु राज्य की सभी विकास योजनाओं को संशोधित करने के लिए वर्ष 2009 में सरकार द्वारा लिया गया निर्णय।
- (घ) विभाग की नए पॉलिसी उपबंधों अर्थात् अर्फोडेबल हाऊसिंग पॉलिसी, नई एकीकृत अनुज्ञापन पॉलिसी, दीन दयाल जन आवास योजना, हरियाणा भवन संहिता—2017 इत्यादि से संबंधित समर्थकारी प्रावधानों को शामिल करना।

- (ड.) सहारनपुर—यमुनानगर—पंचकूला को जोड़ने वाले राष्ट्रीय राजमार्ग—344 (पूर्व में राष्ट्रीय राजमार्ग—73) के नए संरेखण को शामिल करना।
- (च) जमीनी हकीकत के अनुरूप विकास प्रस्तावों को सुनिश्चित करने के लिए सैटलाइट कल्पनाओं को ध्यान में रखते हुए विकास योजनाओं को तैयार करने के संबंध में निर्देश;
- (छ) वाणिज्यिक सेक्टर तथा परिवहन तथा संचार अंचल के रूप में टिम्बर मार्किट के विकास के संबंध में माननीय मुख्यमंत्री की घोषणा;
- (ज) दादूपूर नलवी नहर के लिए अभिगृहीत क्षेत्र को रद्द करने हेतु दिनांक 3 अगस्त, 2018 को सिंचाई तथा जल संसाधन विभाग, हरियाणा सरकार द्वारा जारी अधिसूचना;
- (झ) विकास योजना के दक्षिण तथा उत्तरी सेक्टरों के मध्य अच्छी संयोजकता की आवश्यकता;

तथा चूंकि, यमुनानगर जगाधरी के लिए प्रारूप विकास योजना 2031 ईस्वी, दिनांक 30 जुलाई,2019 को आयोजित बैठक में जिला स्तरीय समिति के समक्ष रखी गई थी तथा योजना निम्नलिखित <u>टिप्पणी / सुझावों</u> के साथ जिला स्तरीय समिति दवारा मंजूर कर दी गई थी:–

- (i) विकास योजना कम से कम 20 वर्षों के लिए तैयार की जानी चाहिये तथा जैसा कि यह पहले से ही वर्ष 2019 है, इसलिए इसे 2031 ईस्वी के बजाय 2041 ईस्वी के लिए योजनाबद्ध किया जाना चाहिए।
- यमुनानगर-जगाधरी एक उत्तम निवेश स्थान है तथा इसमें संतुलित क्षेत्रीय तथा चिरस्थायी विकास, कौशल (ii) विकास सहित नवीनता तथा प्रौद्योगिकी को अपनाने के लिए सुविधा प्रदान करने की संभावना है तथा यह जिले में रोजगार के अवसर सृजित कर सकता है। मैटल युटेन्सल कलस्टर, जगाधरी तथा प्लाईवुड कलस्टर, यमुनानगर जिले में दो मुख्य पारम्परिक मार्किट अग्रणी हैं जो लघु तथा मध्यम पैमाना इकाईयों में ध्यान केन्द्रित करते हैं तथा ये कलस्टर अनुरूप भूमि के उपलब्ध न होने के कारण वृद्धि के विस्तार तथा अगले स्तर को प्राप्त करने में समर्थ नहीं हुए हैं। ये दो पारम्परिक कलस्टर सरकार दवारा आरम्भ की गई उद्यम प्रोन्नति नीति, 2015 में विशेष केन्द्रित होने के लिए विशेष रूप से चिहिनत किए गए हैं। नीति के अनुसार, इन कलस्टरों को अपनी प्रतिस्पर्धा में वृद्धि करने के लिए तथा अपनी खोई हुई नेतृत्व स्थिति को पुनः प्राप्त करने के लिए स्थान बदले जाने की आवश्यकता है। नीति आवश्यक रूप से क्षेत्रीय प्रक्षेप तथा औद्योगिक वृद्धि को बढावा देने के लिए आवश्यक रूप से केन्द्रित करती है जो कुछ क्षेत्रों के लिए विशेष है। यह क्षेत्र में निवेश को आकर्षित करेगी जो स्थानीय, विदेशी निवेशकों तथा कॉर्पोरेट के लिए अनुकूल वातावरण सुजित करेगी जो सरकारी खजाने को लाभ भी पहुँचाएगी। इसलिए, व्यापक औद्यागिक नगर होने के कारण तथा औद्योगिक वृद्धि को मजबूत करने के लिए यमुनानगर—जगाधरी विकास योजना में यमुनानगर तथा जगाधरी के लिए अलग से मुख्य औद्योगिक जोनों पर विचार किया जाना चाहिए तथा औद्योगिक उपयोग के लिए क्षेत्र शहरी सीमा के 30 प्रतिशत तक बढ़ाया जाना चाहिए। नया औद्योगिक जोन राष्ट्रीय राजमार्ग-907 (जगाधरी-पाँवटा साहिब सड़क) के साथ-साथ विद्यमान हरियाणा राज्य औद्योगिक तथा अवसंरचना विकास निगम औद्योगिक संपदा के नजदीक तथा दक्षिणी सेक्टर सडक वी-2 (डी) के बीच क्षेत्र तथा विद्यमान बाहरी परिधीय सडक अर्थात राष्ट्रीय राजमार्ग-344 तथा राज्य राजमार्ग ६ ए के साथ-साथ माणकपुर में योजनाबद्ध किया जाना चाहिए।
- (iii) वर्ष 2021 के लिए दशकीय जनसंख्या वृद्धि 82 प्रतिशत तक अनुमानित की गई है जो अधिक प्रतीत होती है तथा 2041 ईस्वी तक दशकीय वृद्धि की प्रयोजना के लिए संशोधित वास्तविक दृष्टिकोण अपनाया जाना चाहिए। इसलिए, औद्योगिक क्षेत्र में वृद्धि के साथ—साथ अस्थायी जनसंख्या तथा प्रवासियों को समायोजित करने के लिए विकास योजना में औद्योगिक क्षेत्रों को बढ़ाते हुए, विकास योजना 2031 ईस्वी के बजाय भावी वर्ष 2041 ईस्वी के लिए तैयार की जानी चाहिए।
- (iv) सिमिति राष्ट्रीय राजमार्गों / राज्य राजमार्गों के साथ—साथ "इंटीग्रेटिड वेसाईड एमीनीटिज हब" के लिए प्रावधान शामिल करने हेतु निदेशक, नगर तथा ग्राम आयोजना, हिरयाणा के सुझाव से सहमत है। ऐसी सुविधाएँ, लंबी दूरी के यात्रियों के लिए सुरक्षित तथा आरामदायक यात्रा सुनिश्चित करने हेतु आधारभूत सेवाएँ तथा सुविधाएँ प्रदान करने वाले मुख्य सड़कमार्गों के आगे अनेक अंतरालों पर अवस्थित होनी चाहिए। सबसे अहम, यह ड्राइवरों (विशेष रूप से ट्रक ड्राइवरों) के आराम के लिए आरामदायक स्थान उपलब्ध करवाकर दुर्घटनाओं को कम करेगी तथा सड़क सुरक्षा को सुधारेगी।
- (v) समिति ने यह भी बताया है कि वर्तमान में सेक्टर 6 घने रूप से निर्मित है तथा पूर्णतः आवासीय कालोनियों से घिरा हुआ है, जिसे औद्योगिक सेक्टर के रूप में प्रस्तावित किया गया है तथा इसलिए उसका उपयोग औद्योगिक के बजाय आवासीय के रूप में बदला जा सकता है;
- (vi) सिमिति ने यह भी बताया है कि डेडिकेटिड फ्रैंट कोरिडोर कॉरपोरेशन ऑफ इण्डिया ने पहले ही इस्टर्न डेडिकेटिड फ्रेंट कोरिडोर का कार्य शुरू कर दिया है जो जिला यमुनानगर से गुजर रहा है तथा इसे भी विकास योजना में शामिल किया जा सकता है।

- (vii) आगे, सिंचाई विभाग के कार्यकारी अभियन्ता द्वारा बताया गया था कि जिले से होकर गुजरने हेतु पश्चिमी यमुना नगर के विस्तार के लिए प्रस्ताव पहले ही सरकार को प्रस्तुत कर दिया गया है तथा जिसे भविष्य में स्वीकृत किए जाने की संभावना है। योजना में प्रस्तावित की गई 30 मीटर चौड़ी साध्य नहीं है तथा इसलिए, समिति द्वारा यह निर्णय लिया गया था कि विकास योजना में 30 मीटर चौड़ी सड़क के बजाय हरित स्थान/पट्टी प्रस्तावित की जा सकती है।
- (viii) आगे, सिमित दादूपुर—नलवी नहर के दक्षिणी ओर 30 मीटर चौड़ी सड़क के प्रस्ताव पर विचार कर रही है, जिसमें 20 मीटर चौड़ी सड़क लोक निर्माण (भवन तथा सड़कें) विभाग द्वारा पहले ही निर्मित की जा चुकी है, जो जगाधरी छछरौली सड़क जो जगाधरी अम्बाला सड़क से जोड़ती है। 20 मीटर चौड़ी सड़क दादूपुर नलवी नहर के रास्ता अधिकार में निर्मित की जा चुकी है जो आशिंक रूप से सरकार द्वारा रदद की गई है। हालाँकि, गाँव भुकरी तथा भटोली, जो विकास योजना की शहरी सीमा में भी आते है, की राजस्व सम्पदा के बीच आने वाले नहर के भाग को, वर्ष 2004 से अभिगृहीत नगण्य क्षेत्र के सिवाय, रद्द नहीं किया गया है। इसके अलावा, नहर का दक्षिणी छोर घना निर्मित है। तथा प्रस्तावित 30 मीटर सेक्टर विभाजन सड़क के विस्तार के लिए भी कोई भी ओर स्थान उपलब्ध नहीं है। तथा यह सेक्टर विभाजन सड़क वर्तमान संरेखण के उत्तर की ओर से लोक निर्माण (भवन तथा सड़कें) विभाग द्वारा पहले से ही विद्यमान 20 मीटर चौड़ी सड़क को मिलाते हुए दादूपुर नलवी नहर के रास्ता अधिकार में पुनः संरेखित की जा सकती है। इसलिए सिमित द्वारा यह निर्णय लिया गया है कि 45 मीटर चौड़ी सेक्टर विभाजन सड़क विद्यमान लोक निर्माण (भवन तथा सड़कें) विभाग सड़क को शामिल करते हुए दादूपुर नलवी नहर के रास्ता अधिकार में प्रस्तावित की जा सकती है। क्योंकि सभी सेक्टर विभाजन सड़कें 45 मीटर चौड़ी प्रस्तावित की जा रही हैं।

चूंकि, यमुनानगर जगाधरी के लिए प्रारूप विकास योजना 2031 ईस्वी के सुझाव/टिप्पणी जिला योजना सिमति (संविधान के अनुच्छेद य घ के अधीन यथा अनिवार्य हिरयाणा जिला योजना सिमति गठन नियम, 1997 के नियम 3 के साथ पिठत हिरयाणा नगरपालिका अधिनियम, 1973 (1973 का 24) की धारा 203 ख की उप—धारा (1) के अधीन गठित) के समक्ष 13 अगस्त, 2019 को आयोजित इसकी बैठक में रखी गई थी। जिला योजना सिमति के सभी सदस्यों ने जिला स्तरीय सिमति द्वारा सुझाई गई सिफारिशों पर सहमित दे दी थी तथा यमुनानगर—जगाधरी के लिए प्रारूप विकास योजना 2041 ईस्वी के प्रस्ताव को राज्य स्तरीय सिमति से इसकी स्वीकृति के लिए मंजूरी दे दी।

तथा चूंकि, जिला योजना समिति/जिला स्तरीय समिति के सभी सुझावों को योजना में शामिल कर लिया गया था तथा इसे दिनांक 3 सितम्बर, 2019 को आयोजित बैठक में माननीय मुख्य मन्त्री, हरियाणा की अध्यक्षता में जिला स्तरीय समिति के समक्ष रखा गया था। समिति ने जिला योजना समिति/जिला स्तरीय समिति के सभी सुझावों को स्वीकार कर लिया तथा निम्नलिखित के लिए स्वीकृति दी:—

- (i) प्रारूप विकास योजना 2031 ईस्वी के बजाए 2041 ईस्वी के लिए तैयार करें;
- (ii) औद्योगिक क्षेत्र बढ़ाएं (1808 हैक्टेयर औद्योगिक क्षेत्र के रूप में राष्ट्रीय राजमार्ग–907 के साथ 6 नए औद्योगिक सेक्टरों तथा राष्ट्रीय राजमार्ग–344 के साथ 9 नए औद्योगिक सेक्टरों के रूप में जोड़े)
- (iii) नए औद्योगिक सेक्टरों के बनने के कारण परिवहन तथा संचार जोन के लिए एक नया सेक्टर प्रस्तावित है।
- (iv) 5−10 एकड़ के साथ "इंटीग्रटिड वे साईड एमेनिटी हब" के लिए राजमार्गों ⁄ मुख्य सड़कों के साथ − साथ प्रावधान करना।
- (v) पश्चिमी यमुना नहर के साथ-साथ दोनों ओर 30 मीटर हरित पट्टी।
- (vi) दादूपर नलवी नहर के साथ—साथ 30 मीटर चौड़ी सड़क, 45 मीटर चौड़ाई सिहत दादूपुर नलवी के रास्ता अधिकार में स्थानांतिरत की जानी है।
- (vii) समर्पित-पूर्वी भाड़ा गलियारा शामिल किया जाना।
- (viii) वर्ष 2041 के लिए जनसंख्या को 15,24,200 व्यक्तियों तक पुनः अनुमानित किया गया है।
- (ix) गाँव बुरिया के ईर्द–गिर्द के क्षेत्र को नियन्त्रित क्षेत्र घोषित करने उपरांत विकास योजना में शामिल करना।

तथा चूंकि, राज्य स्तरीय समिति द्वारा लिये गये निर्णयों की अनुपालना उपरांत उन्हें यमुनानगर—जगाधरी की प्रारूप विकास योजना—2041 ईस्वी में शामिल कर दिया गया है;

इसलिए, अब हरियाणा नगर निगम अधिनियम, 1994 (1994 का 16) की धारा 346 की उप—धारा (5) तथा पंजाब अनुसूचित सड़क तथा नियन्त्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का अधिनियम 41) की धारा 5 की उप—धारा (4) द्वारा प्रदत्त शिक्तयों का प्रयोग करते हुए, हरियाणा के राज्यपाल, इसके द्वारा अनुबन्ध 'ख' में विनिर्दिष्ट नियन्त्रित क्षेत्रों को लागू किए जाने के लिए प्रस्तावित तथा अनुबन्ध— क

तथा ख में दिए गए निर्बन्धनों तथा शर्तों सहित यमुनानगर—जगाधरी के लिए प्रारूप विकास योजना—2041 ईस्वी को प्रकाशित करते हैं।

इसके द्वारा यह नोटिस दिया जाता है कि इस अधिसूचना के राजपत्र में प्रकाशन की तिथि से तीस दिन की अविध की समाप्ति अथवा इसके पश्चात् सरकार, प्रारूप विकास योजना पर ऐसे आक्षेपों अथवा सुझावों सिहत, यदि कोई हो, जो निदेशक, शहरी स्थानीय निकाय विभाग, हरियाणा बेज़ संख्या 11–14, सेक्टर–4 पंचकूला (नगरनिगम की सीमा के भीतर आने वाले क्षेत्र के लिए) तथा निदेशक, नगर तथा ग्राम आयोजना विभाग, हरियाणा, द्वितीय तल, ब्लॉक ए, नगर योजना भवन, प्लॉट संख्या—3, सेक्टर—18 ए, मध्य मार्ग, चण्डीगढ़ (नगर निगम की सीमा से बाहर आने वाले क्षेत्र के लिए) द्वारा इस योजना के संबंध में लिखित रूप में किसी व्यक्ति से इस प्रकार विनिर्दिष्ट अविध की समाप्ति से पूर्व प्राप्त किये जाएं, पर विचार करेगी।

ड्राईंग

- 1. विद्यमान भूमि उपयोग ड्राईंग संख्या डी.टी.पी.(ए) 1172/65, पंजाब सरकार राजपत्र (असाधारण), दिनांक 22 मार्च, 1966 को पंजाब सरकार, अधिसूचना संख्या 3827—2टी.सी.पी. 65/4550, दिनांक 31 जनवरी, 1966 द्वारा पहले से ही प्रकाशित।
- 2. विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डी.टी.पी.(वाई)97/98, दिनांक 27 जुलाई, 1998, (25 जनवरी, 2005 को हिरयाणा सरकार राजपत्र अधिसूचना संख्या सी.सी.पी. (एन.सी.आर.)/वाई.सी.ए.—I/2005/36, दिनांक 14 जनवरी, 2005, द्वारा पहले से ही प्रकाशित)।
- 3. विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डी.टी.पी. (वाई.)२७०/२०१०, दिनांक १७ सितम्बर, २०१०।
- 4. विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डी.टी.पी.(वाई)85/2020, दिनांक 23 जुलाई, 2020
- 5. यमुनानगर जगाधरी के लिए प्रारूप विकास योजना—2041 ईस्वी, ड्राईंग संख्या डी.टी.पी.(वाई.)86 / 2020, दिनांक 23 जुलाई, 2020 I

अनुबन्ध-क

नियंत्रित क्षेत्र तथा अतिरिक्त नियंत्रित क्षेत्रों के लिए प्रारूप विकास योजना 2041 ईस्वी यमुनानगर—जगाधरी पर व्याख्यात्मक टिप्पण

I. ऐतिहासिक पृष्ठभूमि :

यमुनानगर, फरीदाबाद के बाद हरियाणा का दूसरा बड़ा शहरी केन्द्र है। 1991 की जनगणना के अनुसार इसे एक शहरी समूह (यू.ए.) के रूप में माना गया है जिसमेंतीन भिन्न शहरी बस्तियां अर्थात् जगाधरी, जगाधरी वर्कशाप और यमुनानगर शामिल है। शहर प्लाईवुड इकाईयों, कागज उद्योगों के कलस्टर के रूप में जाना जाता है तथा बड़े उद्योगों को उत्कृष्ट लकड़ी उपलब्ध करवाने के लिए भी जाना जाता है। जगाधरी एक महत्वपूर्ण ऐतिहासिक शहर है तथा इसका पुराना नाम गंगाधरी था। यद्यपि, नादिरशाह ने इस शहर को पूर्णतः नष्ट कर दिया था, परन्तु सिक्ख काल में यह बुड़िया के राय सिंह के द्वारा जीत लिया गया और 1873 में दोबारा निर्मित किया गया था, यह सहज प्रतीकात्मक रूप से विकसित होने वाला संकुचित, तंग गलियों तथा उप—गलियों वाला शहर है। इस शहर की नगरपालिका समिति वर्ष 1882 में स्थापित की गई थी। यह शहर पीतल/तांबा तथा स्टील के बर्तनों के लिये प्रसिद्ध है।

जगाधरी वर्कशाप मुख्यतः रेलगाडी तथा मालगाडी के डिब्बों की मरम्मत करने के लिये प्रादेशिक स्तर की रेलवे वर्कशाप है। यमुनानगर इस शहरी संकुलन का तीसरा शहर है, जो कि वर्ष 1942 में इसके तातकालिक नाम अब्दुल्लापुर के रूप में अधिसूचित क्षेत्र समिति स्थापित होने पर अस्तित्व में आया। इस शहर को वर्ष 1947 में यमुनानगर के रूप में पुनः नाम दिया गया था। विभाजन के बाद, इसकी जनसंख्या बड़ी तेजी से बढ़ी। आज यह राज्य के प्रमुख औद्योगिक शहरों में से एक है। यमुनानगर जिला प्रथम नवम्बर, 1989 को अस्तित्व में आया तथा इसका क्षेत्रफल 1756 वर्ग किलोमीटर है। इसकी चार तहसील है अर्थात जगाधरी, छछरौली, बिलासपुर, रादौर तथा तीन उप–तहसील अर्थात् सढौरा, सरस्वती नगर (मुस्तफाबाद) तथ प्रताप नगर (खिजराबाद)। इसके अतिरिक्त, आदि बद्री नारायण, श्री केदारनाथ तथा मंत्रा देवी मन्दिर उत्तर की ओर यमुनानगर से 40 किलोमीटर की दूरी पर स्थित हैं तथा यह प्राकृतिक सौन्दर्य तथा शांति के साथ बहुत ही प्रकृति मनोहर से परिपूर्ण है। प्राचीन काल के तीन टीले भारतीय पुरातत्त्व सर्वेक्षण द्वारा हाल में ही खोदे गए हैं तथा इसके साथ-साथ यह कहा जाता है कि हिन्दु पौराणिक कथाओं के अनुसार सरस्वती नदी का उद्गम स्थल यही है। इसके अलावा, पवित्र स्थान 'कपाल मोचन' भी यम्नानगर तथा जगाधरी शहर के उत्तर में इसकी सीमा से 24 किलोमीटर की दूरी पर स्थित है। यह कहा जाता है कि पन्द्रहवीं तथा सतरहवीं शताब्दी में पहले सिक्ख गुरू नानक देव जी तथा दसवें गुरू गोबिन्द सिंह जी हरिद्वार की अपनी तीर्थ यात्रा के दौरान इस स्थान पर आए थे तथा विश्राम किया था। दोनों गुरूओं ने आस–पास के क्षेत्र में लोगों को सन्मार्ग पर लाने तथा सामाजिक बुराईयों से दूर रहने का संदेश दिया तथा इस प्रकार, कपाल मोचन में पवित्र कुण्डों (तालाब) अर्थात् रिन मोचन, कपाल मोचन तथा सूर्य कुण्ड सहित हिन्दु तथा सिक्ख धर्म के कई धार्मिक भवन हैं। विभिन्न राज्यों जैसे पंजाब, हरियाणा, हिमाचल प्रदेश, उत्तराखण्ड तथा उत्तर प्रदेश के लोग पवित्र स्थान पर आते हैं तथा अपने पापों से मुक्ति के लिए अपने आप को ईश्वर को सौंपते हुए इन कुन्डों में डुबकी लगाते है।

इस स्थान की महिमा को ध्यान में रखते हुए, स्थानीय प्रशासन पिछले कुछ दशकों से आगन्तुकों के लिए कार्तिक पूर्णिमा की पूर्व संध्या पर नवम्बर के महीने में मेले/प्रदर्शनी की व्यवस्था करता रहा है।

II. अवस्थिति तथा क्षेत्रीय परिवेश:

शहरी केन्द्र 300 7' से 300 12' उत्तरी आक्षांश तथा 770 15' से 770 18' पूर्वी देशान्तर पर समुद्र तल से 278 मीटर की औसत ऊँचाई पर अम्बाला—सहारनपुर सड़क पर स्थित है।शहरी केन्द्र उत्तर में हिमाचल प्रदेश और पूर्व मेंउत्तर प्रदेश के लिये मुख्य द्वार के रूप में काम करता है। यह इसके आसपास के प्रदेशों से राष्ट्रीय राजमार्ग तथा राज्य राजमार्गों के तन्त्र के माध्यम से जुड़ा हुआ है अर्थात् पंचकूला—साहा—यमुनानगर—सहारनपुर सड़क (राष्ट्रीय राजमार्ग संख्या 344), जगाधरी—छछरौली—पाँवटा साहिब सड़क (राष्ट्रीय राजमार्ग 907) यमुनानगर—लाडवा—पीपली—कुरूक्षेत्र सड़क (राज्य राजमार्ग 6ए), जगाधरी—बिलासपुर, सढौरा, नारायणगढ़, बरवाला सड़क(राज्य राजमार्ग 1) इस शहर से गुजर रहे हैं। दूसरी ओर, दो राष्ट्रीय राजमार्ग तथा दो राज्य राजमार्ग जुड़वा शहरों से गुजरते हैं।ये इस शहरों केन्द्र को राष्ट्रीय राजधानी जो कि लगभग 205 किलोमीटर दूर है तथा राज्य की राजधानी से जो लगभग 112 किलोमीटर दूर है, से जोड़ते है और आसपास के महत्वपूर्ण शहरों अर्थात् अम्बाला, पंचकूला, पाँवटा साहिब, कुरूक्षेत्र, सहारनपुर आदि से भी जोड़ते है। इसके अतिरिक्त, अम्बाला—सहारनपुर रेलवे लाईन यमुनानगर के दक्षिण की तरफ से गुजरती है जोकि जुड़वां शहरों को आसपास के क्षेत्र के अन्य सभी मुख्य शहरों से जोड़ने वाला एक महत्वपूर्ण संपर्क है।सड़कों का यह जाल इस शहर की भौतिक स्थिति के प्रतिकूल होने के बावजूद भी इसकी औद्योगिक प्रगति में सहायक है। इसके अलावा, यह शहर अपनी पृष्टभूमि के साथ—साथ घने जंगल/वनस्पति से मली—भांति जुड़ा हुआ है। जिले में भूमिगत जल आमतौर पर ताजा तथा घरेलू तथा सिंचाई प्रयोजनों के लिए उपयुक्त है।

III. भौगोलिक स्थिति :-

यमुनानगर—जगाधरी के पूर्व में पश्चिमी यमुना नहर और स्वयं यमुना नदी है। नहर शहर को यमुना नदी से आने वाली बाढ़ के प्रकोप से सुरक्षा का काम करती है। नगर की सामान्य स्थलाकृति उत्तर—पूर्व से दक्षिण—पश्चिम की ओर हलके से ढलान के साथ समतल है। यहाँ का उप—सतही जल स्तर औसतन 12 मीटर है जिसकी पोटैंशियल ऑफ हाईड्रोजन गुणवत्ता 6.5 से 7 तक की श्रेणी की है जो कि फसलों तथा पीने के प्रयोजनों के लिये उच्च गुणों वाला माना गया है। मिट्टी की बनावट रेतीली दोमट है, जिसे फसलों के लिए अच्छी गुणवत्ता वाली मिट्टी माना गया है।यहाँ औसतन वर्षा 1105 मिलीमीटर होती है। शहर का इतिहास लगभग बाढ़ मुक्त है। जिले में उत्तर और उत्तर पूर्व में शिवालिक पहाड़ियों और तलकृती का रोलिंग मैदान है और पूर्व तथा दक्षिण पूर्व में यमुना नदी के साथ बाढ़ का मैदान है। जिले की मुख्य नदियाँ/जल धाराएँ यमुना, सरस्वती, चौतंग, रक्शी, सोम्ब, बोली इत्यादि हैं।

IV. जनसांख्यिकी रूपरेखा :-

2011 की जनगणना के अनुसार नगर की जनसंख्या 4,78,574 व्यक्तियों की थी। पिछले दशकों में तीव्र शहरी विकास के कारण, दोनों नगरों तथा जगाधरी वर्कशाप एकीकृत हुए तथा बड़े शहर का आकार ले लिया है। 2011 की जनगणना के अनुसार यमुनानगर तथा जगाधरी को मिलाकर इस शहरी केन्द्र की कुल जनसंख्या 3,41,965 है। इस प्रकार 2011 की जनगणना के अनुसार इस शहरी संकुलन की वास्तविक जनसंख्या 4,78,574 व्यक्ति है। जनसंख्या की दशकीय वृद्धि निम्नानुसार है:

वर्ष	जनसंख्या	दशकीय वृद्धि दर (%)
1961	84,337	_
1971	1,15,020	36.38
1981	1,60,424	39.47
1991	2,58,500	61.13
2001	3,38,887	31.10
2011	4,78,574	41.22
2021*	6,81,875	42.48
2031*	9,84,997	44.45
2041*	15,24,200	54.74

स्रोतः भारत की जनगणना

^{*} अनुमानित जनसंख्या

उपरोक्त सारणी दर्शाती है कि दशक 1981—1991 के दौरान इसकी जनसंख्या में तीव्र वृद्धि हुई जब यह पिछले दशक के मुकाबले 61.13 प्रतिशत की उच्च वृद्धि दर दर्ज करते हुए 1981 में 1,60,424 से बढ़कर 1991 में 2,58,500 हो गई। यह उग्रवाद अवधि के दौरान पंजाब से लोगों के बड़ी संख्या में प्रवास का कारण हो सकता है। इसके पश्चात् वृद्धि दर में 41.22 प्रतिशत की मध्यम वृद्धि हुई है। हालांकि, जगाधरी में आदर्श औद्योगिक टॉउनशिप के विकास के सरकार के निर्णय को ध्यान में रखते हुए उच्च अनुमानित वृद्धि दर की कल्पना की गई है तथा जुड़वा शहरों यमुनानगर तथा जगाधरी को एक महत्वपूर्ण पर्यटन स्थल के रूप में विकसित करने के लिये प्रस्तावित किया गया है।

यमुनानगर—जगाधरी शहर के पिछले जनसंख्या रूझानों के अनुसार तथा शहर के इर्द—गिर्द संतुलित विकास को ध्यान में रखते हुए प्रारूप विकास योजना 2041 ईस्वी के लिये जनसंख्या के अनुमान हेतु ज्यामितीय आरोहण पद्धित सर्वथा उपयुक्त है। उसी क्रम में आवासीय वृद्धि के लिए 20 प्रतिशत घटक के प्रावधानों को विचार में रखते हुए विभाग के उच्च सघनता पॉलिसी प्रावधानों जैसे अफोर्डेबल ग्रुप हाऊसिंग, नई एकीकृत लाईसेंसिंग पॉलिसी, दीन दयाल जन आवास योजना, हिरयाणा भवन संहिता,2017 इत्यादि भी जोड़ी गई है। इसके अनुसार कुल अनुमानित जनसंख्या प्रक्षेपण वर्ष 2041 ईस्वी के लिए लगभग 15,24,200 व्यक्ति होगी।

V. आर्थिक विशेषताएँ :

यमनानगर—जगाधरी एक अहम निवेश स्थान है तथा इसमें कौशल विकास के साथ संतलित क्षेत्रीय तथा धारणीय विकास, नवीनता तथा प्रौद्योगिकी को अपनाने की क्षमता है तथा जिले में रोजगार के अवसर पैदा कर सकता है। मैटल युटेनसल कलस्टर, जगाधरी तथा प्लाईवुड कलस्टर, यमुनानगर जिले में दो मुख्य अग्रणी पारम्परिक बाजार हैं जिसमें लघु तथा मध्यम स्तर की इकाईयां हैं तथा ये कलस्टर उपयुक्त भूमि के उपलब्ध न होने के कारण विस्तार नहीं कर सकें तथा वृद्धि के नए स्तर को प्राप्त करने में समर्थ नहीं हुए है। जगाधरी उपजाऊ कृषि की पृष्टभूमि में स्थित होने के कारण आस–पास के क्षेत्रों के लिये मुख्यतः व्यापारिक नगर तथा खुदरा सेवा केन्द्र के रूप में सेवा देता है। सेवाएँ अनाज़ के लिये बाजार तथा क्षेत्र के अन्य कृषि उत्पाद, कृषि उपकरणों के लिये खुदरा बाजार, घरेलू उपभोक्ता वस्तुएँ तथा कृषि औजारों की मरम्मत के लिये बाजार उपलब्ध करवाती है। विनिर्माण तथा औद्योगिक प्रसंस्करण यमुनानगर शहर में मुख्य आर्थिक गतिविधियाँ हैं। जगाधरी वर्कशाप क्षेत्र का भी संपूर्ण शहरी केन्द्र के आर्थिक आधार में अपना योगदान है। नौ बड़े पैमाने की औद्योगिक इकाईयों में से तीन को इस शहरी केन्द्र की अर्थव्यवस्था में विशेष वर्णन की आवश्यकता है अर्थात् बलारपुर पेपर मिल, हरियाणा डिस्टल्री तथा सरस्वती चीनी मिल। इसके अतिरिक्त, ऑटो स्पेयर के सहायक उद्योगों शूगर मिलों के लिए भारी मशीनरी तथा औद्योगिक क्षेत्र तथा संपदा में लघु इकाईयों का इन शहरों की अर्थव्यवस्था में मुख्य योगदान है जो आसपास के क्षेत्र के कुशल/अकुशल कामगारों को रोजगार उपलब्ध करवाते हैं। औद्योगिक गतिविधियों ने पिछले दो दशकों के दौरान तेज गति पकड़ी है। धातु तथा प्लाईवुड उत्पाद अग्रणी उद्योग है जो लघु तथा मध्यम पैमाने की इकाइयों के रूप में इकट्ठे हुए हैं जबकि पेपर, चीनी, एल्कोहल, स्टार्च, विशेष इंजीनियरिंग उत्पाद तथा ऑटो स्प्रिंगस शहर में फल-फुल रहे बर्ड पैमाने के उद्योगों के मुख्य उत्पाद हैं।

जनगणना 2011 के अनुसार, कुल श्रमिकों की संख्या 1,13,762 थी, जो कुल जनसंख्या का 33.26 प्रतिशत है। अर्थव्यवस्था के प्राथमिक, द्वितीय तथा तृतीयक क्षेत्र में कार्यरत श्रमिक कमशः 104899, 8863 तथा 228203 है जोकि कुल श्रमिकों काक्रमशः 30.7 प्रतिशत, 2.59 प्रतिशत तथा 66.73 प्रतिशत दर्शाता है। उपलब्ध जनगणना दशक 2001—2011 प्रदर्शित करती है कि श्रमिक शहर की अर्थव्यवस्था की कुल जनसंख्या का 30 प्रतिशत है अर्थात, जो पूर्व दशक में बढ़कर 60 प्रतिशत तक है।

VI. भूमि उपयोग प्रस्ताव :-

प्रारूप विकास योजना का मुख्य उद्देश्य जुड़वा शहरों का एकल इकाई तथा राज्य के प्रमुख पर्यटन केन्द्र तथा औधोगिक केन्द्र के रूप में विकसित करना है। 2041 इस्वी तक शहरी जनसंख्या 15,24,200 के लगभग होगी। जनगणना 2011 के अनुसार, इसकी जनसंख्या 4,78,574 थी। अतः विकास योजना 2041 ए.डी.में 10,45,626 अतिरिक्त जनसंख्या को समायोजित करने का प्रस्ताव है। अतिरिक्त आबादी को समायोजित करने हेतु शहरीकरण के लिए 12327.52 हेक्टेयर भूमि प्रस्तावित है। गांवों और विद्यमान शहरों का अनुमानतः क्षेत्रफल 2460.57 हेक्टेयर है, जिसमें लगभग 4,78,574 व्यक्तियों की जनसंख्या समायोजित है। इसलिए योजना में 2041 तक लगभग 15,24,200 व्यक्तियों को सकल घनत्व 124 व्यक्ति प्रति हैक्टेयर और शुद्ध क्षेत्र घनत्व 300 व्यक्ति प्रति हेक्टेयर की दर से समायोजित करने का प्रस्ताव है। प्रस्तावित भूमि उपयोग नीचे दिए अनुसार है:

क्रम संख्या	भूमि उपयोग	नगरपालिका सीमा के भीतर का क्षेत्र (हेक्टेयर)	नियंत्रित क्षेत्र के भीतर क्षेत्र (हेक्टेयर)	कुल क्षेत्र (हेक्टेयर)	कुल क्षेत्र की प्रतिशतता
1	आवासी	3402.20	83.11	3485.31	35.32
2	वणिज्यिक	372.35	0.00	372.35	3.77
3	औद्योगिक	1524.30	1353.88	2878.18	29.17
4	परिवहन तथा संचार	952.82	463.56	1416.38	14.35
	सड़के				

5	सार्वजनिक उपयोगिताएं	146.99	35.51	182.50	1.85
6	सार्वजनिक तथा अर्ध सार्वजनिक	234.81	80.65	315.46	3.20
7	खुले स्थान	812.01	388.61	1200.62	12.17
8	विशेष अंचल	0.00	16.16	16.16	0.16
	कुल	7445.48	2421.48	9866.96	100.00

टिप्पण.— कुल शहरीकरण योग्य भूमि 12327.53 हेक्टेयर है, जिसमें यमुनानगर, जगाधरी, जगाधरी वर्कशाप का विद्यमान क्षेत्र तथा विद्यमान गांवों (2460.57 हेक्टेयर) उपरोक्त में शामिल नहीं किया गया है

विभिन्न भूमि उपयोगों का विवरण :

1. आवासीय :

यमुनानगर तथा जगाधरी का प्रारूप विकास योजना 2041 इस्वी 15,24,200 व्यक्तियों की प्रक्षेपित जनसंख्या के लिए प्रस्तावित किया गया है। इस समय जगाधरी, यमुनानगर और जगाधरी वर्कशाप के विद्यमान कस्बों में लगभग 4,78,574 व्यक्तियों की जनसंख्या समायोजित है। शेष 10,45,626 व्यक्तियों को समायोजित करने के लिए 3485.31 हेक्टेयर का क्षेत्र 300 व्यक्ति प्रति हेक्टेयर के आवासीय घनत्व सहित आवासीय सैक्टर के लिए प्रस्तावित किया गया है। शेष सम्भावित जनसंख्या आवासीय सेक्टरों अर्थात 1 (भाग), 2 (भाग), 4, 5, 6(भाग), 10, 12 (भाग), 12ए, 13 (भाग), 14, 15, 16 (भाग), 16ए, 17 (भाग), 17ए, 18 (भाग), 18ए (भाग), 20 (भाग), 21, 22 (भाग), 23 (भाग), 24, 25 (भाग), 26, 27, 28 (भाग), 29, 33, 34, 35 (भाग), 39, 40 (भाग), तथा 41 (भाग) को आवासीय प्रयोजन के लिए निर्दिष्ट किया गया हैं।

घनत्ववृद्धि के प्रस्ताव के अलावा, विकास योजना में निम्नलिखित प्रावधान भी किये गये है :-

- (क) अतिरिक्त आबादी की आवश्यकता को पूरा करने के लिए पहले से ही योजनाबद्ध / विकसित आवासीय क्षेत्रों में अवसंरचना के लिए अतिरिक्त क्षेत्र उपलब्ध करवाया जाएगा।
- (ख) आवासीय कालोनी / सेक्टर में सड़कों की न्यूनतम चौड़ाई 12 मीटर से कम नहीं होगी या लागू नीति के अनुसार होगी।
- (ग) आवासीय कालोनी / सेक्टरों में पार्कों / खुले स्थानों के लिए न्यूनतम क्षेत्र ऐसी रीति में योजनाबद्ध किया जाएगा कि यह प्रति व्यक्ति 2.5 वर्गमीटर के न्यूनतम मानदण्डों को पूरा करेगा।

प्रत्येक आवासीय सेक्टर, क्षेत्र दोनों तरफ 20 प्रतिशत की भिन्नता सहित ड्राईंग में दर्शाई गई सेक्टर सघनता तथा इसके अतिरिक्त नई एकीकृत लाइसेंसिंग पालिसी, अफोर्डेबल ग्रुप हाउसिंग पॉलिसी, दीन दयाल जन आवास योजना पॉलिसी में यथा विहित सेक्टर सघनता में विकसित किया जाएगा। 20 प्रतिशत ग्रुप हाउसिंग काम्पोनैन्ट पॉलिसी आवासीय सैक्टर में भी लागू होगी।

2. वाणिज्यिक :

वर्तमान कस्बें में, वाणिज्यिक क्रिया कलाप शहर की मुख्य सड़कों के साथ बाजार के रूप में अवस्थित है । तथापि, जगाधरी, यमुनानगर और जगाधरी वर्कशाप की वाणिज्यिक जरूरतों को पूरा करने के लिए 372.35 हेक्टेयर भूमि सैक्टर 3 (भाग), 9, 18 (भाग), 19, 24ए तथा 42 में वाणिज्यिक उपयोग के लिए आबंटित की गई है। इसके अतिरिक्त, 150 मीटर चौडी वाणिज्यिक पट्टी सेक्टर 12 (भाग), 13 (भाग), तथा 20 (भाग) की विभाजक सड़कपर प्रस्तावित है, जो इस मुख्य सड़क से सम्भावित लाभ के लिए वाणिज्यिक स्थानों का एक रूप तथा युक्तियुक्त आबन्टन करेगा। आवासीय क्षेत्र में निवास के लिए दिन प्रति दिन खरीदारी केन्द्र के रूप में प्रयीप्त प्रावधान होगा। सेक्टर 19 में सिटी सेंटर के रूप में 82.98 हेक्टेयर का क्षेत्र आरक्षित है।

वर्तमान अनाज मण्डी आवासीय सेक्टर—18 में दोनों कस्बों के बीच मे अवस्थित है जोिक जगाधरी—यमुनानगर मुख्य मार्ग पर सेक्टर 17 में स्थित लघु सचिवालय तथा न्यायिक परिसर के सामने है।इसलिए अनाज मण्डी को सेक्टर—9 में स्थानांतरित करने का प्रस्ताव है जोिक शहरी योजना की बाह्य सीमा पर है। उसके पश्चात् वर्तमान अनाज मण्डी के अधीन भूमि किसी अन्य संगत उपयोग में लाई जा सकेगी। यहाँ इमारती लकड़ी की बाजार में भारी मांग है और यह राष्ट्रीय राजमार्ग 907 पर 70.86 हेक्टेयर क्षेत्र के साथ सेक्टर—42 को प्रस्तावित करते हुए समायोजित की गई है।

3. औद्योगिक :

सामान्य औद्योगिक शहर होने के कारण तथा औद्योगिक विकास को मजबूत करने के लिए तथा यमुनानगर में औद्योगिक विकास के लिए प्लाटों/भूमि की दिन प्रति दिन मांग बढ़ रही है। भविष्य में औद्योगिक जरूरतों को पुरा करने के लिए 2878.18 हेक्टेयर का क्षेत्र सेक्टर 3 (भाग), 3ए (भाग), 7, 30, 30ए, 31, 32, 40 (भाग), 41 (भाग), 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 56, 57, 58 तथा 59 में औद्योगिक उपयोग के लिए आवंटित किया गया है । ये सेक्टर 2(ड़ी) सेक्टर सड़क तथा यमुनानगर—सहारनपुर सड़क (राष्ट्रीय राजमार्ग 344) तथा उत्तर—पूर्व तथा दक्षिण दिशा में जगाधरी—छछरौली सड़क (राष्ट्रीय राजमार्ग 907) के बीच में प्रस्तावित किया गया है।

हरियाणा राज्य औद्योगिक तथा अवसंरचना विकास निगम ने 54 हेक्टेयर के क्षेत्र में जगाधरी— पांवटा साहिब सड़क (राष्ट्रीय राजमार्ग 907) पर नियंत्रित क्षेत्र में मानकपुर में केवल एक औद्योगिक सन्पदा स्थापित की है। योजना में राष्ट्रीय राजमार्ग— 907 (जगाधरी, पांवटा साहिब सड़क) के साथ मानकपुर में वर्तमान हरियाणा राज्य औद्योगिक तथा अवसंरचना विकास निगमकी औद्योगिक सम्पदा के नजदीक तथा दक्षिण क्षेत्र सड़क वी—2 (ड्री) तथा वर्तमान बाह्य परिधीय सड़क अर्थात राष्ट्रीय राजमार्ग—344 तथा राज्य राजमार्ग—6ए शामिल है पर नया औद्योगिक क्षेत्र शामिल किया गया है।

4. परिवहन तथा संचार :

इस विकास योजना में, परिवहन तथा संचार के उपयोग के लिए 1416.38 हेक्टेयर का क्षेत्र प्रस्तावित किया गया है। परिवहन नगर तथा परिवहन डिपो सेक्टर 8 (भाग), 10 (भाग), 11 (भाग), 18ए (भाग), सेक्टर 35 (भाग) में पुरानी सहारनपुर सड़क पर तथा सेक्टर 43 में जगाधरी—छछरौली सड़क (राष्ट्रीय राजमार्ग 907) पर गांव मुकारिबपुर के निकट प्रस्तावित किये गये हैं तथा यमुनानगर तथा जगाधरी कस्बे के लिए गांव पान्जूपुर के नजदीक सेक्टर 55 में वी. 2 (सी) सेक्टर सड़क तथा वी 2 (ए) यमुनानगर सहारनपुर सड़क (राष्ट्रीय राजमार्ग 344) के बीच में भी परिवहन तथा संचार क्षेत्र के लिए स्थल निर्दिष्ट किया गया है।इसके अतिरिक्त, नीति दिनांक 25 जनवरी, 2019 के अनुसार, परिवहन तथा संचार अंचल के अधिकतम 20 प्रतिशत क्षेत्र में वेयरहाउस की स्थापना का प्रावधान रखा गया है।

प्रस्तावित परिवहन नेटवर्क पदानुक्रम में राष्ट्रीय राजमार्ग, अनुसूचित सड़कें (वी–2, वी–2ए तथा वी–4, परिधि सड़कें (वी–1, वी–2 तथा वी–2 बी), हरित पट्टी सिहत सेक्टर सड़कें (वी–2, वी–2 (बी), वी–2 (सी) तथा वी–3, वी–4 तथा वी–4 (सी) तथा अन्य सेक्टर सड़कें(वी–2 (बी), वी–3 तथा वी–4 (ए) तथा वी–4 (सी) तथा वर्तमान चौड़ाई सिहत सड़केंवी–2 (बी), वी–3 तथा वी–4 (बी) शामिल है।

4.1 परिवहन नेटवर्क:

इस शहरी संकुलन की वर्तमान शहरी सड़क प्रणाली, अड़चन पैदा करने वाली है तथा इसमें दुर्घटनाएं होने की संभावना रहती है। अंतर शहरी और अंतः शहरी यातायात की सुरक्षा और सुगमता को सुनिश्चित करने के लिए योजना में निम्नलिखित उपबन्ध किये गये हैं:

(क) राष्ट्रीय राजमार्गः

शहर में भीड़माड़ से बचने और यातायात को बढ़ाने के लिए,राष्ट्रीय राजमार्ग प्राधिकरण द्वारा एक नया राजमार्ग अर्थात् राष्ट्रीय राजमार्ग—344 (पूर्व में एन एच 73) बनाया गया है जिसकी चौड़ाई 60 मीटर है तथा इसके दोनों ओर 30 मीटर चौड़ी हरित पट्टी है जिसे वी—2 के रूप में वर्गीकृत किया गया है।यह नया राजमार्ग अब राष्ट्रीय राजमार्ग 344 है जो सहारनपुर—यमुनानगर—जगाधरी—अम्बाला सड़क को ग्राम बम्मोतली तथा कैल के जंक्शन के पास जोड़ता है। शहर के प्रवेश और निकास बिन्दु पर राष्ट्रीय राजमार्ग 344 पर दो कलोवरलीव का प्रावधान किया गया है। उनमें से एक अम्बाला—जगाधरी सड़क के पास गांव कैल तथा बम्मोरी जंक्शन के नजदीक है तथा दूसरा यमुनानगर—सहारनपुर सड़क (राष्ट्रीय राजमार्ग 344) पर गांव कलानौर के नजदीक है। सड़क वी—2(ए) के रूप में नये वर्गीकरण को शहरीकरण के लिए प्रस्तावित क्षेत्र में राष्ट्रीय राजमार्ग 344 के साथ—साथ नये प्रस्तावित औद्योगिक सैक्टरों अर्थात् सेक्टर 50 से 56, सैक्टर 58 तथा 59 के बीच प्रस्तावित किया गया है, जिसके उत्तर दिशा में 60 मीटर चौड़ी हरित पट्टी है तथा दक्षिण दिशा में 30 मीटर चौड़ी हरित पट्टी प्रस्तावित है। राष्ट्रीय राजमार्ग 907 (जगाधरी—छछरौली—पांवटा साहिब सड़क) को वी—2 के रूप मे वर्गीकृत किया गया है जो 60 मीटर चौड़ी है तथा दोनों तरफ 30 मीटर चौड़ी हरित पट्टी है तथा विकास योजना के शहरीकरण योग्य क्षेत्र से गुजरती है तथा आगे यह पांवटा साहिब को जोड़ती है।

(ख) राज्य राजमार्ग

विकास योजनामें दो राज्य राजमार्ग हैं अर्थात् राज्य राजमार्ग–1 तथा राज्य राजमार्ग–6(ए), जोकि 30 मीटर चौड़ी वी–4 सड़क के रूप में वर्गीकृत किये गये है जिनके दोनों तरफ 30 मीटर चौड़ी हरित पट्टी प्रस्तावित है। राज्य राजमार्ग–1 जगाधरी और बिलासपुर को जोड़ता है तथा राज्य राजमार्ग–6ए यमुनानगर और रादौर को जोड़ता है।

(ग) परिधि सड़कें :

शहरी क्षेत्र के चारों और सड़कों के वर्गीकरण के लिए विकास योजना में परिधि सड़क प्रस्तावित की गई है। पश्चिमी परिधि सड़क, जो वी—2 (बी) के रूप में वर्गीकृत की गई है की चौड़ाई 60 मीटर है जो सेक्टर 9 (गांव जामपुर) सड़क से शुरू होकर सेक्टर 12 (गांव रतोली) तक है।आगे वही सड़क वी—1 अर्थात् 75 मीटर चौड़ी उत्तरी परिधि सड़क के रूप में वर्गीकृत की गई है, जिसके दोनों ओर 50

मीटर चौड़ी हिरत पट्टी है जो सेक्टर 13 (गांव रतोली) से शुरू होकर सेक्टर 33 (गांव नाम) तक शहरी क्षेत्र में आती है। इसके पश्चात्, यह सड़क आगे पूर्वी परिधि सड़क (वी-2) के रूप में वर्गीकृत की गई है जहाँ इसकी चौड़ाई 60 मीटर है तथा इसके दोनों ओर 30 मीटर चौड़ी हिरत पट्टी है और यह कृषि क्षेत्र में आती है, जो गांव कलानौर के नजदीक राष्ट्रीय राजमार्ग 344 को जोड़ती है। एक अतिरिक्त परिधि सड़क (वी-2) के रूप में अतिरिक्त संपर्क हेतु भी प्रस्तावित की गई है जोकि 60 मीटर चौड़ी हैतथा जिसके दोनों तरफ 30 मीटर चौड़ी हिरत पट्टी प्रस्तावित है, जो गांव कैल के नजदीक राष्ट्रीय राजमार्ग 344 को तथा सेक्टर-25 (गांव जरोन्डी) के पास उत्तरी परिधि सड़क को जोड़ती है तथा कृषि अंचल में आती है। शहर के विभिन्न भागों से शुरू होने वाले यातायात जिसका गन्तवय शहर से बाहर है तथा यातायात जिसे शहर को पार करना है, प्रस्तावित परिधीय सड़क से गुजरेगा।

(घ) विद्यमान सड़क:

विद्यमान सड़कें, जो शहर को वर्तमान में अम्बाला, पंचकूला, नारायणगढ़, पांवटासाहिब, कुरूक्षेत्र तथा सहारनपुर से जोड़ती है,को उनकी विद्यमान चौड़ाई सिहत बरकरार रखा गया है। विद्यमान सड़कें वी—4 के रूप में वर्गीकृत की गई है। विद्यमान सड़क पुरानी अम्बाला—जगाधरी सड़क (पूर्व में राष्ट्रीय राजमार्ग—73) दोनों तरफ 30 मीटर चौड़ी हिरत पट्टी सिहत समायोजित की गई है जोिक राष्ट्रीय राजमार्ग 344 से शुरू होकर खेड़ा पावर हाउस के निकट उत्तरी परिधीय सड़क तक कृषि क्षेत्र से गुजरती है। आगे यह वी—4 (सी) के रूप में विस्तारित की गई है जोिक 30 मीटर चौड़ी तथा दोनों तरफ 60 मीटर चौड़ी हिरत पट्टी सिहत सेक्टर 20 तथा 22 के बीच में है।

(ड.) सेक्टर सड़क :--

पूरे शहरी क्षेत्र को सैक्टरों के रूप में अलग भूमि उपयोगों में विभाजित किया जाना प्रस्तावित है। प्रत्येक सैक्टर को कम से कम 45 मीटर चौड़ी सड़क से विभाजित किया जाना प्रस्तावित है, जिसे वी—3 सड़क के रूप में वर्गीकृत किया गया है। तथापि, सड़कों के साथ प्रस्तावित हरित पिट्टयों के कारण शहरी क्षेत्र में सड़कों को वी—2, वी—2 (बी) तथा वी 2 (सी) के रूप में वर्गीकृत किया गया है। पुरानी सहारनपुर सड़क, जो शहरीकरण योग्य क्षेत्र में सेक्टर 15, 39 तथा 38 से गुजरती है को वी—2 के रूप में वर्गीकृत किया गया है तथा इसके पश्चात्, यह पश्चिमी परिधीय सड़क गांव केत के पास मिलती है, जहां इसे वी—2 (बी) के रूप में वर्गीकृत किया गया है। विद्यमान सड़क, जो जगाधरी—बिलासपुर सड़क से गांव सरावन को जाती है, को भी सेक्टर सड़क (वी—3) के रूप में प्रस्तावित किया गया है।

संवर्द्धन नहर के दोनों ओर सेक्टर 4 तथा 5 के बीच से गुजरने वाली 30 मीटर चौड़ी सड़कों को वी–4 (बी) के रूप में वर्गीकृत किया गया है।

विकास योजनाओं में प्रस्तावित विभिन्न सड़कों की चौड़ाई/आरक्षण निम्नानुसार है :-

क्रम संख्या	वर्गीकरण	सड़क का नाम	आरक्षित भूमि
1	वी—1	शहरीकरण योग्य क्षेत्र के साथ उत्तरी परिधीय सड़क	दोनों तरफ 50 मीटर चौड़ी हरित पट्टी सहित 75 मीटर चौड़ी सड़क
2	वी—2	(i) अम्बाला—जगाधरी—यमुनानगर—सहारनपुर सड़क (राष्ट्रीय राजमार्ग 344) (ii) जगाधरी—छछरोली—पावंटासाहिब सड़क (राष्ट्रीय राजमार्ग 907) (iii) पूर्वी परिधीय सड़क (iv) अतिरिक्त परिधीय सड़क (v) सेक्टर विभाजक सड़क	दोनों तरफ 30 मीटर चौड़ी हरित पट्टी सहित 60 मीटर चौड़ी सड़क
3	वी—2 (ए)	अम्बाला— जगाधरी— यमुनानगर— सहारनपुर सड़क (राष्ट्रीय राजमार्ग 344)	उत्तर की ओर 60 मीटर चौडी हरित पट्टी तथा दक्षिण की ओर 30 मीटर चौड़ी हरित पट्टी सहित 60 मीटर चौड़ी सड़क ।
4	वी—2 (बी)	(i) पश्चिमी परिधीय सड़क (ii) सेक्टर विभाजक सड़क (iii) पुरानी सहारनपुर सड़क	60 मीटर चौड़ी सड़क

क्रम संख्या	वर्गीकरण	सड़क का नाम	आरक्षित भूमि
5	वी—2 (सी)	सेक्टर विभाजक सड़क	दक्षिण की ओर 30 मीटर चौड़ी हरित पट्टी सहित 60 मीटर चौड़ी सड़क
6	वी—3	सेक्टर विभाजक सड़क	45 मीटर चौड़ी सड़क
7	वी-4	(i) जगाधरी—बिलासपुर सड़क (राष्ट्रीय राजमार्ग—1) (ii) यमुनानगर—रादौर सड़क (राष्ट्रीय राजमार्ग—6ए) (iii) पुरानी अम्बाला—जगाधरी सड़क	दोनों ओर 30 मीटर चौड़ी हरित पट्टी सहित 30 मीटर चौड़ी सड़क
8	वी—4 (ए)	वर्तमान आन्तरिक सड़कें	विद्यमान चौड़ाई
9	वी—4 (बी)	संवर्धन नहर के साथ सड़क	30 मीटर चौड़ी सड़क
10	वी—4 (सी)	पुरानी अम्बाला जगाधरी सड़क	दोनो तरफ 60 मीटर चौड़ी हरित पट्टी सहित 30 मीटर चौड़ी सड़क

नये औद्योगिक सेक्टरों की प्रस्तावना के साथ सड़कों का नया वर्गीकरण (वी–2 (ए) तथा वी–2 (सी)) प्रस्तावित किया गया है। वी–2 (ए) श्रेणी की सड़क के लिए 60 मीटर भूमि आरक्षित है जिसके उत्तरी दिशा में 60 मीटर हरित पट्टी तथा दक्षिणी दिशा में 30 मीटर हरित पट्टी प्रस्तावित की गई है। यह श्रेणी मुख्य रूप से राष्ट्रीय राजमार्ग 344 के साथ (सेक्टर 50 से 56, 58 तथा 59) है। वी–2 (सी) श्रेणी की सड़क के लिए 60 मीटर भूमि आरक्षित है जिसके दक्षिण की ओर 30 मीटर चौड़ी हरित पट्टी (सेक्टर 3ए से 8) है। वी–3 (45 मीटर चौड़ी) सड़क दादुपुर नलवी नहर के अधिकार क्षेत्र में उत्तर की तरफ पी.डब्ल्यू.डी. (बी. एण्ड आर.) की पहले से विद्यमान 20 मीटर चौड़ी सड़क के वर्तमान संरेखण को शामिल करते हुए प्रस्तावित की गई है।

अन्य सड़कों की चौड़ाई तथा संरेखण सैक्टर योजना या कालोनी की अनुमोदित अभिविन्यास योजनाओं के अनुसार होगी। विकास योजना में दर्शाए गए प्रस्तावित मार्ग जहां—जहां भू—परिस्थितियों के कारण असंभाव्य होंगे, वहां सरकार कारणों का उल्लेख करते हुए इन्हें पुनः संरेखित / समाप्त करने में सक्षम होगी।

4.2 ईस्टर्न डेडिकेटिड फ्रेंट कोरिडोर :

डेडिकेटिड फ्रेंट कारिडॉर ऑफ इन्डिया द्वारा लुधियाना, पंजाब से धनकुनी, पश्चिमी बंगाल तक पूर्वी समर्पित मालभाड़ा गलियारे का निर्माण आरम्भ कर दिया है, जो यमुनानगर जिले से गुजरता है तथा उसी के संरेखण को मौजूदा रेलवे लाईन के साथ विकास योजना में समायोजित कर दिया है।

जन उपयोगिता अंचल :

15,24,200 की अनुमानित जनसंख्या की आवश्यकता को पूरा करने के लिए 182.50 हैक्टेयर क्षेत्र को सार्वजिनक उपयोगिता के लिए चिहिनत किया गया है जोिक जलापूर्ति संस्थापनाओं, ड्रेनेज आपूर्ति, स्वच्छता, निपटान कार्य तथा विद्युत उप—केन्द्र इत्यादि की आवश्यकता को पूरा करने के लिए है। आवासीय क्षेत्रों सेक्टर 1 (भाग), 2 (भाग), 3 ए (भाग), 6 (भाग), 8 (भाग), 11(भाग), 12 (भाग), 23 (भाग) 28 (भाग), 37 (भाग), 40 (भाग) तथा 41 (भाग) में नहर आधारित जल संस्थापन के लिए 75 हैक्टेयर भूमि आरक्षित है। इन स्थलों को पश्चिमी यमुना नहर तथा दादूपुर नलवी नहर के निकट प्रस्तावित किया गया है। वर्तमान में पानी की ज्यादातर आपूर्ति ट्यूबवैल से क्लोरीनेशन के बाद होती है। यहां तीन मलजल शोधन संयंत्र गाँव ममदी तथा गड़ीगुजरान, बढ़ी माजरा तथा परवालों में विद्यमान है जबिक सात मलजल शोधन संयंत्र के लिए अतिरिक्त स्थल अम्बाला यमुनानगर रेलवे लाईन के नजदीक गांव फूसगढ़, सेक्टर 1, सेक्टर 3ए, सेक्टर 12, सेक्टर 23, सेक्टर 28 तथा सेक्टर 41 में भावी मांग को पूरा करने हेतु प्रस्तावित हैं। पुरानी अम्बाला—जगाधरी सड़क पर गांव खेड़ा में एक ठोस अपशिष्ट निपटान स्थल मौजूद हैं तथा गांव खूर्दी तथा गांव नम की राजस्व सम्पदा में संवर्द्धन नहर की दक्षिण की ओर भविष्य में विस्तार के लिए दो स्थल प्रस्तावित किये गये हैं।

जबिक, यमुनानगर में बिजली के बुनियादी ढांचे के संवर्द्धन के लिए गांव भम्बोली में राष्ट्रीय राजमार्ग—344 पर 400 के.वी. सब स्टेशन पहले से ही मौजूद है, जो यमुनानगर—जगाधरी के नियन्त्रित क्षेत्र के बाहर पड़ता है तथा यमुनानगर जगाधरी के सम्पूर्ण डाऊनलाईन लोडइस सब स्टेशन द्वारा दीन बन्धु छोटू राम थर्मल पावर प्लांट, गांव खेड़ा, रादौर सड़क पर जोड़ियां में तथा गांव रत्नपुर (दीन बन्धु छोटू राम थर्मल पावर प्लांट) में पहले से

विद्यमान तीन 220 के.वी. के विद्युत उप—केंद्रों से सिंक्रनाइजेशन में उपलब्ध कराया जा रहा है। इसके अलावा, 220 के.वी. का एक सब स्टेशन गांव चानेटी के नजदीक सेक्टर 33 में प्रस्तावित किया गया है। भविष्य में विस्तार के लिए विकास योजना में गांव सारवान की संपर्क सड़क पर कृषि अंचल में, मेहरमपुर से गागलान की संपर्क सड़क पर तथा गांव नाहरपुर के नजदीक तीन 220 के.वी. सब—स्टेशन प्रस्तावित किये गये है। पाँच 66 के.वी. सब—स्टेशन यमुनानगर—जगाधरी की पुरानी नगरपरिषद सीमा में पहले से विद्यमान है। एक 66 के.वी. सब स्टेशन सेक्टर 15 में विद्यमान है तथा एक 66 के.वी. सब स्टेशन यमुनानगर तथा जगाधरी में वितरण प्रणाली को मजबूत बनाने के लिए रत्नगढ़ गांव के पास विद्यमान ळें जबिक भविष्य में विद्युत की आपूर्ति बढ़ाने तथा इसके संवर्द्धन के लिए इक्कीस 66 के. वी. सब स्टेशन सेक्टर 2, 3ए, 4, 6, 7, 9, 11, 16, 17, 19, 23, 26, 30ए, 31, 32, 36, 41, 47, 52 तथा अमादलपुर सड़क पर गांव सुंग के नजदीक में चिह्नित किया गया है।

सार्वजनिक तथा अर्धसार्वजनिक उपयोग अंचल :

सैक्टर 17 में लघु सचिवालय तथा न्यायिक परिसर और सेक्टर 16 में औद्योगिक प्रशिक्षण संस्थान पहले से कार्यरत है। तथापि, शहरी केन्द्र की क्षमताओं को देखते हुए इसे क्षेत्र में एक महत्वपूर्ण पर्यटन केंद्र के रूप में विकसित किए जाने का प्रस्ताव है। इस प्रयोजन के लिए सेक्टर 11 (माग), 16 (माग), 17 (माग), 20 (माग), 22 (माग), 25 (माग), 35, 36 तथा 36ए में 315.46 हेक्टेयर क्षेत्र को चिहिनत किया गया है। शिक्षा तथा स्वास्थ्य पर्यटन को बढ़ावा देने के लिए सेक्टर 36 में एजुकेशन सिटी तथा मैडी सिटी का विकास किया जा सकता है। आवासीय सेक्टर 25 में जेल भी समायोजित की गई है।

7. खुले स्थल:

प्रारूप विकास योजना में यथा आरक्षित खुले स्थान के अधीन 1200.62 हैक्टेयर क्षेत्र है। सेक्टर 18 में टाउन पार्क के लिए 8.10 हेक्टेयर क्षेत्र विशेष रूप से निश्चित किया गया है। सेक्टर—6 (भाग) तथा सेक्टर 25 में क्रमशः 16 हेक्टेयर तथा 11.63 हेक्टेयर का क्षेत्र खेल का मैदान, स्टेडियम खेल का मैदान तथा पार्क के लिए भी प्रस्तावित किया गया है। इसके अतिरिक्त, खुले क्षेत्र हेतु दो सेक्टर अर्थात् सेक्टर 37 (भाग) तथा 38 प्रस्तावितहै। यह क्षेत्र के सौंदर्यकरण को बढायेगा।

सरकार द्वारा अधिसूचना के अनुसार, दादूपुर नलवी नहर को आशिंक रूप से अधिसूचना से बाहर किया गया है और बाद में नहर के क्षेत्र को खुले स्थल में जोड़ दिया गया है। इसके अलावा, पश्चिमी यमुना नहर की सुरक्षा के लिए इसके दोनों तरफ 30 मीटर चौड़ी हरित पट्टी प्रस्तावित की गई है। सेक्टर/मुख्य सड़कों के साथ प्रस्तावित हरित पट्टियां मुख्य रूप से भविष्य में सेक्टर/मुख्य सड़क के चौड़ीकरण के लिए होगी। तथापि, ऐसे समय तक जब तक चौड़ीकरण नहीं होता है, तब तक उक्त क्षेत्र का उपयोग नर्सरी/वृक्षारोपण, ईंधन स्टेशन, संचार लाईनों, उपयोगिता सेवाओं आदि के लिए किया जा सकता है।

कृषि अंचल :—

नियन्त्रित क्षेत्र में शेष क्षेत्र को कृषि क्षेत्र के रूप में रखा गया है। तथापि, यह इस क्षेत्र के भीतर आवश्यक भवन विकास को नहीं रोकेगा, जैसे आबादी—देह के सीमावर्ती मौजूदा गांव का विस्तार, यदि परियोजना के रूप में अनुमोदितया सरकार द्वारा प्रायोजित अन्य गतिविधियों के अधीन क्षेत्रीय विनियमों के अधीन अनुज्ञेय गतिविधियों के रूप में शामिल हो। कृषि क्षेत्र के रूप में इस क्षेत्र के रख—रखाव और सुधार के लिए आवश्यक परिशिष्ट ख से अनुबन्ध 'ख' सहायक और संबद्ध सुविधाएं, जो कि पूरे शहर के लिए एक खुले ग्रामीण क्षेत्र के रूप में कार्य करने के लिए प्रस्तावित है।

9. विशेष अंचल -इंटिग्रेटिड वेसाइड एमेनिटिज :

विकास योजना में, हाईवे ट्रैफिक को सुविधाजनक बनाने के लिए,सड़क के साथ एकीकृत सुविधाओं के लिए भी प्रावधान विशेष अंचल के रूप में 16.16 हेक्टेयर क्षेत्र पर किया गया है। इस अंचल के अधीन आने वाले क्षेत्रों को राष्ट्रीय राजमार्गों, अनुसूचित सड़कों, राज्य राजमार्गों और बाहरी परिधीय सड़कों पर बुनियादी सेवाओं और सुविधाओं को प्रदान करने के लिए नियमित अन्तराल पर स्थापित करने की योजना है, तािक ड्राईवरों को मनोरंजन और आराम के लिए एक आरामदायक स्थान प्रदान करके दुर्घटनाओं की संभावना को कम करते हुए लंबी दूरी के यात्रियों के लिए सुरक्षित और सुविधाजनक यात्रा सुनिश्चित की जा सके।यह अंचल 20 किलोमीटर (लगभग) के अन्तराल पर 10 एकड़ के क्षेत्रफल के साथ चार अलग—अलग स्थानों पर राष्ट्रीय राजमार्ग 344 पर नजदीक गांव कैल तथा कलानोर और राष्ट्रीय राजमार्ग 907 पर गांव छछरोली के नजदीक तथा पूर्वी परिधीय सड़क के साथ—साथ गांव अमदालपुर के नजदीक बुनियादी सेवाएं और सुविधांए प्रदान करने के लिए प्रस्तावित है।

अंचल विनियम :

भूमि उपयोग संबंधित प्रस्तावों को अंचल विनियम बनाकर वैद्य बनाया जा रहा है। जो इस प्रारूप विकास योजना के भाग रूप बनेंगे। ये विनियम भूमि के उपयोग परिवर्तन और विकास मानकों के लिए लागू होंगे। इन विनियमों में विभिन्न मुख्य भूमि उपयोगों में अनुमत सम्बद्ध तथा सहायक उपयोगों को भी बहुत विस्तारपूर्वक वर्णन किया गया है और यह तय किया गया है कि भूमि उपयोग परिवर्तन तथा विकास सेक्टर योजना में दिये गये ब्योरे अनुसार होगा इससे प्रत्येक सेक्टर का निर्दिष्ट विकास और उचित नियंत्रण करने हेतु विस्तृत सेक्टर योजनायें तैयार करना सुनिश्चित हो सकेगा।

अनुबन्ध—ख

अंचल विनियम :--

ड्राईंग संख्या डी.टी.पी.(वाई.)86/2020, दिनांक 23 जुलाई, 2020 में दर्शाए अनुसार यमुनानगर—जगाधरी के इर्द–गिर्द नियन्त्रित क्षेत्रों में भूमि के उपयोग तथा विकास को शासित करना।

I. सामान्य:-

- यमुनानगर—जगाधरी के इर्द गिर्द नियंत्रित क्षेत्रों के लिए प्रारूप विकास योजना का भाग रूप बनने वाले इन अंचल विनियमों को नियंत्रित क्षेत्र यमुनानगर—जगाधरी के लिए प्रारूप विकास योजना के अंचल विनियम कहा जायेगा।
- 2. विनियमों की अपेक्षाएं, प्रारूप विकास योजना में शामिल समूचे क्षेत्र की सीमा तक होंगी तथा पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) और उसके अधीन बनाये गये नियमों की अपेक्षाओं के अतिरिक्त होंगी।

II. परिमाषायें:-

इन विनियमों में,-

- (क) 'कृषि आधारित उद्योग' से अभिप्राय है, ऐसी औद्योगिक इकाई, जो खाद्यान्न, फलों या कृषि अपशिष्ट का उपयोग कच्चे माल के रूप में करती है;
- (ख) 'अनुमोदित' से अभिप्राय है, सक्षम प्राधिकारी द्वारा अनुमोदित;
- (ग) **'मवन संहिता'** से अभिप्राय है, हरियाणा भवन संहिता, 2017;
- (घ) **'मवन नियमों**' से अभिप्राय है, नियमों के भाग–VII में अन्तर्विष्ट नियम;
- (ड.) **'साईबर सिटी'** से अभिप्राय है, केन्द्रकीय सूचना/प्रौद्योगिकी परिकल्पना के लिए विकसित और कम्पनियों/सूचना प्रौद्योगिकी आधारित सेवाओं के मध्यम तथा बड़े साफ्टवेयर उत्पन्न किए जाने के लिए अति उच्चतम गुणवत्ता का मूलभूत ढांचा, उत्तम परिस्थितियां और उच्च गित संचार से आत्मिनर्भर परिपूर्ण शहर, जहां विनिर्माण ईकाईयों को अनुमत नहीं किया जाएगा;
- (च) **'साईबर पार्क/सूचना प्रौद्योगिकी पार्क'** से अभिप्राय है, वह क्षेत्र जो केवल साफ्टवेयर विकास सम्बन्धी क्रियाकलापों का पता लगाने तथा सूचना प्रौद्योगिकी को समर्थ बनाने वाली सेवाओं के लिए विकसित हों, इसमें किसी भी प्रकार के विनिर्माण (असैम्बलिंग क्रियाकलापों सहित) की अनुमित प्रदान नहीं की जाएगी।
- (छ) ''**ड्राईंग'**' से अभिप्राय है, ड्राईंग संख्या डी.टी.पी.(वाई.)86/2020, दिनांक 23 जुलाई, 2020
- (ज) **'व्यापक उद्योग'** से अभिप्राय है, ऐसा उद्योग जो सरकार की अनुमित से स्थापित किया जाये और जो व्यापक हो, जिसमें 100 से अधिक कामगार नियुक्त हों तथा जिसमें ईंधन चालित शक्ति का प्रयोग किया जाये बशर्ते कि इसमें किसी प्रकार के हानिकारक तत्व न हों;
- (झ) **"फार्म गृह"** से अभिप्राय है, किसीफार्म के स्वामी द्वारा अपनी भूमि पर निम्नलिखित प्रयोजनार्थ निर्मित घर—
 - (i) निवास युनिट अर्थात् मुख्य उपयोगः
 - (ii) फार्म छायाबान अर्थात् गौण उपयोग।

टिप्पण:-

- (1) फार्म गृह का निर्माण 'कृषि अंचल में आबादी देह से बाहर फार्म गृहों की व्यवस्था' संबंधी खण्ड XIX के अधीन दिये गये निर्बन्धनों से शासित होगा;
- (2) 'फार्म शैड' 'भवन नियंत्रण और स्थल विशिष्टियां', के सम्बन्ध में खंड XIX में उल्लेखित निर्बन्धनों द्वारा शासित होंगे।
- (ञ) **'फर्श क्षेत्र अनुपात'** से अभिप्राय है, सभी मंजिलों के कुल आच्छादित क्षेत्र तथा सौ के गुणक को प्लाट क्षेत्र से विभाजित करते हुए प्राप्त किया गया भागफल, अर्थात् :-

फर्श क्षेत्र अनुपात की गणना के प्रयोजन के लिए, कैंटिलीवर अनुमत छत प्रोजेक्शनों; लिफ्ट कमरा, ममटी, छज्जा, तहखाना या कोई फर्श यदि पार्किंग, सेवाओं और भंडारण, केवल पार्किंग/पैदल यात्री प्लाजा के लिए उपयोग हेतु प्रस्तावित स्टिलट क्षेत्र, (खुला), खुली सीढ़ी (ममटी के बिना), पहुँच के साथ या के बिना, छत अग्नि सीढ़ी, अलिंद पानी की टंकी, अनुमत आकार के खुला आंगन के लिये उपयोग किया गया हैं, फर्श क्षेत्र अनुपात में गिना नहीं जाएगाः

परंतु स्टिलट से अगली मंजिल तक शाफ्ट, शूटस, लिफ्ट वैल तथा सीढ़ी के अधीन क्षेत्र, भूमि तल से फर्श क्षेत्र अनुपात केवल एक बार गिना जाएगाः

परंतु यह और कि यदि वेंटिलेशन शाफ्ट क्षेत्र 3 वर्ग मीटर से अधिक है, तो यह फर्श क्षेत्र अनुपात में नहीं गिना जाएगा;

- (ट) **'ईधन स्टेशन'** से अभिप्राय है, ईंधन भरने वाला स्टेशन जो ऑटोमोबाइल के लिए ईंधन की खुदरा आपूर्ति प्रदान करता है, जिसमें पेट्रोल पम्प, सीएनजी स्टेशन, जैव—ईंधन, चार्जिंग स्टेशन, बैटरी उपलब्ध स्टेशन आदि शामिल हैं:
- (ठ) **'हरित पट्टी'** से अभिप्राय है, विकास योजना में दर्शाए गए सेक्टर / मुख्य सड़कों के साथ—साथ भूमि की पट्टियां जो मुख्यतः भविष्य में इन सड़कों को चौड़ा करने अथवा आवश्यक सेवाएं उपलब्ध कराने हेतु होंगी।
- (ड) **'वर्ग आवास'** से अभिप्राय है, रिहायशी प्रयोजन के लिए फ्लैटों के रूप में डिजाईन तथा विकसित किये गये भवन या वर्ग आवास का अनुषंगी कोई भवन;
- (ढ) **'मारी उद्योग'** से अभिप्राय है, सरकार की अनुमित से सार्वजनिक या अर्ध—सार्वजनिक या निजी क्षेत्र में स्थापित किया गया उद्योग (प्लान्ट, मशीनरी इत्यादि की लागत जैसे कि सरकार की उद्योग नीति में परिभाषित हो);
- (ण) **'सूचना प्रौद्योगिकी औद्योगिक ईकाई'** से अभिप्राय है, हरियाणा सरकार की सूचना प्रौद्योगिकी नीति, 2000 के अनुबन्ध में तथा इस अधिसूचना के परिशिष्ट—1 में शामिल उद्योगों की श्रेणियां तथा / अथवा जो हरियाणा सरकार द्वारा, समय—समय पर, परिभाषित की जाये;
- (त) **पुश्तवान याटांड** ' से अभिप्राय है, कमरे के अन्दर बनाए गए अनुलम्ब खम्भे को छोड़कर, किसी भी स्वरूप की शैल्फ जैसे बहिर्गत भाग, बशर्ते जिसका बहिंगत भाग एक मीटर से अधिक चौड़ा न हो।
- (थ) **'हल्के उद्योग'** से अभिप्राय है, ऐसा उद्योग जिसके कारण हानिकारक या घृणाजनक शोर, धुआं, गैस, भॉप गन्ध, धूल, बहिःस्राव और कोई अन्य अत्यधिक डिग्री का प्रदूषण न हो और बिजली द्वारा चालित हों;
- (द) स्थानीय सेवा ज़द्योग' से अभिप्राय है, ऐसा उद्योग जिसका विनिर्मित माल और उत्पादन प्रायः स्थानीय क्षेत्र के भीतर उपभोग किया जाता हो, उदाहरणार्थ बेकरियां, आई सक्रीम विनिर्माण, वातित जल, बिजली से चलने वाली आटे की चिक्कयां, लोंड्री, ड्राईक्लीनिंग और रंगाई, स्वचालित गाड़ियों, स्कूटर तथा साईकलों की मरम्मत तथा सर्विस, घरेलू बर्तनों की मरम्मत, जूते बनाना और उनकी मरम्मत, ईधन डिपो आदि बशर्ते कि उनमें किसी ठोस ईधन का प्रयोग न किया जाता हो;
- (ध) **'अटारी'** से अभिप्राय है, अधिकतम 1.5 मीटर की ऊँचाई सहित अवशिष्ट स्थल पर दो मंजिलों के बीच का मध्यवर्ती स्थल तथा जो केवल भंडारण प्रयोजन हेतू निर्मित की गई है अथवा अपनाई गई है;
- (न) **'वास्तविक तिथि'** से अभिप्राय है, नीचे घोषित किए गए विभिन्न नियंत्रित क्षेत्रों की अधिसूचना के प्रकाशन की तिथि:

क्रम	नियन्त्रित क्षेत्र का नाम और अधिसूचना संख्या	वास्तविक तिथि
संख्या		
1.	दिनांक 28 मई, 1965 को पंजाब सरकार राजपत्र अधिसूचना संख्या—447—2टीसीपी—65 / 6852, दिनांक 6 मार्च, 1965 द्वारा प्रकाशित अधिसूचित नियन्त्रित क्षेत्र।	28 मई, 1965
2.	दिनांक प्रथम जुलाई, 1997 को प्रकाशित हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग हरियाणा सरकार राजपत्र अधिसूचना संख्या— सीसीपी / जे.सी.ए.—1 / 97 / 468, दिनांक 29मई, 1997 द्वारा द्वारा अधिसूचित अतिरिक्त नियंत्रित क्षेत्र।	प्रथम जुलाई, 1997
3.	दिनांक ९ फरवरी, २००७ को प्रकाशित हरियाणा सरकार राजपत्रअधिसूचना संख्या— सीसीपी(एन.सी.आर.)वाई.एन. (ए.सी.ए.—III)/ ए/२००७/४२२, दिनांक ९ फरवरी, २००७ द्वारा अधिसूचित अतिरिक्त नियंत्रित क्षेत्र—III	9 फरवरी, 2007
4.	दिनांक 16 जुलाई, 2020 को प्रकाशित हरियाणा सरकार राजपत्र अधिसूचना संख्या— सीसीपी(एन.सी.आर.)वाई.एन.(ए.सी.ए.—IV)/ 2020/ 901, दिनांक 16 जुलाई, 2020 द्वारा अधिसूचित अतिरिक्त नियंत्रित क्षेत्र—IV	16 जुलाई, 2020

- (प) **'मध्यम उद्योग'** से अभिप्राय है, हल्का उद्योग तथा स्थानीय सेवा उद्योग के अलावा सभी उद्योग और जो घृणाजनक और खतरनाक गंध तथा दुर्गन्ध न फैलाते हों;
- (फ) **'परछती तल'** से अभिप्राय है, निम्न मंजिल का 1/2 (आधा) तक के सीमित क्षेत्र सहित तथा न्यूनतम ऊँचाई 2.3 मीटर सहित दो मंजिलों के बीच कोई मध्यवर्ती तल और ऊपरी तल स्तर से 2.3 मीटर (स्पष्ट ऊँचाई) से कम नहीं होगा;
- (ब) नियंत्रित क्षेत्र में किसी भूमि अथवा भवन के संबंध में 'अननुरूप उपयोग' से अभिप्राय है, ऐसी भूमि अथवा भवन जो विकास योजना में क्षेत्र के उस भाग के लिए विनिर्दिष्ट मुख्य भूमि उपयोग के विपरीत हो;
- (म) **'घृणाजनक या परिसंकटमय उद्योग'** से अभिप्राय है सरकार की अनुमित से स्थापित किया गया उद्योग और जिसमें अत्यिधक पूंजी लगी हो। जिसमें अत्यिधक धुंआ, शोर, स्पन्दन, दुर्गन्ध, अप्रिय या हानिकारक बिहः स्राव, विस्फोटक, ज्वलनशील सामग्री इत्यादि और समुदाय के स्वास्थ्य और सुरक्षा के लिए अन्य खतरनाक तत्व शामिल हों;
- (म) **'सार्वजनिक उपयोगिता सेवा भवन'** से अभिप्राय है, ऐसा भवन जो सार्वजनिक उपयोगिता सेवाओं को चलाने के लिए अपेक्षित हो, जैसे जल सप्लाई, जल निकास, बिजली, डाक तथा तार तथा परिवहन तथा दमकल केन्द्र सहित कोई नगरपालिका सेवा;
- (य) **'नियमों**' से अभिप्राय है, पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन नियम, 1965;
- (य क) "सेक्टर क्षेत्र', और 'कॉलोनी क्षेत्र' से अभिप्राय है, विकास योजना में ऐसे रूप में दर्शाये गये सेक्टर क्षेत्र या कॉलोनी क्षेत्र:

व्याख्या :

- (1) इस परिभाषा में 'सेक्टर क्षेत्र' या 'कालोनी क्षेत्र' से अभिप्राय है, सेक्टर या कालोनी का क्षेत्र जो कालोनी / सेक्टर की अनुमोदित अभिन्यास योजना पर ड्राईंग में दर्शाया गया है जिसमें सेक्टर या कालोनी, जैसे भी स्थिति हो, में भवन विकास के लिए अनुपयुक्त क्षेत्र शामिल नहीं है;
- (2) मुख्य सड़कों तथा उनकी निकटवर्ती हरित पट्टी, यदि कोई हो, के अधीन आने वाले क्षेत्र का 50 प्रतिशत लाभ प्लाटिड/ग्रुप आवास कालोनी की दशा में प्लाटऐबल क्षेत्र/फर्श क्षेत्रफल अनुपात के लिए अनुज्ञात किया जायेगा;
- (3) औद्योगिक कालोनी / सेक्टर से भिन्न कालोनी या सेक्टर की विन्यास योजना में, सड़कों, खुले स्थानों, विद्यालयों, सार्वजिनक तथा सामुदायिक भवन तथा अन्य सामूहिक उपयोगों के लिए आरक्षित भूमि कालोनी / सेक्टर के अधीन भूमि के कुल क्षेत्र के 45 प्रतिशत से कम नहीं होगी।
- (4) सेक्टर सघनता या कालोनी सघनता की संगणना के प्रयोजनों के लिए यह माना जायेगा कि सेक्टर क्षेत्र या कालोनी क्षेत्र का 50 प्रतिशत आवासीय प्लाटों के लिए उपलब्ध होगा जिसमें ग्रुप आवास के अधीन क्षेत्र भी शामिल होगा तथा प्रत्येक भवन प्लाट औसतन प्रत्येक तीन निवास ईकाइयों में 4.5 व्यक्ति प्रति निवास ईकाई या 13.5 व्यक्ति भवन प्लाट या कालोनी / ग्रुप आवास समूह की अंचल योजना में यथा सम्मिलित होगा। यद्यपि, दुकान तथा आवासीय प्लाट के मामले में केवल एक निवास इकाई मानी जायेगी;
- (5) उपरोक्त दी गई किसी बात के होते हुए भी, विनिर्दिष्ट पॉलिसी जैसे नई एकीकृत अनुज्ञापन पॉलिसी के अधीन अनुमोदित परियोजनाएं; प्लॉटऐबल क्षेत्र की बजाय फर्श क्षेत्र अनुपात तथा सघनता पैरामीटर से शासित होंगी:
- (य ख) **'सेक्टर सघनता' और 'कॉलोनी सघनता',** से अभिप्राय है, उस सेक्टर क्षेत्र तथा कॉलोनी क्षेत्र, जैसी भी स्थिति हो, में प्रतिहैक्टेयर व्यक्तियों की संख्या;
- (य ग) **'स्थल आच्छादन'** से अभिप्राय है, भवन के भूतल क्षेत्र और स्थल क्षेत्र द्वारा आच्छादित क्षेत्र के बीच प्रतिशतता में अभिव्यक्त अनुपात;
- (य घ) **'लघु उद्योग'** से अभिप्राय है, ऐसी औद्योगिक इकाई जो उद्योग विभाग द्वारा लघु उद्योग के रूप में पंजीकृत हो;
- (य ड.) **'कृषि उपयोग साधन'** से अभिप्राय है, ऐसा विकास तथा गतिविधियां, जो कृषि संबंधी कार्यों को करने में सहायक रूप में अपेक्षित है, जैसे कि नलकूप, पम्प, चैम्बर, वायु चक्की, सिंचाई, नाले, पक्के प्लेटफार्म, बाड लगाना तथा चारदीवारी बनाना, जल नलके आदि:

- (य च) **'अधिनियम', 'कालोनी', 'उप-निवेशक', 'विकास योजना', 'सेक्टर' और 'सेक्टर योजना'** शब्दों का वहीं अर्थ होगा, जो उन्हेंपंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) और इसके अधीन बनाए गए नियम, 1965में दिया गया है;
- (य छ) किन्हीं अन्य शब्दों का वही अर्थ होगा, जो उन्हें पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) तथा इसके अधीन बनाए गए नियमों में दिया गया है।

III. मुख्य भूमि उपयोग/अंचल:-

- 1. (i) रिहायशी अंचल
 - (ii) वाणिज्यिक अंचल
 - (iii) औद्योगिक अचल
 - (iv) परिवहन तथा संचार अंचल
 - (v) जन उपयोगिता अंचल
 - (vi) सार्वजनिक तथा अर्धसार्वजनिक अंचल (संस्थागत अंचल)
 - (vii) खुले स्थान अंचल
 - (viii) कृषि अंचल
 - (ix) विशेष अंचल
- 2. मुख्य भूमि उपयोगों का वर्गीकरण परिशिष्ट–क के अनुसार है।

IV. सेक्टरों में विभाजन:-

उपर्युक्त अंचल विनियमन—III में क्रम संख्या—(i) से (vii) व (ix) पर वर्णित मुख्य भूमि उपयोग, जो भवन प्रयोजनार्थ भूमि उपयोग हैं, जिन्हें इन सेक्टरों की मुख्य सड़कों के आरक्षण हेतु दर्शाई गई हदबन्दी के अनुसार सेक्टरों में विभाजित किया गया है और प्रत्येक सेक्टर को ड्राईंग में दिखाये अनुसार एक निश्चित संख्या दी गई है।

V. मुख्य उपयोगों में भूमि उपयोग संबंधी ब्यौरा:-

मुख्य, सहायक तथा गौण उपयोग जो इन विनियमों तथा नियमों के अन्य अपेक्षाओं के अध्यधीन हैं, को मुख्य भूमि उपयोग अंचल में अनुमति दी जा सकती है, उनकी सूची परिशिष्ट ख पर दी गई है जो इन विनियमों के साथ जोड़े गये हैं।

VI. विकास के लिए अनुपयुक्त सेक्टर:-

विभिन्न सेक्टरों में भवन परियोजनार्थ, भूमि उपयोग के लिए आरक्षण होते हुए भी, निदेशक, नियंत्रित क्षेत्र के सघन तथा किफायती विकास के दृष्टिगत अपने भूमि उपयोग में किसी प्रकार के परिवर्तन के लिए अथवा उस पर किसी भवन के निर्माण के लिए ऐसे समय तक अनुमित नहीं देगा जब तक वह अपनी संतुष्टि सुनिश्चित नहीं कर लेता है कि इन सेक्टरों के लिए जल सप्लाई, जल मल निकास व्यवस्था तथा अन्य सुविधायें, उपलब्ध नहीं हो जाती हैं।

VII. केवल सरकारी उपक्रमों के माध्यम से विकसित किये जाने वाले सेक्टर:-

सरकार अपने द्वारा या उसके अभिकरणों द्वारा, विकास के लिए कोई सेक्टर अधिसूचित कर सकती हैं, ऐसे मामले में ऐसे सेक्टरों में भूमि उपयोग के परिवर्तन या अनुज्ञप्ति प्रदान करने के लिए आगे कोई भी अनुमित अनुमत नहीं की जाएगी।

VIII. मुख्य सड़कों के लिए भूमि आरक्षण:

(1) ड्राईंग में चिहिनत की गई मुख्य सड़कों के लिए भृमि का आरक्षण निम्न प्रकार से किया जायेगा :

क्रम संख्या	वर्गीकरण	सड़क का नाम	आरक्षित भूमि
1	वी—1	शहरी क्षेत्र सहित उतरी परिधीय सड़क	दोनों तरफ 50 मीटर चौड़ी हरित पट्टी सहित 75 मीटर चौड़ी सड़क
2	वी—2	(i) अम्बाला—जगाधरी—यमुनानगर—सहारनपुर सड़क (राष्ट्रीय राजमार्ग 344) (ii) जगाधरी छछरोली—पावंटासाहिब सड़क (राष्ट्रीय राजमार्ग 907)	दोनों तरफ हरित पट्टी 30 मीटर चौड़ी सहित 60 मीटर चौड़ी सड़क

		(iii) पूर्वी परिधीय सड़क (iv) अतिरिक्त परिधीय सड़क (v) सेक्टर को विभाजित करने वाली सड़क	
3	वी—2 (ए)	अम्बाला—जगाधरी—यमुनानगर—सहारनपुर सङ्क (राष्ट्रीय राजमार्ग 344)	उत्तर की ओर 60 मीटर चौडी हरित पट्टी तथा दक्षिण की ओर 30 मीटर चौड़ी हरित पट्टी सहित 60 मीटर चौड़ी सड़क ।
4	वी—2 (बी)	(i) पश्चिमी परिधीय सड़क (ii) सेक्टर की विभाजक सड़क (iii) पुरानी सहारनपुर सड़क	60 मीटर चौड़ी सड़क
5	वी—2 (सी)	सेक्टर विभाजक सड़क	दक्षिण की ओर 30 मीटर चौड़ी हरित पट्टी सहित 60 मीटर चौड़ी सड़क
6	वी—3	सेक्टर विभाजक सड़क	45 मीटर चौड़ी सड़क
7	वी—4	(i) जगाधरी बिलासपुर सड़क (राज्य राजमार्ग 1) (ii) यमुनानगर–रादौर सड़क (राज्य राजमार्ग 6 ए) (iii) पुराना अम्बाला जगाधरी सड़क	दोनों ओर 30 मीटर चौड़ी हरित पट्टी सहित 30 मीटर चौड़ी सड़क
8	वी—4 (ए)	वर्तमान आन्तरिक सड़के	विद्यमान चौड़ाई
9	वी—4 (बी)	संवर्धन नहर के साथ सड़क	30 मीटर चौड़ी सड़क
10	वी—4 (सी)	पुरानी अम्बाला जगाधरी सड़क	दोनो तरफ 60 मीटर चौड़ी हरित पट्टी सहित 30 मीटर चौड़ी सड़क

- (2) अन्य सड़कों की चौड़ाई और सीधाई, सेक्टर योजना के अनुसार अथवा कालोनियों की अनुमोदित अभिविन्यास योजना के अनुसार होगी।विकास योजना में दर्शाए गए प्रस्तावित मार्ग जहां—जहां भू—परिस्थितियों के कारण असंभाव्य होंगे, वहां सरकार कारणों का उल्लेख करते हुए इन्हें पूनः संरेखित/समाप्त करने में सक्षम होगी।
- (3) व्यापार योग्य फर्श क्षेत्र अनुपात का लाभ विनिर्दिष्ट पॉलिसी के अनुसार सेक्टर सड़क या हरित पट्टी तथा खुला क्षेत्र अंचलों के अधीन आने वाली भूमि के लिए प्रदान की गई अनुज्ञप्तियों के लिए अनुज्ञात किया जा सकता है।

IX. अननुरूप उपयोग अर्थात् विद्यमान या भूमि उपयोग में वैद्य परिवर्तन की अनुमति प्राप्त:-

- विकास योजना में औद्योगिक अंचल से भिन्न अंचलों में दर्शाए गए विद्यमान उद्योगों के संबंध में, निदेशक द्वारा निर्धारित की जाने वाली नियत अविध, किन्तु दस वर्ष से अधिक न हों, के लिए ऐसे औद्योगिक अननुरूप उपयोग जारी रखने की अनुमित दी जाएगी; बशर्ते कि सम्बद्ध भवन का स्वामीः
 - (क) निदेशक को स्थल के बाह्य विकास के लिए, उस द्वारा यथा निर्धारित अनुपातिक प्रभारों तथा जब भी निदेशक द्वारा इस निमित्त ऐसा करने के लिए कहा जाये, के भुगतान का वचन देता है;
 - (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार बहिःस्राव के निष्कासन की सुनिश्चित व्यवस्था करेः तथाः
 - (ग) अनन्रूप उपयोग के क्षेत्र में विद्यमान परियोजना के विस्तार की अनुमित नहीं होगी;
- 2. उन परियोजनाओं के बारे में, जिन्हें भूमि उपयोग की मान्य स्वीकृति है, तथा जो विकास योजना में अनुरूप उपयोग अंचल से भिन्न अवस्थित हैं, ऐसे अननुरूप उपयोग जारी रखने के लिए अनुमत किए जाएंगे, बशर्ते कि सम्बद्ध भवन का स्वामी.—
 - (क) निदेशक को स्थल के बाह्य विकास के लिए उस द्वारा यथा निर्धारित अनुपातिक प्रभारों तथा निदेशक द्वारा इस निमित्त ऐसा करने के लिए कहा जाये, के भुगतान का वचन देता है;
 - (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार बिहः स्राव के लिए संतोषजनक व्यवस्था करे।

X. अननुरूप उपयोग बन्द करना:-

- यदि किसी भूमि का अननुरूप उपयोग दो वर्ष या इससे अधिक अविध के लिए लगातार बन्द रहा हो, तो उसे समाप्त हुआ समझा जायेगा और केवल अनुरूप अनुमत उपयोग के अनुसार ही भूमि के पुनः उपयोग या पुनः विकास की अनुमति दी जायेगी।
- 2. यदि अननुरूप उपयोग भवन, आग, बाढ़, विस्फोट, भूकम्प, लड़ाई, दंगा या किसी अन्य प्राकृतिक आपदा से इसके पुनरूत्पादन मूल्य के 50 प्रतिशत या इससे अधिक क्षतिग्रस्त हो जाता है, तो उसे केवल अनुमत उपयोग के लिए पुनःविकसित करने की अनुमति दी जायेगी।
- 3. खण्ड IX के अधीन शामिल परियोजनाओं के समाप्त होने के बाद, भूमि केवल अनुरूप उपयोग के लिए पुनः विकसित करने या उपयोग में लाने के लिए अनुमत की जायेगी।
- 4. खण्ड IX(1) के अधीन नियत अविध की समाप्ति के बाद भूमि केवल अनुरूप उपयोग के लिए पुनः विकसित या उपयोग में लाने के लिए अनुमत की जाएगी।

XI. सेक्टर योजना और आंचलिक योजना के अनुरूप विकास:-

विनियम—IX में यथा उपबन्धित को छोड़कर, मुख्य भूमि उपयोग में किसी भी भूमि को भवन निर्माण प्रयोजनार्थ उपयोग तथा विकास के लिए तब तक अनुमत नहीं किया जाएगा जब तक प्रस्तावित उपयोग और विकास, सेक्टर योजना और आंचलिक योजना अथवा अनुमोदित कालोनी योजना, जिसमें भूमि अवस्थित है, में दिखाये गये ब्यौरे के अनुसार न हो।

XII. अनुमोदितअभिविन्यास या आंचलिक योजना का भाग बनने वाले विशिष्ट स्थल:-

किसी प्लाट पर भवन निर्माण या पुनःनिर्माण की अनुमति तब तक नहीं दी जायेगी जब तक -

- (i) प्लाट अनुमोदित कालोनी का भाग न हो या प्लाट ऐसे क्षेत्र में न हो, जिसके लिए विनियम XVII में यथा उपबन्धित अनुसार छूट दी गई है; तथा
- (ii) निदेशक की संतुष्टि अनुसार प्लाट तक पहुंच के लिए सड़क की व्यवस्था न हो और सड़क न बनी हो।

XIII. विभिन्न प्रकार के भवनों के प्लाटों का न्यूनतम आकार:-

(1) विभिन्न प्रकार के उपयोगों के लिए प्लाटों के न्यूनतम आकार निम्न अनुसार होंगे:—

क्रम संख्या	भूमि उपयोग	आकार			
(i)	रिहायशी प्लाट	50 वर्ग मीटर	59.8 वर्ग गज	538.20 वर्ग फीट	
(ii)	सरकार द्वारा अनुमोदित आर्थिक सहायता प्राप्त औद्योगिक आवास या गन्दी बस्तियों में रहने वालों के लिए आवास स्कीम में रिहायशी प्लाट	35 वर्ग मीटर	41.86 वर्ग गज	376.74 वर्ग फीट	
(iii)	दुकान एवं रिहायशी प्लाट	100 वर्ग मीटर	119.60 वर्ग गज	1076.40 वर्ग फीट	
(iv)	शापिंग बूथ जिनमें सामने बरामदा या पत्थर तथा ईंट पैदल मार्ग शामिल हो	20 वर्ग मीटर	23.92 वर्ग गज	215.28 वर्ग फीट	
(v)	स्थानीय सेवा उद्योग प्लाट	100 वर्ग मीटर	119.60 वर्ग गज	1076.40 वर्ग फीट	
(vi)	हल्के उद्योग प्लाट	250 वर्ग मीटर	299 वर्ग गज	2691 वर्ग फीट	
(vii)	मध्यम उद्योग प्लाट	8000 वर्ग मीटर	9568 वर्ग गज	86112 वर्ग फीट	

(2) रिहायशी और वाणिज्य विकास के लिये वर्ग आवास कालोनी, प्लाटिड रिहायशी कालोनी और वाणिज्य कालोनी के लिए क्षेत्र मानदण्ड, समय–समय पर, अधिसूचित नीतियों के अनुसार होंगें। तथापि, यदि वर्ग आवास स्कीम हरियाणा शहरी विकास प्राधिकरण या किसी अन्य सरकारी एजेंसी द्वारा प्रारम्भ की जाती है, तो वर्ग आवास स्थल का आकार योजना में यथा विनिर्दिष्ट होगा।

XIV. विभिन्न प्रकार के भवनों के अन्तर्गत आच्छादित क्षेत्र / ऊँचाई और आकार:-

विशिष्ट प्लॉट/स्थल के लिए अनुमत आच्छादित क्षेत्र, फर्श क्षेत्र अनुपात तथा ऊँचाई पैरामीटर, भवन संहिता/नियमों तथा/या ऐसे प्लाट/स्थल के जोनिंग प्लान में यथा अधिकथित विहित पॉलिसी द्वारा शासित होंगे।

XV. भवनों की अगली और पिछली ओर भवन पंक्ति:-

ये भवन संहिता / नियमों के अनुसार तथा / या ऐसे क्षेत्र के जोनिंग प्लान में यथा अधिकथित उपबन्धित होगी।

XVI. वास्तुकला संबंधी नियंत्रण:-

जहां कहीं भी वास्तुकला संबंधी नियंत्रण आवश्यक समझा जाता है, तो प्रत्येक भवन, हरियाणा भवन संहिता, 2017 के खण्ड 6.4 के अधीन बनाये गए वास्तुकला संबंधी नियंत्रण के अनुरूप होगा।

XVII. कृषि अंचल में ढील:-

कृषि अंचल में आने वाली किसी भूमि के मामले में, सरकार, इस विकास योजना के उपबन्धों में निम्नलिखित हेतु ढील दे सकती है.—

- (क) भूमि के आवासीय अथवा औद्योगिक कालोनी में उपयोग तथा विकास हेतु, बशर्ते उपनिवेशक द्वारा यह भूमि वास्तविक तिथि से पहले उक्त उपयोग तथा विकास के लिए क्रय की गई हो और उपनिवेशक नियमानुसार इस प्रयोजन के लिए अनुमति प्राप्त करता है।
- (ख) व्यक्तिगत स्थल के रूप में भूमि उपयोग हेतु (औद्योगिक कालोनी से भिन्न) परन्तु—
 - (i) वास्तविक तिथि से पूर्व भूमि क्रय की गई हो;
 - (ii) सरकार की संतुष्टि हो गई हो कि उद्योग की आवश्यकता इस प्रकार की है कि उपयुक्त अंचल में वैकल्पिक स्थल के नियतन की प्रतीक्षा नहीं की जा सकती;
 - (iii) भू-स्वामी, नियमों के यथा अपेक्षित अधीन भवन निर्माण के लिए अनुमति प्राप्त करता है; तथा
 - (iv) भू—स्वामी, निदेशक द्वारा निर्धारित अनुपातिक प्रभारों, जब कभी इस निमित्त निदेशक द्वारा मांग की जाये, का भुगतान निदेशक को करने का वचन देता है और अंतरिम अविध में बिहःस्राव के निकास की संतोषजनक व्यवस्था करता है।

व्याख्या.— इस विनियम में क्रयशब्द से अभिप्राय है, पूर्ण स्वामित्व अधिकारों का अर्जन तथा क्रय इत्यादि के करार जैसा कोई कमतर अधिकार नहीं।

(ग) ऐसा स्थल रक्षा संस्थापनाओं, यदि कोई हो, के इर्द–गिर्द रक्षा संकर्म अधिनियम, 1903(1903 का केन्द्रीय अधिनियम 7) के अधीन अधिसूचित निर्बन्धित पट्टी के भीतर नहीं आना चाहिए।

XVIII. सघनता:-

दोनों ओर से 20 प्रतिशत की विभिन्नता सिंहत प्रत्येक रिहायशी सेक्टर, ड्राईग में दर्शायी गई सेक्टर सघनता तथा इसके अतिरिक्त, नई एकीकृत अनुज्ञापन पॉलिसी, दीन दयाल जन आवास योजना पॉलिसी तथा अफोर्डऐबल ग्रुप हाऊसिंग पॉलिसी में यथा विहित सघनता में विकसित किया जाएगा। 20 प्रतिशत ग्रुप हाऊसिंग कम्पोनन्ट पॉलिसी रिहायशी सेक्टर में भी लागू होगी।

XIX. कृषि अंचल में आबादी देह के बाहर फार्म गृहों की व्यवस्था:-

केवल भू—स्वामी (स्वामियों) को वास्तविक उपयोग के लिए फार्म गृहों की अनुमित दी जाएगी बशर्तें कि किसी शहरी क्षेत्र में उसका अपना कोई आवास नहीं हो, चूंिक कृषि अंचल में फार्म गृहों को अनुमत करने के लिए वास्तविक उद्देश्य फार्म के छोटे भाग पर कृषकों की आवासीय आवश्यकताओं को पूरा करना है तािक वह उस फार्म पर निवास करने के दौरान अपने कृषि उत्पाद की देख—रेख कर सकें। इसिलए आबादी देह के बाहर कृषि अंचल में निम्निलिखित शर्तों पर फार्म गृह अनुमत किया जा सकता है, यदि भूमि का क्षेत्र 2 एकड़ या इससे अधिक है :

	फार्म हाउस का आकार	आवासीय इकाई का मुख्य भवन	मुख्य आवासीय इकाई का अनुषंगी भवन
(i) स्थल आच्छादन	न्यूनतम 2 एकड तक परन्तु विकास योजना अनुसार सड़क आरक्षण तथा प्रस्तावित सड़क की चौड़ाई के अधीन आने वाली भूमि/क्षेत्र भूमि उपयोग में परिवर्तन की अनुमति हेतु मान्य नहीं होगी। किन्तु कृषि अंचल में आने वाले आवेदित 2 एकड़ क्षेत्र मे से हरित पट्टी/ प्रतिबधित पट्टी के अधीन आने वाले क्षेत्र को छोड़ते हुए शेष क्षेत्र 1.5 एकड़ से कम नहीं होना चाहिए।	समकक्ष रिहायशी प्लाट के लिये	प्रतिशत

	3 एकड़ तक	375 वर्ग गज के समकक्ष रिहायशी प्लाट के लिये यथा लागू।	−सम <u>−</u>
	4 एकड़ तक और अधिक	500 वर्ग गज के समकक्ष रिहायशी प्लाट के लिये यथा लागू।	−सम <u>−</u>
(ii) ऊंचाई तथा मंजि	जेल व	11 मीटर, तीन मंजिलें	4 मीटर एक मंजिल

(iii) दूरी: कृषि भूमि के सभी किनारों से कम से कम 10 मीटर दूर बशर्तें कि यदि फार्म हाऊस से संबद्ध भूमि सड़क के साथ लगती है तो गृह का निर्माण सड़क के किनारे से कम से कम निम्नलिखित दूरी पर किया जायेगा:—

क्रम संख्या	सड़क	चौड़ाई
(क)	जहां सड़क अनुसूचित सड़क का बाईपास है	100 मीटर
(ख)	जहां सड़क अनुसूचित सड़क है या जैसा विकास योजना में दर्शाया गया है।	30 मीटर
(ग)	कोई अन्य सड़क	10 मीटर

(iv) पहुँच सड़क:-

राजस्व रिकार्ड में परिभाषित कोई राजस्व रास्ता / सडक।

(v) तहखाना:-

तहखाना, भू—तल आच्छादन की अधिकतम सीमा तक अनुमत किया जाएगा और उपयोग हरियाणा भवन संहिता, 2017 के अनुसार अनुज्ञात किए जाएंगे।

(vi) पुश्तवान, अटारी तथा परछती तल:-

पुश्तवान, अटारी और परछती तल की अनुमित भवन के भीतर उक्त निर्बन्धनों के साथ—साथ विकास योजना के अंचल विनियमों के खण्ड—II में दी गई परिभाषा में नियत निर्बन्धनों के अध्यधीन दी जायेगी।

(vii) सेवायें, जल आपूर्ति तथा जल-निकास:-

- (क) यदि फार्म गृह का निर्माण किया जाता है, तो फार्म में मानव उपयोग के लिए अच्छी पीने योग्य जल आपूर्ति उपलब्ध होनी चाहिए।
- (ख) डेरी फार्म के मामले में छायावानों की सफाई हेतु खुली स्वच्छ निकास नालियां अथवा ढकी हुई निकास नालियों की व्यवस्था की जाये, सभी भवनों के मामले में, वर्षा जल के निकास हेतु निकास नालियों की व्यवस्था की जानी है।
- (ग) नियमों के उपबन्धों के अनुसार मानव और पशुओं के अपशिष्ट निस्तारण के लिए मलाश्य की व्यवस्था की जाये।
- (घ) मलाश्य और खुले कुएं अथवा नलकूप के बीच दूरी नियमों में यथा उपबन्धित अनुसार होगी;
- (viii) भू—स्वामी को फार्म हाऊस की मुख्य आवासीय इकाई और उसके अनुषंगी भाग के इर्द—गिर्द चार दीवारी के निर्माण की अनुमित दी जायेगी तथा फार्म के शेष क्षेत्र के इर्द—गिर्द कंटीली तारों वाली बाड़ लगाने की अनुमित होगी।
- (ix) केन्द्रीय भूजल बोर्ड द्वारा यथा घोषित अत्यधिक शोषित अथवा सकंटमय क्षेत्र से भिन्न क्षेत्र में फार्म हाऊस की स्थापना हेतु भूमि उपयोग में परिवर्तन की अनुमति पर विचार किया जायेगा :

परन्तु सरकार कृषि अंचल के उचित उपयोगिता के लिए राज्य सरकार/राज्य अभिकरण द्वारा प्रायोजित किसी स्कीम के लिए फार्म के न्यूनतम आकार में संशोधन कर सकती है।

XX. सूचना प्रौद्योगिकी इकाईयों और साईबर पार्कों / साईबर शहरों के लिए उपबन्ध:-

(i) अवस्थिति:-

- (क) सूचना प्रौद्योगिकी इकाईयां केवल औद्योगिक क्षेत्र/औद्योगिक अंचल में अवस्थित होंगी;
- (ख) साईबर पार्क / सूचना प्रौद्योगिकी पार्क एकीकृत विकास के रूप में सेक्टर सड़क के साथ लगते हुए या तो औद्योगिक क्षेत्र या औद्योगिक अंचल में अवस्थित होंगे। यद्यपि, ऐसे पार्कों में किन्हीं विनिर्माण इकाईयों को अनुज्ञात नहीं किया जाएगा।
- (ग) साईबर शहर:- ऐसी सुविधा की अवस्थिति सरकार द्वारा सुनिश्चित की जाएगी।

(ii) आकार

क्रम संख्या	प्रकार	आकार
1	सूचना प्रौद्योगिकी औद्योगिक इकाई	1 से 5 एकड़
2	साईबर पार्क / सूचना प्रौद्योगिकी पार्क	5 से 15 एकड़
3	साईबर सिटी	न्यूनतम ५० एकड़

(iii) विविध:-

(I) पार्किंग:-

पार्किंग, समय समय पर, यथा संशोधित हरियाणा भवन संहिता, 2017 के उपबन्धों के अनुसार होगी।

(II) अन्य क्रियाकलाप :-

- (क) आनुषंगिक वाणिज्यिक क्रियाकलाप जैसे बैंक, रैस्टोरैन्ट, इंश्योरैंस कार्यालय इत्यादि, को साईबर पार्क/सूचना प्रौद्योगिकी पार्क के कुल क्षेत्र के 4 प्रतिशत निर्बन्धन के अधीन रहते हुए अनुमित दी जायेगी;
- (ख) साईबर शहर के क्षेत्र का केवल 5 प्रतिशत क्षेत्र वर्ग आवास के लिए अनुमत किया जायेगा तथा इस साईबर शहर का कुल क्षेत्र 4 प्रतिशत वाणिज्यिक/संस्थागत उपयोगों के लिए अनुमत किया जायेगा
- (ग) साईबर शहर में रिहायशी प्लाटिड विकास की अनुमति नहीं दी जायेगी;
- (घ) किसी साईबर शहर परियोजना के लिए यदि कृषि अंचल में अनुज्ञात हो, तो उद्यमी जल–आपूर्ति तथा अन्य सुविधाओं जैसे मल जलनिस्तारण/निकास नालिया इत्यादि का प्रबन्ध करेगा।
- (III) सरकार, कोई अन्य शर्त अधिरोपित कर सकती है जैसा समय–समय पर आवश्यक समझे।

XXI. संचार टावरों की स्थापना :-

नियंत्रित क्षेत्र के भीतर संचार टावर स्थापित करने के लिए अनुमति, समय—समय पर यथा संशोधित विभाग की पालिसी/अनुदेशों दिनांक 10 मार्च, 2015 के अनुसार प्रदान की जाएगी।

XXII. भूकंम्पीय आपदा से सुरक्षा :-

विकास योजना क्षेत्र में सभी विकास/भवन कियाकलापों को भारतीय मानक आई.एस. 1893:2002, के भूकम्पीय क्षेत्र मानचित्र के अनुसार, विकास योजना क्षेत्र में भूकम्पीय कियाकलापों की तीव्रता को ध्यान में रखते हुए किया जाएगा। उपरोक्त को ध्यान में रखते हुए, समग्र शहरी विकास, घटना की उक्त तीव्रता की सम्भाव्यता हेतु सुरक्षा के लिए जांच की जाएगी तथा भवनों तथा अवसंरचना में अपेक्षित भूकम्पीय प्रतिरोध जो आवश्यक पाया जाए, उन्नत किया जाएगा।

XXIII. नियंत्रित क्षेत्र में स्थित ईंटों के मट्टे:-

नियंत्रित क्षेत्रों में स्थित ईंट भट्टे, सक्षम प्राधिकारी द्वारा समय—समय पर जारी सम्बंधित नीति/दिशा—निर्देशों के द्वारा शासित होंगे।

XXIV. विकास योजना में ढील:-

सरकार,अत्यन्त किठनाई की दशा में अथवा वास्तविक तिथि से पूर्व निर्मित किसी ढांचे को बचाने के दृष्टिगत ऐसे विकास प्रभारों के भुगतान पर और ऐसी अन्य शर्तों पर, जो वह लगाना उचित समझे, साम्य और न्याय के सिद्धान्तों पर विकास योजना के किसी भी उपबन्ध में ढील दे सकती है।

परिशिष्ट क भूमि उपयोगों का वर्गीकरण

मुख्य कोड	उपकोड	मुख्य वर्ग	उपवर्ग
100		रिहायशी	पड़ोस–पद्धति पर रिहायशी सैक्टर
200		वाणिज्यिक	
	210		परचून व्यवसाय
	220		थोक व्यवसाय
	230		भांडागार और भंडारण
	240		कार्यालय और बैंक जिसमें सरकारी कार्यालय भी शामिल है।
	250		रैस्तरां, होटल तथा अस्थाई बोर्डिंग हाऊस, जिनमें धर्मशाला, पर्यटक गृह आदि जैसे रिहायशी आवास की व्यवस्था वाली सार्वजनिक सहायता संस्थायें भी शामिल हैं
	260		सिनेमा एवं वाणिज्यिक आधार पर लोगों के एकत्रित होने वाले अन्य स्थान
	270		व्यावसायिक स्थापनायें
300		औद्योगिक	
	310		सेवा उद्योग
	320		हल्के उद्योग
	330		व्यापक उद्योग
	340		भारी उद्योग
400		परिवहन तथा संचार	
	410		रेलवे यार्ड, रेलवे स्टेशन तथा साईडिंग
	420		सड़कें, सड़क परिवहन डिपो और पार्किंग क्षेत्र
	430		गोदी तथा घाट
	450		तार कार्यालय, टैलीफोन एक्सचेंज इत्यादि
	460		प्रसारण केन्द्र
	470		दूरदर्शन केन्द्र
500		जन उपयोगितायें	
	510		जल आपूर्ति संस्थापन जिसमें शोधन संयंत्र भी शामिल है
	520		जल निकास और सफाई संस्थापनायें जिनमें मल शोधन सयंत्र तथा निस्तारण संकर्म भी शामिल है
	530		बिजली संयंत्र उपस्टेशन आदि
	540		गैस संस्थापना और गैस कार्य
	550		ठोस अपशिष्ट प्रबन्धन स्थल
600		सार्वजनिक और अर्ध—सार्वजनिक	
	610		सरकारी प्रशासन, केन्द्रीय सचिवालय, जिला कार्यालय, विधि न्यायालय, जेलें, पुलिस थाने, राज्यपाल तथा राष्ट्रपति निवास
	620		शिक्षा, सांस्कृतिक और धार्मिक संस्थायें

मुख्य कोड	उपकोड	मुख्य वर्ग	उ पवर्ग
	630		चिकित्सा तथा स्वास्थ्य संस्थायें
	640		मुख्यतः गैर वाणिज्यिक किस्म के थियेटर, आपेरा, गृह इत्यादि जैसी सांस्कृतिक संस्थायें
	650		रक्षा से सम्बन्धित भूमि
700		खुले स्थान	
	710		खेलकूद मैदान, स्टेडियम, क्रीड़ा मैदान
	720		पार्क
	730		हरित पट्टी, बाग, कृषि वानकी / फूलों की खेती तथा अन्य मनोरंजन संबंधी उपयोग
	740		कब्रिस्तान, शमशान घाट इत्यादि
	750		ईंधन स्टेशन तथा बस क्यू शैल्टर
	760		जल निकाय/झील/जल पुनर्भरण अंचल
	770		मेला मैदान, बहु–उद्वेशीय स्थल
800		कृषि भूमि	
	810		मार्किट गार्डन
	820		फलोद्यान तथा नर्सरियां
	830		प्रधान फसल के अन्तर्गत भूमि
	840		चराई भूमि तथा चरागाहें
	850		वन भूमि
	860		दलदल भूमि
	870		बंजर भूमि
	890		डेरी फार्मिंग
900		विशेष अंचल	इंटिग्रेटिड वे साईड एमिनिटी

परिशिष्ट—ख

मुख्य भूमि उपयोगों के अधीन दी गई अनुमत गतिविधियां, सरकार द्वारा स्वीकृत पालिसी/मापदंडों तथा सैक्टर/कालोनी में सक्षम प्राधिकारी द्वारा स्थल पर यथा अनुमत अनुसार अनुमत की जाएगी।

I. रिहायशी अंचल

- (i) आवासीय
- (ii) सामाजिक,सामुदायिक, धार्मिक और आमोद-प्रमोद गृह
- (iii) जन उपयोगिता भवन
- (iv) शैक्षणिक भवन और सभी प्रकार के विद्यालय और महाविद्यालय, जहाँ आवश्यक हों
- (v) स्वास्थ्य संस्थायें
- (vi) सिनेमा
- (vii) वाणिज्यिक और व्यवसायिक कार्यालय
- (viii) परचून की दुकानें, ढाबे और रैस्तरां
- (ix) स्थानीय सेवा उद्योग
- (x) ईंधन स्टेशन
- (xi) बस स्टाप, तांगा, टैक्सी, स्कूटर तथा ऑटो/रिक्शा स्टैंड
- (xii) नर्सरियां और हरित गृह

- (xiii) रिहायशी उपयोग में अनुषंगी कोई अन्य छोटी-छोटी जरूरतें
- (xiv) सितारा होटल
- (xv) क्लब / सामुदायिक केन्द्र
- (xvi) संचार टावर
- (xvii) अतिथि / बोर्डिंग आवास
- (xviii) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

II. वाणिज्यिक अंचल

- (i) परचून व्यापार
- (ii) थोक व्यापार
- (iii) भांडागार और भंडारण
- (iv) वाणिज्यिक कार्यालय और बैंक
- (v) रैस्तरां तथा अस्थाई आवास गृह जिसमें धर्मशाला और पर्यटक गृह आदि जैसे रिहायशी स्थान प्रदान करने वाले सार्वजनिक सहायता संस्थाएं शामिल हैं
- (vi) सिनेमा, होटल, मोटल तथा वाणिज्यिक आधार पर चलने वाले और लोगों के इकट्ठा होने वाले अन्य स्थान जैसे थियेटर, क्लब, ड्रामा क्लब आदि
- (vii) व्यावसायिक स्थापनायें
- (viii) प्रथम तथा उच्चतर मंजिलों पर निवास
- (ix) स्थानीय सेवा उद्योग
- (x) जन उपयोगिता भवन
- (xi) ईंधन स्टेशन और सर्विस गैरेज
- (xii) माल चढाने और उतारने वाले यार्ड
- (xiii) पार्किंग स्थल, बस स्टाप, टैक्सी, तांगा, आटो / रिक्शा स्टैंड
- (xiv) नगर पार्क
- (xv) संचार टावर
- (xvi) कोई अन्य उपयोग, जिसे सरकारलोकहित में विनिश्चित करे।

III. औद्योगिक अंचल

- (i) हल्के उद्योग
- (ii) मध्यम उद्योग
- (iii) घृणाजनक और परिसंकटमय उद्योग
- (iv) भारी उद्योग
- (v) सर्विस उद्योग
- (vi) भांडागार और भंडारण
- (vii) पार्किंग, माल चढ़ाने और उतारने वाले क्षेत्र
- (viii) ट्रक स्टैंड/बस स्टाप, टैक्सी तांगा और आटो/रिक्शा स्टैंड
- (ix) सेक्टर के कुल क्षेत्र की अधिकतम तीन प्रतिशत की सीमा के अध्यधीन जन उपयोगिता, सामुदायिक भवन, परचून की दुकानें, बैंक, ढाबे, रैस्टोरैन्ट, दो/तीन/पांच सितारा होटल तथा बीमा कार्यालय निम्नानुसार हैं:—

क्रम	सुविधा का	क्षेत्र		मुविधा का क्षेत्र सैक्टर में व		वाणिज्यिक	अधिकतम	फर्श क्षेत्र	पहुँच सड़क
संख्या	नाम	न्यूनतम	अधिकतम	कुल सुविधाएं	घटक	भूतल आच्छादन	अनुपात		
1	ढाबा	500 वर्गमीटर	1000 वर्गमीटर	2	50 वर्गमीटर	40 प्रतिशत	0.40	न्यूनतम 18 मीटर	
2	रैस्टोरैन्ट	1000 वर्गमीटर	2000 वर्गमीटर	2	10 प्रतिशत	30 प्रतिशत	1.50	न्यूनतम 18 मीटर	

3:	दो / तीन सितारा होटल	1.0 एकड	2.5 एकड	2	15 प्रतिशत	30 प्रतिशत	वाणिज्यिक योजनानुसार	न्यूनतम 24 मीटर
4.	पांच सितारा होटल	2.5 एकड	४ एकड़	1	15 प्रतिशत	30 प्रतिशत	वाणिज्यिक योजनानुसार	सेक्टर विभाजक सडक जिस पर सर्विस सड़क का प्रावधान हो।

(x) सर्विस गैरज, बिक्री / प्रदर्शन केन्द्र-एव-सर्विस गैरज का विवरण निम्न अनुसार है:-

क्रम	सुविधा का नाम	क्षेत्र (प	रकड़ में)	वाणिज्यिक घटक	अधिकतम	फर्श क्षेत्र	पहुँच मार्ग	उंचाई
संख्या		न्यूनतम	अधिकतम		भूतल आच्छादन	अनुपात		
1	सर्विस गैरज	0.5	1	शून्य	60 प्रतिशत	1.25	न्यूनतम 18 मीटर या सेक्टर सड़क के साथ प्रस्तावित सर्विस सड़क	18 मीटर
2	बिक्री / प्रदर्शन केन्द्र—एवं— सर्विस गैरज	0.5	2	अनुज्ञेय फर्श क्षेत्र अनुपात का 10 प्रतिशत	60 प्रतिशत	1.25	न्यूनतम १८ मीटर या सेक्टर सड़क के साथ प्रस्तावित सर्विस सड़क	18 मीटर

- टिप्पण.- * वाणिज्यिक घटक के विषय में फीस तथा प्रभार वाणिज्यिक दरों पर उद्गृहीत किए जाएंगे;
 - * विद्यमान / पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिक्री / प्रदर्शन केन्द्र की अनुमित देने हेतु उपरोक्त मानदण्डों को पूरा करने के अध्यधीन विचारा जाएगा।
- (xi) ईंधन स्टेशन तथा सर्विस गैरेजस
- (xii) निदेशक द्वारा अनुमत तरल पैट्रोलियम गैस गोदाम
- (xiii) साईबर पार्क / सूचना प्रौद्योगिकी पार्क / सूचना प्रौद्योगिकी औद्योगिक इकाइयां
- (xiv) स्वास्थ्य सुविधाएं जैसे अस्पताल, औषधालय, नर्सिंग होम तथा क्लीनिकः

क्रम	सुविधा का	क्षेत्र		सैक्टर में	रिहायशी	अधिकतम	फर्श
संख्या	नाम	न्यूनतम	अधिकतम	कुल सुविधाएं	घटक	भूतल आच्छादन	क्षेत्र अनुपात
1.	अस्पताल	2.5 एकड़	5 एकड़	1	15 प्रतिशत	33 प्रतिशत	1.00
2.	औषधालय	1.0 एकड़	1.5 एकड़	1	15 प्रतिशत	33 प्रतिशत	1.00
3.	नर्सिंग होम	250 वर्गमीटर	500 वर्गमीटर	2	शून्य	60 प्रतिशत	1.00
4.	क्लीनिक	250 वर्गमीटर	500 वर्गमीटर	2	शून्य	60 प्रतिशत	1.00

- **टिप्पण.** * वाणिज्यिक घटक के विषय में फीस तथा प्रभार वाणिज्यिक दरों पर उद्गृहीत किए जाएंगे;
 - विद्यमान/पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिक्री/प्रदर्शन केन्द्र कीअनुमित देने हेतु उपरोक्त मानदण्डों को पूरा करने के अध्यधीन विचारा जाएगा।
- (xv) औद्योगिक कालोनी कम से कम 25 एकड़ में होगी। इस क्षेत्र का उपयोग अपर मुख्य सचिव, नगर तथा ग्राम आयोजना विभाग, हरियाणा, चण्डीगढ़ की यथा अद्यतन संशोधित पालिसी संख्या मिसलेनियस 388/पी.ए.(आरबी)/2015/7/16/2006—2टीसीपी, दिनांक प्रथम अक्तूबर, 2015 के अनुसार होगा।
- (xvi) संचार टावर
- (xvii) तैयार मिश्रण कंक्रीट संयत्र, वेट मिश्रण संयत्र, गर्म मिश्रण संयत्र इत्यादि
- (xviii) धर्म कांटा
- (xix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

IV. परिवहन तथा संचार अंचल

- (i) रेलवे यार्ड, रेलवे स्टेशन और साईडिंग
- (ii) परिवहन नगर, सडकें और परिवहन डिपो और पार्किंग क्षेत्र
- (iii) हवाई अड्डा और हवाई स्टेशन

- (iv) दूरभाष केन्द्र
- (v) प्रसारण केन्द्र
- (vi) दूरदर्शन केन्द्र
- (vii) अनुमोदित स्थलों और स्थानों पर कृषि, बागवानी और नर्सरिज
- (viii) ईंधन स्टेशन और सर्विस गैरेज
- (ix) पार्किंग स्थल, बस स्टाप-शैल्टर, टैक्सी, टांगा और ओटो / रिक्शा स्टैंड
- (x) रसद केन्द्रों / कंटेनर यार्डस, अंतिदेशीय कंटेनर डिपो, कंटेनर फेट स्टेशन
- (xi) धर्म कांटा
- (xii) संचार टावर
- (xiii) सेक्टर के कुल क्षेत्र की अधिकतम 20 प्रतिशत की सीमा तक भांडागार
- (xiv) वर्तमान नीति के अनुसार ढाबा।

V. जन उपयोगितायें

- (i) जल सप्लाई, संस्थापनाएं जिसमें शोधन संयंत्र भी शामिल हैं
- (ii) जल निकास और सफाई स्थापनाएं इसमें मलजल शोधन संयंत्र तथा निपटान कार्य भी शामिल हैं
- (iii) विद्युत शक्ति संयंत्र तथा सबस्टेशन जिसमें ग्रिड सब स्टेशन भी शामिल हैं
- (iv) गैस संस्थापनाएं तथा गैस वर्कस
- (v) टोस अपशिष्ट प्रबन्धन स्थल

VI. सार्वजनिक तथा अर्धसार्वजनिक उपयोग अंचल

- (i) सरकारी कार्यालय, सरकारी प्रशासन केन्द्र, सिचवालय और पुलिस थाना
- (ii) शैक्षणिक, सांस्कृतिक और धार्मिक संस्थायें
- (iii) चिकित्सा स्वास्थ्य संस्थायें
- (iv) नागरिक / सांस्कृतिक और सामाजिक संस्थान जैसे थियेटर, ओपेरा हाउस इत्यादि जो मुख्यतः गैर वाणिज्यिक किस्म के हों।
- (v) रक्षा से सम्बन्धित भूमि
- (vi) ढाबा, रेस्टोरेन्ट निम्न अनुसार:-

क्रम	सुविधा	9		सैक्टर में कुल	वाणिज्यिक	अधिकतम भूतल	फर्श क्षेत्र	
संख्या	का नाम	न्यूनतम	अधिकतम	सुविधाओं की संख्या	घटक	आच्छादन	अनुपात	
1	ढाबा	500 वर्गमीटर	1000 वर्गमीटर	2	50 वर्गमीटर	50 प्रतिशत	40 प्रतिशत	
2	रैस्टोरैन्ट	1000 वर्गमीटर	2000 वर्गमीटर	2	10 प्रतिशत	30 प्रतिशत	150 प्रतिशत	

- (vii) संचार टावर
- (viii) ईंधन स्टेशन
- (ix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

VII. खुले स्थान

- (i) खेलकूद मैदान, स्टेडियम तथा कीड़ा मैदान
- (ii) पार्क,हरित पट्टी, बाग, कृषि वानकी / फूलों की खेती तथा अन्य मनोरंजन संबंधी उपयोग
- (iii) कब्रिस्तान, शमशान घाटइत्यादि

- (iv) निदेशक की अनुमित से सड़कों के साथ ईंधनस्टेशन, बस पंक्ति / शैल्टर
- (v) अनुसूचित सड़कों तथा मुख्य सड़कों के साथ हरित पट्टी में सार्वजनिक उपयोगिता सेवाएं जैसे इलैक्ट्रक ग्रिड स्टेशन, प्रेषण लाईनें, संचार लाईनें, जल आपूर्ति लाइनें सीवरेज लाईनें, ड्रैनेज लाईनें।
- (vi) जल निकाय/ झील/ जल पुर्नभरण क्षेत्र
- (vii) संचार टावर
- (viii) मेला स्थल तथा बहु उपयोगी मैदान
- (ix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

VIII. कृषि अंचल

- (i) कृषि, बागवानी, डेरी और मूर्गी पालन
- (ii) आबादी देह के भीतर गांव घर
- (iii) अंचल विनियम XIX में यथा निर्धारित निर्बन्धनों के अध्यधीन, आबादी देह के बाहर फार्म हाऊस
- (iv) वन रोपण विकास तथा मनोरंजन के लिए उसका कोई भाग
- (v) आबादी देह के समीप वर्तमान गांव का विस्तार यदि यह परियोजना, केन्द्र सरकार या राज्य सरकार द्वारा अनुमोदित या प्रायोजित हो
- (vi) दुग्ध अवशीतन केन्द्र और पैस्चयूरीकरण केन्द्र
- (vii) बस अड्डा और रेलवे स्टेशन
- (viii) अनिवार्य भवनों सहित हवाई अड्डा
- (ix) बेतार केन्द्र
- (x) निदेशक द्वारा अनुमोदित स्थलों पर अनाज गोदाम, भंडारण स्थल
- (xi) मौसम कार्यालय
- (xii) भू-जल निकास और सिंचाई, पन बिजली कार्य और सिंचाई के लिए नलकूप
- (xiii) टेलीफोन और बिजली प्रेषण लाईनें ओर खम्भे
- (xiv) खनन तथा उत्खनन कार्य जिसमें चूना तथा ईंटों के भट्टे, पत्थर, खदानें और क्रेशिंग शामिल है, जो नियमों तथा अनुमोदित स्थल पर, के अधीन रहते हुए हैं।
- (xv) शमशान और कब्रिस्तान
- (xvi) ईंधन स्टेशन और सर्विस गैरेज
- (xvii) नवीकरणीय और गैर नवीकरणीय ऊर्जा शक्ति संयंत्र
- (xviii) निदेशक के अनुमतसे तरल पैट्रोलियम पदार्थ भण्डारण गोदाम
- (xix) लघु उद्योग औद्योगिक इकाइयों को निम्नलिखित शर्तों की पूर्ति के अधीन रहते हुए अनुमित दी जाएगी, बशर्ते ऐसा स्थल, रक्षा संस्थापनाओं, यदि कोई हो, के इर्द–गिर्द रक्षा संकर्म अधिनियम, 1903 (1903 का केन्द्रीय अधिनियम 7) के अधीन वर्जित पट्टी तथा अनुसूचित सड़कों, राष्ट्रीय राजमार्गों तथा राज्य राजमार्गों से भिन्न न्युनतम 30 फट चौड़े राजस्व रास्ते/सार्वजनिक सड़क होना चाहिए:—

अंचल	मानदं	मानदंड						
मध्यम संभावित क्षेत्र	शहरीकरण क्षेत्र से 2 किमी के भीतर (परिधीय सड़कों को छोड़कर, यदि शहरी सीमा के साथ–साथ प्रस्तावित)	शहरीकरण क्षेत्र से 2 किमी से अधि (परिधीय सड़कों को छोड़कर, यदि शह सीमा के साथ—साथ प्रस्तावित)						
	एस.एस.आई. की गैर—प्रदूषणकारी हरी, नारंगी श्रेणी इकाइयां अधिकतम 5 एकड़	किसी भी क्षेत्र की ग्रीन और नारंगी श्रे इकाइयां						
ख. पहुँच मा	नदंड							
मध्यम और निम्न संभावित	औद्योगिक उपयोग के लिए कृषि क्षेत्र में भूि न्यूनतम 30 फीट चौड़ा राजस्व सड़क/सार्क तथापि, यदि भूमि उपयोग की औद्योगिक प	जनिक सड़क पर विचार किया जाएगा						

क्षेत्र मार्ग/सार्वजनिक सड़क पर दी गई है, तो उस सड़क पर भूमि उपयोग परिवर्तन अनुमित के लिए आवेदन, इस शर्त के अध्यधीन विचारा जाएगा कि आवेदन करने वाले साइट के सामने 6 कर्म (33 फुट) परियोजना प्रत्यार्तक दर्शाता है कि 1 करम (5.5 फुट) चौड़ी पट्टी ग्राम पंचायत/स्थानीय प्राधिकरण को हिबबानैमा/उपहार के माध्यम से विस्तृत पट्टी के रूप में बनाने के लिए लागू की गई भूमि ।

अनुसूचित सड़कों, राष्ट्रीय राजमार्ग और राज्य राजमार्ग के अलावा सार्वजनिक सड़क / रास्ता जिसकी चौड़ाई 30 फीट से कम है, पर गैर प्रदूषणकारी मध्यम और बड़े पैमाने पर कृषि आधारित उद्योग, बशर्ते कि ऐसी स्थापना, यदि कोई हो, के लिए यथा लागू सुरक्षा स्थापना के आसपास निर्बन्धित पट्टी के भीतर नहीं होना चाहिए ।

(xxi) निर्बन्धित / हरित पट्टी के बाहर क्षेत्र में राष्ट्रीय राजमार्ग / अनुसूचित सड़कों के साथ ढाबे, बैंक्विट हाल, लघु रैस्टोरेन्ट, मोटल, होटल रिर्सोटज तथा मन बहलाव पार्क / थीम पार्क निम्न अनुसार होंगेः

क्रम	अनुज्ञेय गतिविधि	क्षेत्र	ī	वाणिज्यक	अधिकतम भूतल	फर्श क्षेत्र
संख्या		न्यूनतम	अधिकतम	घटक	आच्छादन	अनुपात
1	ढाबा	1000 वर्ग मीटर	1.0 एकड़	50 वर्ग मीटर	40 प्रतिशत	40 प्रतिशत
2	रैस्टोरैन्ट	2000 वर्ग मीटर	1.0 एकड़	15 प्रतिशत	30 प्रतिशत	150 प्रतिशत
3	बैंकट सुविधाओं सहित मोटल	2.5 एकड़	5 एकड़	15 प्रतिशत	30 प्रतिशत	150 प्रतिशत
4	रिर्सोट	4.0 एकड़	10 एकड़	15 प्रतिशत	30 प्रतिशत	150 प्रतिशत
5	मन–बहलाव पार्क / थीम पार्क	2.5 एकड़	10 एकड़	15 प्रतिशत	30 प्रतिशत	50 प्रतिशत

परन्तु पहुंच अनुज्ञा, यदि स्थल राष्ट्रीय राजमार्ग पर अवस्थित है, तो भारतीय राष्ट्रीय राजमार्ग प्राधिकरण तथा यदि स्थल अनुसूचित सड़क पर अवस्थित है, तो कार्यकारी अभियन्ता, लोक निर्माण विभाग (भवन तथा सड़कें) से प्राप्त की गई है।

(xxii) **बेंक्विट हालः**

अनुज्ञेय अचंल	कृषि अचंल
पहुंच	1. पहुंच सड़क की न्यूनतम चौडाई 18 मीटर होनी चाहिए।
	2. यदि स्थल अनुसूचित सड़क पर स्थित हो तो पहुंच अनुज्ञा कार्यकारी अभिंयता, लोक निर्माण विभाग (भवन तथा सड़कें) से अपेक्षित है।
	3. राष्ट्रीय राजमार्ग से भी पहुंच विचारी जा सकती है, यदि स्थल चौराहा / पहुंच मार्ग से न्यूनतम दूरी मानक पूरा करता हो तथा न्यूनतम ७ मीटर चौड़ी सेवा सड़क पर अवस्थित हो या आवेदक भारतीय राष्ट्रीय राजमार्ग
	प्राधिकरण से पहुंच की पूर्व अनुज्ञा प्रस्तुत करता है।
अपेक्षित क्षेत्र	न्यूनतम २.५ एकड्
	अधिकतम 5.00 एकड़
फर्श क्षेत्र अनुपात	50 प्रतिशत
भूतल आच्छादन	30 प्रतिशत
परिवर्तन प्रभार	वाणिज्यिक उपयोग के लिए विहित दर का 50 प्रतिशत
फर्श क्षेत्र अनुपात के	उपहार दुकान, एस टी डी बूथ, खिलौना केन्द्र तथा फूलों की दूकानें इत्यादि के
भीतर अनुज्ञेय	लिए अनुमत फर्श क्षेत्र अनुपात का 10 प्रतिशत
अनुषांगिक उपयोग	
पार्किंग	स्थल क्षेत्र का न्यूनतम 25 प्रतिशत

टिप्पण:—नगरपालिका सीमा के भीतर विवाह महल / बँक्विट हॉल की व्यवस्था शहरी स्थानीय निकायविभाग द्वारा अनुमोदित तथा समय समय पर संशोधित नीति के अनुसार होगा ।

(xxiii) माईक्रोवेव टावर/स्टेशन, भूकम्प केन्द्र तथा दूरसंचार केन्द्र

- (xxiv) संचार टावर
- (xxv) सरकार या सरकारी एजेंसी द्वारा संविदा अथवा कार्य हेतु अल्पावधि के लिए लगाए जाने वाले तैयार मिश्रण कंकीट संयंत्र, वेट मिश्रण संयंत्र, गर्म मिश्रण संयंत्र इत्यादि।
- (xxvi) सर्विस गैरज, बिक्री / प्रदर्शन केन्द्र-एवं-सर्विस गैरज का विवरण निम्न अनुसार है:

क्रम	सुविधा का	क्षेत्र (एकड़ में)	वाणिज्यिक	अधिकतम भूतल		पहुंच मार्ग	उंचाई
संख्या	नाम	न्यूनतम	अधिकतम	घटक	आच्छादन	अनुपात		
1	सर्विस गैरज	0.5	1	शून्य	60 प्रतिशत	1.25	18 मीटर या सेक्टर सड़क के साथ सर्विस सड़क	18 मीटर
2	बिक्री / प्रदर्शन केन्द्र–एवं– सर्विस गैरज बिक्री प्रदर्शन केन्द्र	0.5		अनुज्ञेय फर्श क्षेत्र अनुपात का १० प्रतिशत	60 प्रतिशत	1.25	18 मीटर या सेक्टर सड़क के साथ सर्विस सड़क	18 मीटर

टिप्पण.— * वाणिज्यिक घटक के विषय में फीस तथा प्रभार वाणिज्यिक दरों पर उद्गृहीत किए जाएंगे;

- * विद्यमान/पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिकी/प्रदर्शन केन्द्र की अनुमति देने हेतु उपरोक्त मानदण्डों को पूरा करने के अध्यधीन विचारा जाएगा।
- (xxvii) धर्म कांटा
- (xxviii) शैक्षणिक संस्थान
- (xxix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

IX. विशेष अंचल

वे साईड एमिनिटिज जिसमें शामिल है सेवाएं जैसे पार्किंग, तेल भराव, सर्विस तथा मुरम्मत , दूरभाष और दूर संचार, ढाबा / रैस्टोरेंट तथा मोटल, दवाईयां, पुलिस, नागरिक सुविधा, मनोरंजन, बैंकिंग (ए.टी.एम.) तथा राजमार्गीय यातायात को सुविधाजनक बनाने वाली अन्य आवश्यक सेवाएं।

X. बिल्कुल निषिद्ध उपयोग

उचित अनुज्ञप्ति के बिना पैट्रोलियम और अन्य प्रज्जवलनीय सामग्री का भंडारण

परिशिष्ट-1

सूचना प्रौद्योगिकी उद्योग के स्कोप/परिमाषा में सम्मिलित किए गए उद्योगों की श्रेणियां

(क) कम्प्यूटर डिवाईसिज के अन्तर्गत:

डैस्क्टाप

पर्सनल कम्पयूटरर्स

सरवर्स

वर्क स्टेशन

नोडस

टरमिनलस

नैटवर्क पी.सी.

होम पी.सी.

लैपटॉप कम्पयूटरर्स

नोट बुक कम्पयूटरर्स

पामटॉप कम्पयूटरर्स / पी.डी.ए.

(ख) नैटवर्क कंट्रोलर कॉर्ड / मेमोरी के अन्तर्गत :

नैटवर्क इन्टरफेस कार्ड (एन.आई.सी.)

एडोप्टर इथरनेट / पी.सी.आई. / ई.आई.एस.ए. / कोम्बो / पी.सी.एम.आई.सी.ए.

एस.आई.एम.एम.मेमारी

डी.आई.एम.एम.मेमोरी

सैन्ट्रल प्रोसैंसिग यूनिट(सी.पी.यू.)

कन्ट्रोलर एस.सी.एस.आई. / ऐरे

प्रोसैसर का प्रौसेसर/प्रोसैसर पावर मोडयूल/अपग्रेड

(ग) स्टोरेज यूनिटस के अन्तर्गत:

हार्ड डिसक ड्राईवस/हार्ड ड्राईवस

आर.ए.आई.डी. डिवाईसिस एवं उसके कन्ट्रोलर

फलोपी डिस्क ड्राईव

सी.डी.रोम डाईव

टेप ड्राईवस डी.एल.टी. ड्राईवस/डी.ए.टी.

आपटिकल डिस्क ड्राईव

अन्य डिजीटल स्टोरेज डिवाईज

(घ) अन्य :

की बोर्ड

मोनीटर

माऊस

मल्टीमीडिया किट्स

(ड.) प्रिन्टर तथा आऊटपुट डिवाईसिस के अन्तर्गत :

डोट मैट्रिक्स

लेजरजेट

इन्कजैट

डेस्कजैट

एल.ई.डी. प्रिन्टर्स

लाईन प्रिन्टर्स

प्लाटर्स

पास बुक प्रिन्टर्स

(च) नेटवर्किंग उत्पाद के अन्तर्गतः

हब्ज

रूटर्स

स्विचिस

कोन्सनट्रेटर्स

ट्रांसरिसिवर्स

(छ) सोफटवेयर के अन्तर्गत :

एप्लीकेशन्स साफटवेयर

आपरेटिंग सिस्टम

मिडल वेयर / फर्म वेयर

(ज) कम्पयूटर सिस्टम के लिए लगने वाली पावर सप्लाई के अन्तर्गत :

स्विच मोड पावर सप्लाई अनइन्टरप्टिड पावर सप्लाई

(झ) नेटवर्किंग/केबलिंग तथा उससे संबंधित उपकरण :

(सूचना प्रौद्योगिकी उद्योग से संबंधित)

फाईबर केबल

कोपर केबल

केबल्स

कनैक्टर्स, टरिमनल ब्लाक

जैक पैनल्स, पैच कोर्ड

माऊटिंग कोर्ड / वायरिंग ब्लाक

सरफेस माउंट बक्से

(স) কন্তযুদ্মৰল্ম के अन्तर्गत :

सी.डी.रोम / कम्पैक्ट डिस्क

फलोपी डिस्क

टैप्स डी.ए.टी./डी.एल.टी.

रिबन्स

टोनर्स

इन्कजैट कारटेजिस

आऊटपुट डिवाईसिस को लगने वाली इंक

(ट) इलैक्ट्रोनिक कम्पोनेन्ट :

प्रिंटिड सर्किट बोर्ड/पापुलेटिड पी.सी.बी.

प्रिंटिड सर्किट बोर्ड / पी.सी.बी.

ट्रांजिस्टर्स

इन्टैग्रेटिड सर्किट्स/आई.सी.

डायोड्स/थाईरिस्टर/एल.ई.डी.

रेसिस्टर्स

केपेसिटर्स

स्विचिस (ऑन/ऑफ, पुश बटन, रोकर्स इत्यादि)

प्लगस / सोकेट्स / रिलेज

मेगनेटिक हेड्स, प्रिन्ट हैड्स

कनेक्टर

माईक्रोफोन्स / स्पीकर्स

फयूजिस

(ठ) टैलीकम्यूनिकेशन इक्वीपमेन्ट के अन्तर्गत :

टैलीफोन

विडियो फोन

फेसी माईल मशीन / फैक्स कार्ड

टैली प्रिन्टर्स / टैलेक्स मशीन

पी.ए.बी.एक्स. / ई.पी.ए.बी.एक्स. / आर.ए.एक्स. / एम.ए.एक्स. टैलीफोन एक्सचैंज मल्टीप्लेक्सर्स / म्यूजिस

मोडम्स

टैलीफोन आन्सरिंग मशीन

टैलीकम्युनिकेशन्स स्वीचिंग एपरेटर्स

एन्टेना तथा मास्ट

वायरलैस डेटाकोम इक्वीपमेन्ट

रिसीविंग इक्वीपमेन्ट लाईक पेजर्स, मोबाईल/सैल्यूलर फोन इत्यादि

वी.एस.ए.टीज.

वीडियो कोनफोरेंसिंग इक्वीपमेन्ट'

वीडियो एवं डिजिटल सिंगनलिंग के लिए लगने वाले सैट टाप बक्से के अन्तर्गत

(ढ) सूचना प्रौद्योगिकी को समर्थ बनाने वाली सेवायें वह व्यवसायिक किया तथा सेवायें है जिसके अन्तिम उत्पाद / सेवायें जिनको :

- भारत से बाहर वितरित करने के लिए
- संचार-जाल के लिए वितरित करने के लिए; तथा
- या तो बाहरी ठेके (बाहरी स्त्रोत) या उस कम्पनी के सुदूर गौण द्वारा उपलब्ध किया हुआ (बाहर अवस्थित

टिप्पण :--

सेवाएं जो इनमें शामिल नहीं हैं, :

- सुदूर उत्पादन / विनिर्माण इकाइयां
- कम्पनियों के निगमित कार्यालय अथवा उनकी स्थानीय शाखाएं
- इन्टरनैट पर वास्तविक व्यवसाय
 निम्नलिखित सेवाएं जो उपरोक्त दिये गये मानदण्ड पूर्ण करती हैं, सिम्मिलित होंगी :
 - (i) बैंक ऑफिस आप्रेशन्स
 - (ii) काल सैन्टरज
 - (iii) कोन्टैन्ट डिवैल्पमैन्ट अथवा एनीमेशन
 - (iv) डाटा प्रोसैसिंग
 - (v) अभियान्त्रिकी तथा रचना
 - (vi) ज्योग्राफिक इन्फोरमेशन सिस्टम सर्विसिज
 - (vii) मानव संसाधन सेवायें
 - (viii) बीमा दावा प्रोसेसिंग
 - (ix) लीगल डाटा बेस
 - (x) मैडीकल ट्रान्सक्रिप्शन
 - (xi) पे-रोल
 - (xii) सुदूर रख-रखाव
 - (xiii) राजस्व लेखाकरण
 - (xiv) स्पोर्ट सैन्टरज तथा
 - (xv) वैब-साईट सर्विसेज

एस. एन. रॉय, अपर मुख्य सचिव, हरियाणा सरकार, शहरी स्थानीय निकाय विभाग। अपूर्व कुमार सिंह, प्रधान सचिव, हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग।

HARYANA GOVERNMENT

TOWN AND COUNTRY PLANNING DEPARTMENT

AND

URBAN LOCAL BODIES DEPARTMENT

Notification

The 18th November, 2020

No.CCP(NCR)/YNR/DDP-2041/2020/1542.- Whereas, the Draft Development Plan-2021 A.D of Yamuna Nagar - Jagadhri was published in the Official Gazette vide Haryana Government, Town and Country Planning Department, notification No. CCP(NCR)/YCA-1/2005/36, dated the 14th January, 2005 for a projected population of 6.88 lacs for the Controlled Areas notified on the 6th March, 1965 and the 29th May, 1997. The Development Plan was revised to incorporate the alignment of the proposed Dadupur-Nalvi Canal as the same was passing through the sectors proposed in the development plan. Besides, there is a scope of improvement in the published Draft Development Plan in terms of population density, population projections, exploitation of canal fronts and in allocation of land uses. Accordingly, it has been revised to accommodate the population of 11,50,000 persons by 2021 AD. The Revised Draft Development Plan-2021 AD was published in the Official Gazette vide Haryana Government, Town and Country Planning Department, notification No. CCP(NCR)/YCA-1/RDDP/2006/3588, dated the 7th December, 2006.

And whereas, the above said Revised Draft Development Plan 2021AD could not be finalized on account of following developments taken place from time to time:

- (a) the Additional Controlled Area-III was notified vide Haryana Government Gazette notification no. CCP (NCR)/YN(ACA-III)/A/2007/422, dated the 9th February, 2007 around Municipal Council of Yamuna Nagar-Jagadhri;
- (b) notification of Municipal Corporation, Yamuna Nagar vide Haryana Government Gazette, notification No. 18/2/2010-3 C1, dated the 17th March, 2010;
- (c) decision taken by the Government in the year 2009 to revise all the Development Plans of the State to increase the sector density from 80 PPA to 100 PPA and from 100 PPA to 120 PPA.
- (d) to introduce enabling provisions relating to new policy provisions of the Department viz.Affordable Housing Policy, New Integrated Licencing Policy, Deen Dayal Jan Awas Yojna, Haryana Building Code, 2017 etc.
- (e) to incorporate the new alignment of NH-344 (erastwhile NH-73) connecting Saharanpur-Yamunanagar-Panchkula.
- (f) directions regarding preparation of Development Plans keeping in view the satellite imageries so as to ensure plan proposals in conformity with ground realities.
- (g) announcement of Hon'ble CM regarding development of Timber Market as Commercial Sector and Transport and Communication zone.
- (h) notification issued by Irrigation and Water Resource Department, Haryana Government on the 3rd August, 2018 to denotify the area acquired for Dadupur Nalvi Canal.
- (i) requirement of improved connectivity between the southern and northern sectors of the Development Plan.

And whereas, the Draft Development Plan 2031 AD for Yamuna Nagar-Jagadhri was placed before the District Level Committee (DLC) in the meeting held on the 30th July, 2019 and the plan was approved by the District Level Committee with the following observation/suggestions: -

- (i) The Development Plan should be prepared for at least 20 years and as it's already 2019, therefore, it should be planned for 2041AD instead of 2031AD.
- (ii) Yamuna Nagar-Jagadhri is a pre-eminent investment destination and has a potential to facilitate a balanced regional and sustainable development, capabilities for adoption of innovation & technology along with skill development and can generate employment opportunities in the District. The Metal Utensil Cluster, Jagadhri and Plywood Cluster, Yamuna Nagar are the two main traditional market leaders in the district which concentrates in small and medium scale units and these clusters have not been able to expand and achieve next level of growth due to non-availability of conforming land. These two traditional clusters have been specifically identified for special focus in the Enterprises Promotion Policy, 2015 introduced by the Government. As per the policy, these clusters need to be repositioned to increase their competitiveness and to regain their lost leadership position. The policy essentially focuses on the regional context and to promote the industrial growth which is peculiar to a certain region. It will

attract investment in region and will create a conducive environment for local, foreign investors and corporate that will also benefit the State Exchequer. Hence, being the generic industrial town and in order to strengthen the industrial growth, Yamuna Nagar-Jagadhri development plan should envisage prominent industrial zones separately for Yamuna Nagar & Jagadhri and the area for industrial use should be increased upto 30% of the urbanisable limit. The new Industrial Zone should be planned near existing Haryana State Industrial and Infrastructure Development Corporation Industrial estate in Manakpur along the National Highway-907 (Jagadhri-Paonta Sahib Road), and the area between the Southern Sector road V2(d) and the existing outer peripheral road i.e. National Highway-344 and also along the State Highway-6A.

- (iii) The decadal population growth for the year 2021 has been projected to 82%, which seems to be on a higher side and a revised realistic approach to project the decadal growth upto 2041AD may be adopted. Hence, while increasing the industrial areas in the development plan to accommodate the floating population and migrants along with increased industrial area, the development plan should be prepared for the prospective year 2041 AD instead of 2031 AD.
- (iv) The committee agreed to the suggestion of Director, Town and Country Planning, Haryana to incorporate the provision for "Integrated Wayside Amenities Hub" along National Highways / State Highways. Such amenities should be located at frequent intervals across major roadways, providing basic services and amenities, to ensure safe and convenient journey for long-distance travelers. Most importantly, it would reduce the incidence of accidents and improve road safety, by providing drivers (especially truckers) a comfortable place to rest.
- (v) The committee has also pointed out that Sector-6 at present is thickly built-up and completely occupied with residential colonies, which has been proposed as industrial sector and hence the use of the same may be changed to residential instead of industrial.
- (vi) The committee also pointed out that the Dedicated Freight Corridor Corporation of India Ltd has already commissioned the work of Eastern Dedicated Freight Corridor which is passing through District Yamuna Nagar and the same may also be incorporated in the Development Plan.
- (vii) Further, it was pointed out by the Executive Engineer, Irrigation Department that the proposal for expansion of the Western Yamuna Canal for the stretch passing through the District has already been submitted to the Government and is likely to be approved in future. The 30 metre wide road as proposed in the plan is not feasible and hence, it was decided by the committee that the green space/ belt may be proposed instead of 30 metre wide road in the Development Plan.
- (viii) Further, the committee deliberated over the proposal of 30 metre wide road on the Southern side of Dadupur-Nalvi Canal, wherein a 20 metre wide road has already been constructed by Public Works (B&R) Department connecting Jagadhri Chhachhrauli road to Jagadhri Ambala road. The 20 metre wide road has been constructed in the right of way of Dadupur-Nalvi Canal which stands de-notified partly by the Government. However, the portion of Canal falling between the revenue estate of village Bhukri and Bhatauli which also falls in the urbanisable limit of the Development Plan has not been denotified except the negligible area which was acquired in the year 2004 onwards. Moreover, the Southern side of the Canal is thickly built-up and no further space is available even for the expansion of proposed 30 metre wide Sector dividing road and this Sector dividing road may be re-aligned in the right of way of Dadupur-Nalvi Canal superimposing the already existing 20 metre wide road by Public Works (B&R) Department towards the Northern side of the present alignment. Hence, it was decided by the committee that 45 metre wide Sector dividing road may be proposed in the right of way of Dadupur-Nalvi Canal including the existing PWD (B&R) road as all the Sector dividing roads are being proposed as 45 metre wide.

Whereas, the suggestion/ observation of Draft Development Plan 2031 AD for Yamuna Nagar-Jagadhri was then placed before the District Planning Committee (DPC) (constituted under sub-section (1) of section 203 B of the Haryana Municipal Act, 1973 (24 of 1973), read with rule 3 of the Haryana Constitution of District Planning Committee Rules, 1997 as mandated under article 243 ZD of the Constitution) in its meeting held on the 13th August, 2019. All the members of District Planning Committee (DPC) consented by the recommendations as suggested by the District Level Committee and appraised the proposal of Draft Development Plan 2041 AD for Yamuna Nagar-Jagadhri for its further approval from the 'State Level Committee'.

And whereas all the suggestions of the District Planning Committee/District Level Committeewere incorporated in the Plan and it was placed before the State Level Committee under the Chairmanship of Hon'ble Chief Minister, Haryana in the meeting held on the 3rdSeptember, 2019. The Committee accepted all the suggestions made by District Planning Committee/District Level Committee and approved the following: -

- (i) Prepare Draft Development Plan for 2041 AD instead of 2031AD.
- (ii) Increase Industrial area (1808 hectares as industrial area added in form of 6 new industrial sectors along NH-907 and 9 new industrial sectors along NH-344).
- (iii) A new Sector proposed for Transport and Communication zone due to the addition of new industrial sectors
- (iv) Provision for "Integrated Wayside Amenities Hub" with 5-10 acre after every 20 kilometre stretch along the highway/major roads.
- (v) 30 metre wide green belt along Western Jamuna Canal on both sides.
- (vi) 30 metre wide road along Dadupur-Nalvi Canal to be shifted in ROW of Dadupur-Nalvi Canal with 45m width.
- (vii) Incorporation of Eastern Dedicated Freight Corridor.
- (viii) Population for the year 2041 has been re-projected to 15,24,200 persons.
- (ix) To include the area around village Buria Jagir in the development plan after notifying the controlled area.

And whereas the decisions of State Level Committee have been complied with by incorporating the same in the Draft Development Plan 2041AD of Yamuna Nagar-Jagadhri;

Now, therefore, in exercise of the powers conferred by sub-section (5) of section 346 of Municipal Municipal Corporation Act, 1994 (16 of 1994) and Sub-Section (4) of Section 5 of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963), the Governor of Haryana hereby publishes the Draft Development Plan 2041 AD for Yamuna Nagar-Jagadhri along with restrictions and conditions as given in Annexure A and B proposed to be made applicable to the controlled areas specified in Annexure-B.

Notice is hereby given that the Draft Development Plan shall be taken into consideration by the Government on or after expiry of a period of thirty days from the date of publication of this notification in the Official Gazette together with objections and suggestions, if any, which may be received by the Director, Urban Local Bodies Department, Haryana, Bays No. 11-14, Sector 4, Panchkula, for the area falling within Municipal Corporation limit and Director, Town and Country Planning Department, Haryana, 2nd Floor, Block A, Nagar Yojna Bhawan, Plot No. 3, Sector 18 A, Madhya Marg, Chandigarh for the area falling outside Municipal Corporation limit, from any person, in writing, with respect to the Draft Development Plan, before the expiry of the period so specified.

Drawings

- 1. Existing Land Use Plan bearing Drawing No. DTP(A) 1172/65 (already published vide Punjab Government, notification No. 3827-2TCP-65/4550, dated the 31st January, 1996 in Punjab Government extra Ordinary Gazette, dated the 22nd March, 1966.)
- 2. Existing Land Use Plan bearing Drawing No. DTP(Y)97/98, dated the 27th July, 1998 (already published vide Haryana Government Gazette, notification No.CCP(NCR)/YCA-1/2005/36, dated the 14th January, 2005 on 25th January, 2005.)
- 3. Existing Land Use Plan bearing Drawing No. DTP(Y) 270/2010, dated the 17th September, 2010.
- 4. Existing Land Use Plan bearing Drawing No. DTP(Y) 85/2020, dated the 23rd July, 2020.
- 5. Draft Development Plan-2041 AD for Yamuna Nagar-Jagadhri bearing Drawing No. DTP(Y)86/2020, dated the 23rd July, 2020.

Annexure-A

Explanatory Note on the Draft Development Plan 2041 AD of Yamuna Nagar-Jagadhri for controlled area and additional controlled areas.

I. Historical Background:

Yamuna Nagar is the second-largest Urban Centre of Haryana after Faridabad. It has been considered as an urban agglomeration (U.A) in 1991 census that consists of three distinct Urban Settlements namely Jagadhri, Jagadhri Workshop, and Yamuna Nagar. The town is known for the cluster of plywood units, paper industries and also known for providing fine timber to larger industries. Jagadhri is an important historical town and its old name was Gangadhri. Although, this town had been destroyed by Nadir Shah, but during the Sikh period, it was conquered by Raj Singh of Buria and was re-settled again in 1873. It is a typical organically grown town having narrow lanes, deadend streets and bye lanes. The Municipal Committee of the town was established in year 1882 AD. The town is famous for brass/bronze and steel utensils.

Jagadhri Workshop is a regional level railway workshop for repair of rail coaches and wagons. Yamuna Nagar, the third town of this urban agglomeration, became a town, when notified area committee was established in

the year 1942 with its erstwhile name Abdullapur. The town was rechristened as Yamuna Nagar in the year 1947. After partition, its population has grown considerably. Presently, it has become one of the major industrial towns of the state. Yamuna Nagar District came into existence on 1stNovember, 1989 and its area is 1756 square kilometers. It has four tehsils namely; Jagadhri, Chhachhrauli, Bilaspur, Radaur and three Sub-Tehsil namely Sadhaura, Saraswati Nagar (Mustafabad) and Pratap Nagar (Khizrabad). Apart from this, the Adi Badri Narayana, Shri Kedarnath and Mantra Devi Temples are situated 40 Kilometers away from Yamuna Nagar in the Northern side and it is a picturesque abundant with natural beauty and tranquility. The three mounds of antiquities have recently been excavated by the Archaeological Survey of India as well as it is said that the origination of the river Saraswati is also subsisted there as per the Hindu mythology. Moreover, the sacred place "Kapal Mochan" is also subsisted in the precinct of Yamuna Nagar and Jagadhri town on its Northside, nearly 24 kilometre away from its confinement. It is said that in the fifteenth and seventeenth century, the first Sikh Guru Nanak Dev Ji and tenth Guru Govind Singh Ji had visited and halted at this place during their pilgrims of Haridwar. Both the Guru's had spread the message to edifying the people in surrounding and to keep away from social evils and thus, there are many religious edifices of Hindu and Sikh religion at Kapal Mochan with sacred Kunds (ponds) namely Rin Mochan, Kapal Mochan and Surya Kund. It is thus expounded that people of different states i.e. Punjab, Haryana, Himachal Pradesh, Uttarakhand and Uttar Pradesh have visited the sacred place and to dive in these Kunds (ponds) by offering their self to God to get rid of their sins.

Keeping in view the importance of this place, the local administration has been arranging the mela/fair in the month of November on the eve of Kartik Purnima for the visitors from the last few decades.

II. Location and Regional Setting:

The Urban Centre is situated between 30°-7' to 30°-12' North latitude and 77°-15' to 77°-18' East longitude at an average height of 278 metres above mean sea level and it is Located on Ambala- Saharanpur Road. The urban center serves as a Gateway to Himachal Pradesh in the North and Uttar Pradesh in the East. It is connected to its surrounding region by means of National Highway and State Highways, i.e. Panchkula–Saha-Yamuna Nagar-Saharanpur Road (NH-344), Jagadhri–Chhachhrauli–Paonta Sahib Road (NH-907), Yamuna Nagar-Ladwa–Pipli–Kurukshetra Road (SH-6A), Jagadhri–Bilaspur-Sadhaura-Naraingarh-Barwala Road (SH-1) are passing through the towns. On the other hand, two National Highways and two State Highways are passing through the twin towns. They connect this urban centre with National Capital which is about 205 kms away, and State Capital which is about 112 kilometre away and also links other important cities of surrounding region e.g. Ambala, Panchkula, Paonta Sahib, Kurukshetra, Saharanpur, etc. Besides, Ambala –Saharanpur Railway line passes by the southern side of Yamuna Nagar, which is an important link connecting the twin towns from all the important cities of the surrounding region. The network of roads has helped industrial growth of the town despite its locational disadvantage. Apart from this, the towns are very well linked with its hinterland as well as dense forest/vegetation. The soil types in the district are mainly silty loam (Khadar), loam (Bhangar and Nardak) and light loam (Seoti). The underground water in the district is generally fresh and suitable for domestic and irrigation purposes.

III. Physiography:

Yamuna Nagar and Jagadhri are bounded on its east by Western Jamuna Canal and Yamuna River itself. The canal safeguards the towns from the fury of the inundation of river Yamuna. The general topography of the town is plain, gently sloping from northeast to southwest. The average subsurface water level is 12 meters having pH value ranging from 6.5 to 7 which is very good for prevailing crops and drinking purposes. The texture of the soil is sandy loam, considered as high-quality soil for crops. The average rainfall is 1105 mm. The town has almost flood-free history. The district has Shivalik hills and foothill rolling plain in the North and north east and flood-plain along the Yamuna river in the east and south-east. The important rivers/ streams of the district are Yamuna, Saraswati, Chautang, Rakshi, Somb, Boli etc.

IV. Demographic Profile:

As per 2011 census, the town had a population of 4,78,574 persons. Due to fast urban development in the past decades, the twin towns and Jagadhri workshop have integrated and taken the shape of a large city. The total population of this urban center consisting of Yamuna Nagar and Jagadhri is 3,41,965 as per 2011 census. Thus actual population as per 2011 census of this urban agglomeration comes to 4,78,574 persons. The decadal growth of population is as follows:

Year	Population	Decadal Growth Rate (%)
1961	84,337	-
1971	1,15,020	36.38
1981	1,60,424	39.47

1991	2,58,500	61.13
2001	3,38,887	31.10
2011	4,78,574	41.22
2021*	6,81,875	42.48
2031*	9,84,997	44.45
2041*	15,24,200	54.74

Source: Census of India, *Projected Population,

The above table shows a sudden increase in its population during the decade 1981-1991 when it increased from 1,60,424 in 1981 to 2,58,500 in 1991 registering a higher growth rate of 61.13 percent as compared to preceding decades. This can be attributed to large-scale migration of people from Punjab during militancy period. Thereafter, the growth rate has shown moderate increase of 41.22%. However, a higher induced growth rate has been envisioned in view of the decision of the Government to develop a model industrial township at Jagadhri and proposals made to develop the twin towns - Yamuna Nagar and Jagadhri as an important tourists' destination.

As per previous population trends of YamunaNagar-Jagadhri town and for envisaging a balanced development around the town, Geometrical Progression is the most applicable method for projecting the population for Draft Development Plan 2041 AD. In that thread, by considering the provisions of 20% component of residential growth also added like high-density policy provisions of the Department *viz*Affordable Group Housing, New Integrated Licensing Policy, Deen Dayal Jan AwaasYojna, Haryana Building Code-2017, etc. According to that the net projected population will be around 15,24,200 people for the projected year 2041 AD.

V. Economic Characteristics:

Yamuna Nagar-Jagadhri is a pre-eminent investment destination and has a potential to facilitate a balanced regional and sustainable development, capabilities for adoption of innovation & technology along with skill development and can generate employment opportunities in the District. The Metal Utensil Cluster, Jagadhri & Plywood Cluster, Yamuna Nagar are the two main traditional market leaders in the district which concentrates in small and medium scale units and these clusters have not been able to expand and achieve next level of growth due to non-availability of conforming land. Jagadhri being located in rich agrarian hinterland serves primarily as a mercantile town and retail services center for the surrounding region. The services provides the market for grains and other agricultural products of the area, retail market for agricultural inputs, household consumer goods and service industry for repair of agriculture implements, etc. Manufacturing and industrial processing are major economic activities in Yamuna Nagar town. Jagadhri workshop areas also enhance its share of economic base to the urban center as a whole. Three out of nine large-scale industrial units need specially mentioned in the economy of this urban center i.e. Ballarpur Paper Mill, Haryana Distillery and Saraswati Sugar Mills. Apart from these, ancillary industries of the auto spares and heavy machinery for sugar mills and scores of smaller units in industrial area and estate are mainstay of these towns economic, which provide employment to skilled/unskilled workers of surrounding area. The industrial activity has gained substantial momentum during the last two decades. Metalware and Plywood product are the leading industries, which concentrate, in small and medium scale units whereas paper, sugar, alcohol, starch, specialized engineering products and auto springs, are the major products of large-scale industries flourishing in the town.

According to 2011 census, the total number of workers was 1,13,762 that accounted for 33.26 percent of the total population. The workers engaged in primary, secondary and tertiary sector of the economy were 104899, 8863 and 228203 respectively that comes out to be 30.7%, 2.59% and 66.73% percent respectively of the total workers. The available census data for the decade 2001-2011 reveals that total workers are i.e. 30 percent of the total population of this urban sprawl, which is an increase by about 60% from the previous decade.

VI. Land use proposals:

The main concept of the Draft Development Plan is to weave the twin towns into a single entity and develop them as an important tourism node and industrial hub of the state. The projected population of the urban centre is about 15,24,200 by 2041 AD. As per census 2011, its population was about 4,78,574. Hence, development plan proposals are to be made to adjust the additional 10,45,626 population of about by 2041 AD. In order to accommodate the additional population, 12327.52 hectares of land is proposed to be urbanized. The area of villages and existing towns is 2460.57 hectares approximately, which is accommodating a population of about 4,78,574

persons. Therefore, the proposed plan envisages to accommodate about 15,24,200 persons by 2041 AD at a gross density of about 124 PPH and net sector density is 300 person/ hectare. The proposed land uses are as given below:-

Serial Number	Land use	Area within MC Limit (Hectare)	Area within Controlled Area (Hectare)	Total Area (Hectare)	% of Total Area*
1.	Residential	3402.20	83.11	3485.31	35.32
2.	Commercial	372.35	0.00	372.35	3.77
3.	Industrial	1524.30	1353.88	2878.18	29.17
4.	Transport & Communication	952.82	463.56	1416.38	14.35
5.	Public Utilities	146.99	35.51	182.50	1.85
6.	Public & Semi Public	234.81	80.65	315.46	3.20
7.	7. Open Spaces		388.61	1200.62	12.17
8.	Special Zone	0	16.16	16.16	0.16
	Total Area	7445.48	2421.48	9866.96	100.00

^{*}Note.— The total urbanisable area is 12327.53 hectares, wherein, the area of existing town of YamunaNagar, Jagadhri, Jagadhri workshop and existing villages (2460.57 Hectares) has not been included in the above area statement.

Description of various land uses:

1. Residential:

The Draft Development Plan-2041AD of Yamuna Nagar and Jagadhri has been planned for the projected population of 15,24,200 persons. Presently, the existing towns of Jagadhri, Yamuna Nagar and Jagadhri Workshop are accommodating a population of about 4,78,574 persons. In order to accommodate remaining 10,45,626 persons, an area of 3485.31 hectares of land has been proposed to be developed for residential sectors with residential density of 300 persons per hectare. The rest of projected population would be accommodated in residential sectors i.e.1(part), 2(part), 4, 5, 6(part), 10, 12(part), 12A, 13(part), 14, 15, 16(part), 16A, 17(part), 17A, 18(Part), 18A(Part), 20(Part), 21, 22(Part), 23(part), 24, 25(part), 26, 27, 28(part), 29, 33, 34, 35(part), 39, 40(part) and 41(part) have been designated for residential purpose.

Apart from the proposal to increase the density, the following provisions have also been made in Development Plan:

- (a) The additional area for infrastructure shall be provided in the already planned/developed residential sectors to meet out the requirement of the additional population.
- (b) The minimum width of the roads in the residential colony/sector shall not be less than 12 meters or as per the applicable policies.
- (c) The minimum area for park/open spaces in residential colony/sectors shall be planned in such a manner that it shall meet the minimum norms of 2.5 square meters per person.

Every residential sector shall be developed to the sector density indicated in the drawing with 20% variation on either side and in addition to it, the density as prescribed in the New Integrated Licensing Policy (NILP), Affordable Group Housing policy, Deen Dayal Jan Awaas Yojna Policy (DDJAY), 20% Group Housing component policy will also be applicable in a residential sector.

2. Commercial:

Within the existing town, the retail commercial activity is mostly located along the main roads of the town in the form of bazaar. However, in order to cater the commercial needs of Jagadhri, Yamuna Nagar and Jagadhri workshop an area of 372.35 hectares of land has been allocated for commercial use comprising of sectors 3(Part), 9, 18(Part), 19, 24A and 42. Besides, a 150 meter wide commercial belt is proposed along sector dividing road of sector's 12(part), 13(part) and 20(part) to exploit the potential of this major road which will make even and reasonable distribution of commercial spaces. The residential sector would have adequate provisions in the form of

neighbourhood shopping center for day to day shopping of residents. An area of about 82.98 hectares is reserved as "City Centre" in sector 19.

The existing grain market is situated in the middle of the twin towns in residential sector-18 which is located on the main Jagadhri-Yamuna Nagar road opposite to the mini-secretariat and judicial complex situated in sector-17. Hence, the provision for shifting the grain market in Sector-9 has been proposed which is at the peripheral boundary of the urbanisable plan. The land under the existing Grain Market can be utilised for some other compatible use thereafter. There is a huge demand for the Timber Market and it has been accommodated by proposing sector-42 on NH-907 having an area of 70.86 hectares.

3. Industrial:

Being the generic industrial town and in order to strengthen the industrial growth and the upcoming demand for developed industrial plots/ land in Yamunanagar is increasing day by day. In order to cater the future Industrial needs of the town an area of 2878.18 hectares of land has been allocated for Industrial use comprising sectors 3(part), 3-A(part), 7, 30, 30A, 31, 32, 40(part), 41(part), 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 56, 57, 58, and 59. These sectors have been proposed along in between V 2(d) sector road and Yamuna Nagar-Saharanpur Road (NH-344) and on the north-east and southern side on Jagadhri-Chhachhrauli Road (NH-907).

HSIIDC has established only one Industrial estate at Manakpur in the Controlled Area on Jagadhri-Chhachhrauli-Paonta Sahib road (NH-907) road over an area of about 54 hectare. The new industrial area has been incorporated in the plan near existing Haryana State Industrial and Infrastructure Development Corporation Limited Industrial estate in Manakpur along the National Highway-907 (Jagadhri-Paonta Sahib Road) and the area between the southern sector road V2(d) and the existing outer peripheral road i.e. National Highway-344 and also along the State Highway-6A.

4. Transport and Communication:

In this development plan, an area of 1416.38 hectares has been proposed for Transport and Communication use. Transport Nagar and Transport Depots are proposed to be developed in sector 8(part), 10(part), 11(part), 18-A (part), Sector 35(part) on old Saharanpur Road and sector- 43 on Jagadhri-Chachhrauli Road (NH-907) near village Mukaribpur and sector 55 in between V 2(c) sector road and V2(a)-Yamuna Nagar-Saharanpur Road (NH-344) near village Panjupur have also been designated for Transport and Communication zone for Yamuna Nagar and Jagadhri towns. In addition, as per the policy dated 25.01.2019, the provision of maximum limit of 20% of the total of Transport and Communication zone/sectors for the purpose of establishing the warehouses has been kept in this zone.

The proposed transport network hierarchy includes National Highway, Scheduled Roads (V-2, V-2(a) and V-4; peripheral roads (V-1, V-2 and V-2(b)); sector roads with green belts (V-2, V-2(b), V-2(c) and V-3, V-4 and V-4(c)) and other sector roads (V-2(b), V-3 and V-4(a) and V-4(c)) and roads with existing width is V-2(b), V-3 and V-4(b).

4.1 Transportation Network:

The present urban road system of this urban agglomeration is erratic causing bottlenecks and is prone to accidents. In order to ensure safe and speedy movement of inter-city and intra-city traffic, the plan envisages the following provisions:

- (a) National Highways— To avoid congestion in the city and to augment the traffic, a new highway has been made by NHAI i.e. NH-344 (earlier NH-73) having width of 60 meter wide road along with 30 metre wide green belt on both sides and has been classified as V-2. This new highway is now NH-344 which connects Saharanpur-Yamunanagar-Jagadhri-Ambala Road near the junction of village Kail and Bhambholi. The provision of two cloverleavers are proposed on NH-344 at the entry and exit point of the town. One of them near the junction of village Kail and Bhambholi along Ambala-Jagadhri road and another nearby village Kalanaur on Yamunanagar-Saharanpur road (NH-344). The new classification of road V2(a) have been proposed along NH-344 in the urbanizable zone along the new proposed industrial sectors i.e. sector 50 to 56, sector 58 and 59, which has a width of 60-meter wide green belt on the northern side and 30 meter wide green belt on the southern side. NH-907 (Jagadhri Chhachhrauli Paonta Sahib Road) has been classified as V-2 having width of 60 meter wide road along with 30 meter wide green belt on both sides and is passing through the urbanizable zone of the Development plan and further connects Paonta Sahib.
- (b) State Highways— There are two State Highways passing through the Development Plan i.e. SH-1 & SH-6A, both have been classified as V-4 having width of 30 meter wide road alongwith 30 meter wide green belt on both sides. SH-1 is connecting Jagadhri to Bilaspur and SH-6A is connecting Yamuna Nagar to Radaur.

- (c) Peripheral Roads—In order to segregate the classification of roads around the urbanizable area, peripheral road have been proposed in the Development Plan. The western peripheral road which has been classified as V-2(b) having width of 60 meter wide road starting from sector-9 (village Jampur) till sector-12 (village Ratauli). Further, the same road has been classified as V-1 i.e Northern Peripheral road which is 75 meter wide with 50 meter green belt on both sides starting from sector-13 (village Ratauli) till sector-33 (village Nabh) and falls in urbanizable zone. Beyond that, this road is further classified as Eastern peripheral road (V-2) having width of 60 meter wide road along with 30 meter wide green belt on both sides and is faling in Agricultural zone, which is connecting NH-344 near village Kalanaur. An additional link has also been proposed as Additional peripheral road (V-2) having width of 60 meter wide road along with 30 meter wide green belt on both sides which is connecting NH-344 near village Kail and Northern peripheral road at sector-25 (village Jaraudi) and is falling in Agricultural zone. The traffic originating from various part of the city and having a destination outside it and the traffic to by-pass of the city would ply on the proposed peripheral road.
- (d) Existing Roads -Existing roads presently connecting the city with Ambala, Panchkula, Naraingarh, Paonta Sahib, Kurukshetra and Saharanpur have been retained with their existing widths. The existing road have been classified as V-4. The existing road Old Ambala –Jagadhri road (erstwhile NH-73) have been augmented with 30 meter wide green belt on both sides on the stretch passing through Agricultural zone starting from NH-344 till Northern peripheral road near Khera Power House. Further, it has been extended as V-4 (c) having width of 30 meter wide road alongwith 60 meter wide green belt on both sides in between sector 20 & 22.
- (e) Sector Roads -Entire urbanisable area is proposed to be divided into various land use zones designated as sectors. Each sector is proposed to be bounded by a minimum 45 metres wide sector dividing road which has been classified as V-3. However, few roads in urbanisable area have been catagorised as V-2, V-2(b) and V-2 (c) due to the proposed green belts along these roads. The Old Sharanpur road passing in the urbanizable zone from sector-15, 39 & 38 has been classified as V-2 and further, it has been classified as V-2(b) connecting Eastern peripheral road near village Kait. The existing road, leading from Jagadhri-Bilaspur road to village Sarawan, has also been proposed as sector road (V-3).

The roads along the augmentation canal on both sides passing between sector-4 & 5 has been classified as V-4(b) having width of 30 meter.

The width/ reservation of vari	ous roads proposed in	the development j	plan are as under:-
--------------------------------	-----------------------	-------------------	---------------------

Serial number	Classification	Name of Road	Land Reservation
1	V-1	Northern Peripheral road along urbanisable zone.	75 meter wide road along with 50 meter wide green belt on both sides
2	V-2	 i. Ambala-Jagadhri- Yamuna Nagar-Saharanpur Road (NH- 344) ii. Jaghadri - Chhachhrauli - Paonta Sahib Road (NH-907) iii. Eastern Peripheral Road iv. Additional Peripheral Road v. Sector Dividing Road 	60 meter wide road along with 30 meter wide green belt on both sides
3	V-2(a)	Ambala-Jagadhri- Yamuna Nagar-Saharanpur Road (NH-344)	60 meter wide road along with 60 m wide green belt on northern sides and 30 m wide green belt on southern side.
4	V-2(b)	i. Western Peripheral Road ii. Sector Dividing Road iii. Old Saharanpur Road	60 meter wide road
5	V-2(c)	Sector Dividing Road	60 meter wide road along with 30 m wide green belt on southern side

6	V-3	Sector Dividing Road	45 meter wide road
7	V-4	i. Jagadhri-Bilaspur road (SH-1)ii. Yamuna Nagar-Radaur Road (SH-6A)	30 meter wide road along with 30 meter wide green belt on both sides
		iii. Old Ambala-Jagadhri Road	
8	V-4(a)	Existing internal roads	Existing width
9	V-4(b)	Road along Augmentation Canal	30meter wide road
10	V-4(c)	Old Ambala-Jagadhri Road	30 meter wide road along with 60 meter wide green belt on both sides

The new classification of roads {V2(a) & V2 (c)} have been introduced/proposed by the addition of new industrial Sectors. The land reserved for V2(a) category of road is 60 metre wide along with 60 metre wide green belt on northern side and 30 metre wide green belt on southern side. This category of road is mainly along NH-344 (from Sector 50 to 56, 58 & 59). The land reserved for V2(c) category of the road is 60 metre wide along with 30 metre wide green belt on southern side (from Sector 3A to 8), V-3 (45 metre wide) sector dividing road has been proposed in the right of way (ROW) of Dadupur-Nalvi Canal superimposing the already existing 20 metre wide road by Public Works (B&R) Department towards the Northern side of the present alignment including the existing PWD (B&R) road.

The width and alignment of other roads shall be as per sector plans or as per approved layout plans of colonies. Wherever, roads shown in the Development Plan are found to be non-feasible, as per ground condition, Government shall be competent to realign/delete the same after recording the reasons thereof.

4.2 Eastern Dedicated Freight Corridor:

The Dedicated Freight Corridor Corporation of India Ltd has already commissioned the work of Eastern Dedicated Freight Corridor from Ludhiana, Punjab to Dankuni, West Bengal which is passing through District Yamuna Nagar and the alignment of same has been incorporated in the Development Plan along the existing railway line.

5. Public Utility Zone:

In order to cater to the needs of projected population of 15,24,200 an area of 182.50 hectares has been earmarked for the public utilities in order to meet the requirements of water supply installations, drainage installations, sanitation, disposable works and grid sub-stations, etc. 75 hectares of land is reserved for canal based water installation in residential sectors 1(part), 2(part), 3-A(part), 6(part), 8(part), 11(part), 12(part), 23 (part), 28(part), 37(part), 40(part) and 41(part). These sites have been provided adjacent to Western Jamuna Canal and Dadupur-Nalvi Canal. Presently, the water is mostly supplied through the tube-wells after chlorination. There are three nos. STP's existing at village Mamidi and Garhi Gujran, Badhi Majra and Parwalo, whereas seven additional sites for STP has been proposed along Ambala-Yamuna Nagar Railway line near village Phoosgarh, sector-1, sector-3A, sector-12, sector-23, sector-28 & sector-41 to cater the future demand. There is one solid waste existing site at village Khera road an Old Ambala-Jagadhri road and two sites have been proposed for future expansion at southern side of augmentation canal near village Khurdi and in the revenue estate of village Nabh.

While, regarding the augmentation of power infrastructure in Yamuna Nagar, 400KV sub-station already exists at village Bhamboli on NH-344, which is falling outside the Controlled Areas of Yamuna Nagar-Jagadhri and the entire downline load for Yamuna Nagar-Jagadhri is being fed by this sub-Station in synchronising with Deen Bandhu Chottu Ram Thermal Power Plant. 3 no. 220 KV sub-stations already exist at village Khera, Jorian on Radaur road and Rattanpura (Deen Bandhu Chottu Ram Thermal Power Plant). Apart from this, 1 nos. 220 KV sub-station has been proposed in Sec-33 near village Chaneti. 3 nos. 220 KV sub-station have been proposed in the agriculture zone of the Development Plan on road leading to village Sarawan; on village link road from Mehrampur to Goglon and near village Naharpur for future expansion. 5 no. 66 KV sub-stations already exist in the original Municipal limit of Yamuna Nagar –Jagadhri; 1 no. 66 KV sub-station exists in Sec-15 and 1 no. 66 KV sub-station is existing near village Rattangarh to strengthen the distribution system in Yamunnagar and Jagadhri. While for the future augmentation and strengthening of power demand 21 nos. 66 KV sub-station has been earmarked in sectors 2, 3A, 4, 6, 7, 9, 11, 16, 17, 19, 23, 26,30A, 31, 32, 36, 41, 47, 52 & near village Sugh on Amadalpur road.

6. Public and Semi Public Use Zone:

Mini Secretariat and Judicial Complex are already functioning in sector-17 and I.T.I. in sector-16. However, the urban centre has been envisioned to be developed as an important tourism node in the region in order to boost its prospects. As such an area of 315.46 hectares of land has been earmarked in sector 11 (part), 16 (part), 17 (part), 20(part), 25(part), 35, 36 and 36A for this purpose. An education city and medi-city may be developed in sector 36 to boost education and health tourism. Jail has also been accommodated in residential sector 25.

7. Open Spaces:

The area under open space as reserved in the Draft Development Plan is 1200.62 hectares. Area measuring 8.10 hectares of land is specifically earmarked for Town Park in sector-18. The area for sports grounds, stadium playgrounds and parks has also been proposed in sector-6(part) and sector-25 having area 16 hectare and 11.63 hectare, respectively. Besides this, there are two sectors of open space i.e. sector-37(part) and 38. It will add to the aesthetic beauty of the area.

As per the notification by Govt., the Dadupur-Nalvi Canal has been partly de-notified and subsequently, the area of the canal has been added in the open space. Also, 30 M wide green belt has been proposed along the Western Jamuna Canal on both sides to protect the Canal. The green belt shown along the sector / arterial roads shall be primarily meant for the widening of the sector / arterial road in the future. However, till such time the widening does not take place, the said area may be utilized for nursery/plantations, fuel-station, communication lines, utility services, etc.

8. Agriculture Zone:

The remaining area in the controlled area is kept as agriculture zone. However, it would not eliminate to essential building development within this area, such as, the extension of the existing village contiguous to Abadi-deh if undertaken as a project approved or sponsored by the Government other activities included as permissible activities in the Zoning regulations under Appendix B to AnnexureB ancillary and allied facilities necessary for the maintenance and improvement of this area as agricultural land which is proposed to serve as an open countryside for the town as a whole.

9. Special Zone - Integrated Wayside Amenities:

In the Development Plan, the provision for Integrated Wayside Amenities have also been made as Special Zone over an area measuring 16.16 hectare in order to facilitate the highway traffic. The areas under this zone are planned to be located at frequent intervals across National Highways, Scheduled Roads, State Highways and outer peripheral roads providing basic services and amenities, to ensure safe and convenient journey for long-distance travellers in order to reduce the incidence of accidents and improve road safety, by providing drivers a comfortable place to rest, entertainment and leisure. This zone has been proposed at the interval of 20 km (approximately) with an area of 10 acre each at four different locations along NH-344 near village Kail & Kalanaur and NH-907 near village Chhachhrauli and along the Eastern Peripheral Road near village Amadalpur to provide basic services and amenities.

Zoning Regulations

The legal sanctity to the proposal regarding land use is given effect to by a set of zoning regulations, which from part of this development plan. These regulations will govern the change of land use and standards of development. They are also elaborately detailed out for allied and ancillary uses which will be permitted in the various major land uses and stipulate that all the change of land use and development shall be in accordance with the details shown in the sector plan thereby ensuring the preparation of detailed sector plan for each sector to guide the development and enforce proper control.

ANNEXURE-B

Governing use and development of land in the Controlled Areas of Yamuna Nagar-Jagadhri as shown in Draft Development Plan Drawing No. DTP(Y)86/2020, dated the 23rd July, 2020.

I. General:-

- 1. These zoning regulations forming part of the Draft Development Plan for the controlled areas of Yamuna Nagar-Jagadhri shall be called zoning regulations of the Draft Development Plan for the controlled areas Yamuna Nagar-Jagadhri.
- 2. The requirement of these regulations shall extend to the whole of area covered by the development plan and shall be in addition to the requirements of the Haryana Municipal Corporation Act, 1994 (16 of 1994) and the Punjab Scheduled Roads and Controlled Areas Restrictions of Unregulated Development Act, 1963 (Punjab Act 41 of 1963), and the rules framed thereunder.

II. Definitions:-

In these regulations:-

- (a) 'Agro based Industries' means an industrial unit, which uses food grains, fruits or Agro waste as raw-material;
- (b) 'Approved' means approved by the competent authority;
- (c) **'Building Code'** means, the Haryana Building Code 2017;
- (d) **'Building rules'** means the rules contained in part VII of the rules:
- (e) **'Cyber City'** means self contained intelligent city with high quality of infrastructure, attractive surrounding and high speed communication access to be developed for nucleating the Information Technology concept and germination of medium and large software companies Information Technology Enabled services; wherein no manufacturing units may be allowed;
- (f) **'Cyber Park/Information Technology Park'** means an area developed exclusively for locating software development activities, and Information Technology Enabled services wherein no manufacturing of any kind (including assembling activities) shall be permitted;
- (g) 'Drawing' means Drawing No. DTP(Y)86/2020, dated the 23rd July,2020.
- (h) **'Extensive Industry'** means an industry set up with the permission of the Government and in extensive, employing more than 100 workers and may use any kind of motive power of fuel provided they do not have any obnoxious features;
- (i) **'Farm House'** means a house constructed by the owner of a farm at his land for the purpose of:
 - (i) Dwelling unit, i.e. main use,
 - (ii) Farm shed i.e. Ancillary use.

Notes:-

- (1) The construction of the farm house shall be governed by the restrictions given under clause XIX regarding 'provision of farm houses outside adadi- deh in agricultural zone'.
- (2) 'Farm sheds' shall be governed by the restriction mentioned in clause XIX regarding building control and site specifications.
- (j) **'Floor Area Ratio (FAR)'** means a quotient obtained by dividing the multiple total covered area of all floors and hundred, by the area of plot i.e.

$$FAR = \frac{\text{Total covered area}}{\text{Plot area}} \times 100$$

For the purpose of calculating FAR, cantilevered permitted roof projections, lift room, mumty, balcony, basement or any floor if used for parking, services and storage, stilt area (unenclosed) proposed to be used for parking and pedestrian plaza only, open staircase (without mumty), terrace with or without access, fire staircase, atrium, water tank, open court yard of permitted size shall not be counted towards FAR:

Provided that area under shaft, chutes, lift well and staircase from stilt to next floor shall be counted towards FAR only at once on ground floor;

Provided further that in case the ventilation shaft area is more than 3 square metres, it shall not be counted in FAR;

- (k) **'Fuel Station'** means the fuel filling station providing retail supply of fuel for automobiles which shall include petrol pumps, CNG station, bio-fuels, charging station, battery providing stations etc;
- (l) **'Green Belt'** shall means, strips of land along sector/arterial road shown in the development plan primarily meant for the widening of the sector/arterial road in future
- (m) **'Group Housing'** means a building designed and developed in the form of flats for residential purpose or any building ancillary to group housing:
- (n) **'Heavy Industry'** means an industry to be set up in public or semi public or private sector with the permission of the Government (the cost of plant machinery etc. as defined in the industrial policy of the Government);

- (o) 'Information Technology Industrial Units' means the categories of industries included in the Annexure to the Government of Haryana Information Technology Policy, 2000 and in Appendix-1 to this notification and/or, as may be defined by the Government of Haryana from time to time;
- (p) **'Ledge or Tand'** means a shelf-like projection, supported in any manner whatsoever, except by means of vertical supports within a room itself but not having projection wider than one metres;
- (q) **'Light Industry'** means industry not likely to cause injurious or obnoxious noise, smoke, gas, fumes or odors, dust, effluent and any other nuisance to an excessive degree and motivated by electric power;
- (r) **'Local Service Industry'** means an industry, the manufacture and product of which is generally consumed within the local area, for example: bakeries, ice-cream manufacturing, aerated water, attachakkies with power, laundry, dry cleaning and dyeing repair and service of automobile, scooters and cycles, repair of household utensils, shoe making and repairing, fuel depots etc. provided no solid fuel is used by them.
- (s) 'Loft'shall means an intermediate space between two floors on a residual space with maximum height of 1.5 metres and which is constructed or adopted for storage purposes only;
- (t) **'Material Date'** means the date of publication of notification of various controlled areas declared as under:

Serial Number	Name of the Controlled Area and Notification No.	Material date	
1.	Controlled Area notified vide Punjab Government Gazette notification No. 447-2TCP-65/6852, dated the 6th March, 1965 published on the 28th May, 1965		
2.	Additional Controlled Area notified vide Haryana Government Gazette Notification no. CCP/JCA-I/97/468, dated the 29th May 1997 published on the 1st July ,1997		
3.	Additional Controlled Area-III notified vide Haryana Government Gazette notification No. CCP/(NCR)YN (ACA-III)/A/2007/422, dated the 9th Feb.2007 published on the 9th Feb, 2007		
4.	Additional Controlled Area- IV notified vide Haryana Government Gazette notification No. CCP/(NCR)/YN (ACA-IV)/2020/901, dated the 16th July.2020 published on the 16th July, 2020		

- (u) 'Medium Industry'shall means all industries other than Light Industry and Local Service Industry and not omitting obnoxious or injurious fumes and odours;
- (v) **'Mezzanine floor'** means an intermediate floor, between two floors, with area restricted to ½ (half) of the area of the lower floor and with a minimum height of 2.3 metres and shall not be lower than 2.3 metres (clear height) above floor level;
- (w) 'Non-conforming use' in respect of any land or building in a controlled area means the existing use of such land or building which is contrary to the major land use specified for that part of the area in the Draft Development Plan.
- (x) 'Obnoxious or 'Hazardous Industry' means an industry set up with the permission of the Government and is highly capital intensive associated with such features as excessive smoke, noise, vibration, stench, unpleasant or injurious effluent, explosive, inflammable material etc. and other hazards to the health and safety of the community.
- (y) **'Public Utility Service Building'** means any building required for running of public utility services such as water supply, drainage, electricity, post and telegraph and transport and for any municipal service including a fire station.
- (z) 'Rules' means the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Rules, 1965.

(za) **'Sector Area'** and **'Colony Area'** shall means the area of sector or of colony indicated as such in the Development Plan;

Explanation:-

- (1) In this definition the 'Sector Area' or 'Colony Area' shall mean the area of the Sector or of Colony as shown on the drawing on the approved layout plan of the colony/sector which will be excluding the area unfit for building development within the sector or the colony as the case may be.
- (2) Benefit of 50% of the area falling under major roads and their adjoining green belts, if any, shall be allowed for plotable area/floor area ratio (FAR) in case of plotted/group housing colony;
- (3) In the layout plan of colony or sector, other than industrial colony/sector, the land reserved for roads, open space, schools, public and community building and other common uses shall not be less than 45% of the gross area of the land under the colony/sector;
- (4) For the purposes of calculation of sector density or colony density, it shall be assumed that 50 percent of the sector area or colony area will be available for residential plots including the area under Group Housing and that every building plot shall on the average contain three dwelling units each with a population of 4.5 persons per dwelling unit or 13.5 persons building plot or as incorporated in the zoning plan of the colony/group housing complex. In the case of shop-cumresidential plot, however, only one dwelling unit shall be assumed;
- (5) Notwithstanding above, the projects approved under specific policy like New Integrated Licensing Policy; Floor Area Ratio and density shall be the governing parameters instead of plotable area;
- (zb) 'Sector Density' and 'Colony Density' shall mean the number of persons per hectares in sector area or colony area or colony area as the case may be;
- (zc) **'Site Coverage'** means ratio expressed in percentage between the area covered by the ground floor of building and the area of the site;
- (zd) **'Small Scale Industries'** means Industrial unit, which is registered as Small Scale Industry by the Industries Department.
- (ze) **'Subservient to Agriculture'** mean development and activities, which are required to assist in carrying out the process of "agriculture" such as tubewells, pump chambers, wind mills, irrigation drains, pucca platform, fencing and boundary walls, water hydrants etc;
- (zf) The terms 'Act', 'Colony', 'Colonizer', 'Development Plan', 'Sector' and 'Sector Plan' shall have the same meaning as assigned to them in the Punjab Scheduled Roads and Controlled areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963) and rules, 1965 framed there under.
- (zg) Any other term shall have the same meaning as assigned to it in the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963, (Punjab Act 41 of 1963) and the rules 1965 framed there under;

III. Major land uses / Zones:-

- (1) (i) Residential Zone
 - (ii) Commercial Zone
 - (iii) Industrial Zone
 - (iv) Transport and Communication Zone
 - (v) Public Utility Zone
 - (vi) Public and Semi Public Zone (Institutions)
 - (vii) Open Space Zone
 - (viii) Agriculture Zone
 - (ix) Special Zone.
- (2) Classification of major land uses is according to Appendix A.

IV. Division into sectors:-

Major land uses mentioned at serial number (i) to (vii) and (ix) in zoning regulation – III above, which are land uses for building purposes, have been divided into sectors as shown on the drawing and each sector shall be designated by the specific number as indicated on the drawing.

V. Detailed land uses within major uses:-

Main ancillary and allied uses, which are subject to the other requirements of these regulations and of the rules, may be permitted in the respective major land use zone are listed in Appendix 'B' sub-joined to these to these regulations.

VI. Sectors not ripe for development:-

Notwithstanding the reservation of various sectors for respective land uses for building purposes the Director may not permit any changes in their land use or allow construction of building thereon from considerations of compact and economical development of the Controlled Area, till such time as availability of water supply, drainage arrangement and other facilities for these sectors are ensured to his satisfaction.

VII. Sectors to be developed exclusively through Government enterprises:-

Government may notify any sector for development exclusively by it or by its agencies, in which case, no further permission for change of land use or grant of licence shall be permitted in such sectors.

VIII. Land reservation for major roads:-

(1) Land reservation for major roads shall be as under :-

Serial Number	Classification	Name of Road Land Reservation		
1	V-1	Northern Peripheral road along urbanisable zone.	75 meter wide road along with 50 meter wide green belt on both sides	
2	V-2	 i. Ambala-Jagadhri- Yamuna Nagar-Saharanpur Road (NH- 344) ii. Jaghadri - Chhachhrauli - Paonta Sahib Road (NH-907) iii. Eastern Peripheral Road iv. Additional Peripheral Road v. Sector Dividing Road 	60 meter wide road along with 30 meter wide green belt on both sides	
3	V-2(a)	Ambala-Jagadhri- Yamuna Nagar-Saharanpur Road (NH-34)	60 meter wide road along with 60 m wide green belt on northern sides and 30 m wide green belt on southern side.	
4	V-2(b)	i. Western Peripheral Road i. Sector Dividing Road ii. Old Saharanpur Road		
5	V-2(c)	Sector Dividing Road	60 meter wide road along with 30 m wide green belt on southern side	
6	V-3	Sector Dividing Road	45 meter wide road	
7	V-4	i. Jagadhri-Bilaspur road (SH-1)ii. Yamuna Nagar-Radaur Road (SH-6A)iii. Old Ambala-Jagadhri Road	30 meter wide road along with 30 meter wide green belt on both sides	

8	V-4(a)	Existing internal roads	Existing width
9	V-4(b)	Road along Augmentation Canal 30meter wide road	
10	V-4(c)	Old Ambala-Jagadhri Road	30 meter wide road along with 60 meter wide green belt on both sides

- (2) Width and alignment of other roads shall be as per sector plan or as per approved layout plan of colonies. Wherever, road shown in the Development Plan are found to be non-feasible, as per ground condition, Government shall be competent to realign / delete the same after recording the reasons thereof
- (3) Benefit of tradable Floor Area Ratio, may be allowed against licences granted for the land falling under sector road or green belt and open space zones in accordance with specified policies.

IX. Non-conforming uses either existing or having valid change of land use permission:-

- (1) With regard to the existing industries shown in the zones other than industrial zone in the Development Plan, such industrial non-conforming uses shall be allowed to continue for a fixed period to be determined by the Director, but not exceeding ten years; provided that the owner of the building concerned:
 - (a) Undertakes to pay to the Director, as determined by him the proportionate charges towards the external development of the site as and when called upon by the Director to do so in this behalf;
 - (b) During the interim period makes satisfactory arrangements for the discharge of effluent to the satisfaction of the Director; and
 - (c) Shall not be allowed to expand the existing project within the area of non-conforming use.
- (2) With regard to the projects having valid change of land use permissions, and located in the zones other than conforming-use zone in the Development Plan, such non-conforming uses shall be allowed to continue, provided that the owner of the building concerned.
 - (a) Undertakes to pay to the Director, as determined by him the proportionate charges towards the external development of the site as and when called upon by the Director to do so in this behalf; and
 - (b) During the interim period makes satisfactory arrangements for the discharge of effluent to the satisfaction of the Director.

X. Discontinuance of non-conforming uses:-

- (1) If a non-conforming use of land has remained discontinued continuously for a period of two years or more, it shall be deemed to have been terminated and the land shall be allowed to be re-used or redeveloped only according to the conforming use.
- (2) If a non-conforming use building is damaged to the extent of 50 percent or more of its reproduction value by fire, flood, explosion, earthquake, war, riot or any other natural calamity, it shall be allowed to be re-developed only for a conforming use
- (3) After the discontinuance of projects included under clause IX, the land shall be allowed to be redeveloped or used only for conforming use
- (4) After a lapse of period fixed under clause IX (1), the land shall be allowed to be redeveloped or used only for conforming use.

XI. Development to conform to sector plan and zoning plan:-

Except as provided in regulation IX, no land within major land use shall be allowed to be used and developed for building purposes unless the proposed use and development is according to the details indicated in the sector plan and zoning plan or the approved colony plan in which the land is situated.

XII. Individual site to form part of approved layout or zoning plan:-

No permission for erection or re-erection of building on a plot shall be given unless

(i) The plot forms a part of an approved colony or the plot is in such area for which relaxation has been granted as provided in regulation XVII; and

(ii) The plot is accessible through a road laid out and constructed up to the situation of the plot to the satisfaction of the Director.

XIII. Minimum size of plots for various types of buildings:-

(1) The minimum size of the plots for various types of uses shall be as below:-

Serial Number	Land Use		Size	
i.	Residential plot	50 Square meters	59.8 square yard	538.20 square feet
ii.	Residential plot on subsidized industrial housing or slum dwellers housing scheme approved by the Government	35 Square meters	41.86 square yard	376.74 square feet
iii.	Shop-cum-residential plot	100 Square meters	119.60 square yard	1076.40 square feet
iv.	Shopping booths including covered corridor or pavement in front	20 Square meters	23.92 square yard	215.28 square feet
v.	Local service industry plot	100 Square meters	119.60 square yard	1076.40 square feet
vi	Light industry plot	250 Square meters	299 square yard	2691 square feet
vii.	Medium industry plot	8000 Square meters	9568 square yard	86112 square feet

(2) The area norms for group housing colony plotted residential colony and commercial colony shall be in accordance with the policies specified from time to time for residential and commercial development. However, in a case group housing scheme is floated by the Haryana Shehri Vikas Pradhikaran or any other Government Agency, the size of group housing site shall be as specified in the scheme.

XIV. Site coverage, height and bulk of building under various types of buildings:-

The site coverage, Floor Area Ratio and height permitted on a specific plot/site shall be governed by the prescribed policy parameters, building code/rules and /or as laid down in the zoning plan of such plot/site.

XV. Building lines in front and rear of buildings:-

These shall be provided in accordance with building code/rules and /or as laid down in the zoning plan of such site.

XVI. Architectural control:-

Wherever architectural control is considered necessary, every building shall conform to architectural control prepared under clause 6.4 of Harvana Building Code 2017.

XVII. Relaxation of agricultural zone:-

In the case of any land lying in Agriculture zone, Government may relax the provisions of this development plan-

- (a) for use and development of the land into a residential or industrial colony provided the colonizer has purchased the land for the said use and developed prior to the material date and the colonizer secures permission for this purpose as per Rules,
- (b) for use of land as an individual site (as distinct from an industrial colony)

Provided that-

- (i) The land was purchased prior to the material date;
- (ii) The Government is satisfied that the need of the industry is such that it cannot await alternative allotment in the proper zone;
- (iii) The owner of the land secures permission for building as required under the Rules;
- (iv) The owner of the land undertakes to pay to the Director, as determined by him, the proportionate charges as and when called upon by the Director in this behalf and during the interim period makes satisfactory arrangement for discharge of effluent.

Explanation: The word purchase in the regulation shall means acquisition of full property right and no lesser title, as agreement to purchase etc.

(c) the site should not fall within restricted belt notified under 'the Work of Defence Act, 1903' around Defence installations, if any.

XVIII. Density:-

Every residential sector shall be developed to the sector density indicated in the drawing with 20% variation on either side and in addition to it, the density as prescribed in the New Integrated Licensing Policy, Deen Dayal Jan Awaas Yojna Policy and Affordable Group Housing policy, 20% Group Housing component policy shall also be applicable in a residential sector.

XIX. Provision of Farm House outside Abadi-Deh in Agricultural Zone:-

Farmhouses shall be allowed only for bonafide use of landowner(s) provided he does not own a house in any urban area because the real objective for allowing farmhouses in agriculture zone is to meet the housing needs of the farmers on a small portion of the farm so that he can take care of his agriculture produce while living on that farm. Hence, a farm house in agriculture zone, outside abadi-deh may be allowed if the area of the land is 2 acres or more on the following conditions:-

Serial Number	Size of farm house	Main building of the dwelling unit.	Ancillary building of main dwelling unit.
(i)Site Coverage	2 Acres minimum but CLU permission for the area falling under road reservation /proposed road widening as per Development Plan, shall not be considered. However the net area should not be less than 1.5 acres after excluding the area falling under the green belt/ restricted belt and falling in Agriculture zone from applied area of 2 acres.	As applicable to residential plot equivalent to 250 square yards.	1 percent of the farm land (not more than 40 percent shall be used for labour/ servant quarters)
	Upto 3 acres	As applicable to residential plot equivalent to 375 square yards	-do
	Upto 4 acres and above	As applicable to residential plot equivalent to 500 square yards.	-do
(ii) Height	and Storey	11 Meters., three storeyed	4 Meters, single storey.

(iii) Set back: It shall be at least 10 metres away from the edge of the agricultural land on all sides provided that if land attached to the farm house abuts a road, the house shall be constructed with a minimum set back from the edge of the road as under:-

(a)	Where the road is bye-pass to a scheduled road or an expressway	100 metres
(b)	Where the road is a scheduled road or as shown in the development plan	30 metres
(c)	Any other road	10 metres

(iv) Approach road

Any revenue rasta/road defined in the revenue record.

(v) Basement

Basement shall be permitted to the maximum extent of ground floor coverage and uses are permitted as per the Haryana Building Code-2017.

(vi) Ledge, loft and mezzanine floor

Ledge, loft and mezzanine floor shall be permitted within the building subject to the restrictions above as well as the restrictions stipulated in the definition given in clause –II of zoning regulations of Development Plan.

(vii) Services, water supply and drainage

- (a) Good potable water supply should be available in the farm for human consumption in case farm house is built.
- (b) Open Sanitary drains or covered drains to be provided to clean the sheds in case of dairy farms, Drains are to be provided for carrying rain water in case of all buildings.
- (c) Septic tank to be provided for disposal of human and animals waste as per provisions of the Rules.
- (d) The distance between the septic tank and open well or tubewell shall be as provided in the Rules.
- (viii) The owner shall be permitted to construct boundary wall around the main dwelling unit and ancillary portion thereof and around remaining area of farm barbed wire fencing shall be allowed.
- (ix) The Change of Land Use permissions for setting up of farmhouse shall be considered in the area other than over exploited or critical areas as declared by Central Ground Water Board.

Provided that Government may amend the minimum size of the farm for any scheme sponsored by the State Government/State agency for the proper utilisation of the agricultural zone.

XX. Provision of information technology units and cyber parks/cyber cities:-

(i) Location :

- (a) Information Technology Industrial Units will be located in Industrial Areas / Industrial Zones only;
- (b) Cyber Parks/Information Technology Parks will be located either in Industrial Areas or Industrial abutting sector roads in the form of integrated development. However, no manufacturing units will be permitted in such parks.
- (c) Cyber Cities:- The location of such a facility will be decided by the Government;

(ii) Size:

Serial Number	Туре	Size
1	Information Technology Industrial Unit	1 to 5 acres
2	Cyber Park / Information Technology Park	5 to 15 acres
3	Cyber City	minimum 50 Acres

(iii) Miscellaneous:

I Parking:

Parking will be as per the provisions of Haryana Building Code 2017 as amended from time to time.

II Other Activities:

- (a) Incidental commercial activities like Banks, Restaurants, Insurance Offices etc. shall be permitted subject to restriction of 4% of the gross area of the Cyber Park/Information Technology Park;
- (b) Only 5% of the area of the Cyber City shall be allowed for Group Housing and 4% of the total area of the Cyber City shall be permitted for Commercial/Institutional uses.
- (c) No residential plotted development shall be allowed in a Cyber City;
- (d) For a Cyber City Project if allowed in Agricultural Zone, the entrepreneur shall make the arrangement of water supply and other facilities like sewerage disposal/drainage etc;
- III The Government may impose any other condition as deemed necessary from time to time.

XXI. Setting up of communication towers:-

Permission of Mobile Towers within the controlled area shall be granted as per the policy instructions of Department memo dated 10.03.2015 and as amended from time to time;

XXII. Safety against Seismic Hazards:-

All the developments/building activities in the Development Plan area shall be carried out keeping in view the intensity of the seismic activity in development plan area, as per Seismic zone map of Indian Standard IS 1893:2002, in order to take care of the same the whole urban development shall be checked for safety against said intensity probability of occurrence, and upgraded for required seismic resistance in buildings and infrastructure as found necessary.

XXIII. Brick Kilns in controlled areas:-

Siting of the brick kilns in the Controlled Areas shall be governed by the respective policy/ guidelines issued by the Competent Authority from time to time.

XXIV. Relaxation of development plan:-

Government may in case of hardship or with a view to save any structure constructed before the material date, relax any of the provisions of the Development Plan on principles of equity and justice on payment of such development charges and on such other conditions as it may deem fit to impose.

APPENDIX A Classification of land uses

Main code	Sub code	Main group	Sub group
100		Residential	Residential Sector on neighborhood pattern
200		Commercial	particular control of particular parti
_ 0 0	210		Retail Trade
	220		Wholesale Trade
	230		Warehousing and Storage
	240		Office and Banks including Government Office
	250		Restaurants, Hotels and Transient Boarding Houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist House etc.
	260		Cinema and other places of public assembly on a commercial basis.
	270		Professional Establishments.
300		Industrial	
	310		Service Industry
	320		Light Industry
	330		Extensive Industry
400		Transport and Communication	
	410		Railway Yards, Railway Stations and Sidings
	420		Roads, Road Transport Depots and Parking Areas.
	430		Dockyards and Jettys
	450		Telegraphs Offices, Telephone Exchanges etc.
	460		Broadcasting Stations
	470		Television Station
500		Public Utilities	
	510		Water Supply installation including treatment plants
	520		Drainage and Sanitary installation including disposal works
	530		Electric power plants, sub-stations etc.
	540		Gas Installation and Gas work
	550		Solid Waste Disposal
600		Public and semi- public	
	610		Government Administrative Central Secretariat, District Offices, Law Courts, Jails, Police station, Governor and President's residences
	620		Education, Cultural and Religious Institutions
	630		Medical and Health Institutions
	640		Cultural institution like Theaters Opera Houses etc. of a predominately non-commercial nature.
	650		Land belonging to Defence.

Main code	Sub code	Main group	Sub group
700		Open Spaces	
	710		Sports Grounds, Stadiums and Play grounds
	720		Parks
	730		Green Belts, Garden, Agro forestry/floriculture and other Recreational Uses.
	740		Cemeteries, crematories etc.
	750		Fuel filling stations and bus queues shelters.
	760		Water Bodies/Lakes/Water Recharge Zone.
800		Agricultural land	
	810		Market Garden
	820		Orchards and nurseries
	830		Land under staple crops
	840		Grazing and land pastures
	850		Forest land
	860		Marshy land
	870		Barren land
	880		Land under water
	890		Diary farming
900		Special zone	Integrated Wayside Amenities

Appendix B

The permissible activities given under main land uses shall be allowed in accordance with the policy/parameters approved by the Government and/or at sites as approved by the Competent Authority in the Sector/Colony/Scheme Plan.

I. Residential Zone:

- (i) Residence
- (ii) Social community religious and recreational buildings
- (iii) Public utility building
- (iv) Educational buildings and all types of school and college where necessary
- (v) Health institutions
- (vi) Cinemas
- (vii) Commercial and professional offices
- (viii) Retail shops, dhabas and restaurants
- (ix) Local service industries
- (x) Fuel stations
- (xi) Bus stops, tonga, taxi, scooter and auto/rickshaw stand
- (xii) Nurseries and greenhouses
- (xiii) Any other minor needs to ancillary to residential use
- (xiv) Starred hotels
- (xv) Club/Community Centres
- (xvi) Communication Towers
- (xvii) Guest/Boarding Houses
- (xviii) Any other use, which the Government may in public interest decide

II. Commercial Zone:

- (i) Retail Trade.
- (ii) Wholesale Trade.
- (iii) Warehouses and storages.
- (iv) Commercial offices and banks.
- (v) Restaurant and Transient Boarding Houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist House etc
- (vi) Cinemas, Hotels, Motels and other places of public assembly like theatres, club, Dramatic Club, etc. run on commercial basis
- (vii) Professional establishments.
- (viii) Residences on the first and higher floors.
- (ix) Local service industry.
- (x) Public utility buildings.
- (xi) Fuel stations and service garages.
- (xii) Loading and unloading yards.
- (xiii) Parking spaces, bus stops, taxis, tonga and auto/rickshaw stand.
- (xiv) Town parks.
- (xv) Communication Towers
- (xvi) Any other use, which the Government may in public interest decide

III. Industrial Zone:

- (i) Light industry
- (ii) Medium industry
- (iii) Obnoxious and Hazardous Industry
- (iv) Heavy industry
- (v) Service industry
- (vi) Warehouse and storages
- (vii) Parking, loading and unloading area
- (viii) Truck stand/bus stops, taxi, tonga and auto/rickshaw stand
- (ix) Public utility, community buildings, retail shops, banks, dhabas, restaurants, two/three/five star hotels and insurance offices subject to a maximum limit of 3 percent of the total area of the sector as under:

Serial number	Name of	Area		No. of	Commercial	Maximum	Floor Area	Approach
	Facility	Minimum	Maximum	facilities	component	Ground Coverage	Ratio	Road
1	Dhabas	500 square metres	1000 square metres	2	50 square metres	40 %	0.40	Minimum 18 metres
2	Restaurants	1000 square metres	2000 square metres	2	10 %	30 %	1.50	Minimum 18 metres
3	Two/ Three Star Hotels	1.0 Acre	2.5 Acres	2	15 %	30 %	As per commercial policy	Minimum 24 metres
4	Five Star Hotels	2.5 Acres	4.0 Acres	1	15 %	30 %	As per commercial policy	Sector Dividing Road with the provision of a service road

(x) Service Garage and Sale/display Centre-cum- Service Garage:-

Serial number	Name of	Area		Commercial	Maximum	Floor	Approach	Height
	facility	Minimum	Maximum	component	ground coverage	Area Ratio	Road	
1	Service Garage	0.5	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/Display Centre-cum- service garage	0.5	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

- The fee and charges on commercial component shall be levied on the commercial rates.
- Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.
- (xi) Fuel stations and service garages.
- (xii) Liquid Petroleum Gas godowns permitted by the Director.
- (xiii) Cyber Parks/Information Technology Parks/ Information Technology Industrial Units
- (xiv) Health Facilities like Hospital, Dispensary, Nursing Home and Clinic as under:

Serial	Name of	Area			Residential	Maximum ground	
Number	facility	Minimum	Maximum	in a sector	component	coverage	area ratio
1	Hospital	2.5Acres	5.0Acres	1	15 %	33 %	1.00
2	Dispensary	1.0 Acre	1.5Acres	1	15 %	33 %	1.00
3	Nursing Home	250 square metre	500 square metre	2	Nil	60 %	1.00
4	Clinic	250 square metre	500 square metre	2	Nil	60 %	1.00

- (xv) Industrial Colony with a minimum area of 15 acres. The area utilization shall be as per policy issued vide ACS, T&CP, Haryana, Chandigarh memo no. Misc.388/PA(RB)/2015/7/16/2006-2TCP dated 01.10.2015 as amended upto date.
- (xvi) Communication Towers
- (xvii) Ready mix concrete plant, wet mix plants, hot mix plants
- (xviii) Weighing Bridges.
- (xix) Any other use, which the Government may in public interest decide.

IV. Transport and Communication Zone:

- (i) Railway yards, railway station and siding
- (ii) Transport Nagar, Roads and Transport depots and parking areas
- (iii) Airports and Air Stations
- (iv) Telephone exchange
- (v) Broadcasting stations
- (vi) Televisions station
- (vii) Agricultural, horticulture and nurseries at approved sites and places
- (viii) Fuel stations and service garages
- (ix) Parking spaces ,bus stop-shelters, taxi, Tonga and auto/rickshaw stands
- (x) Logistics Hubs/Container Yards, In land container Depot, Container Freight Station.

- (xi) Weighing Bridge.
- (xii) Communication Towers.
- (xiii) Warehouses upto a maximum limit of 20% of the total area of the sector.
- (xiv) Dhabas, as per prevailing policy.

V. Public Utilities:

- (i) Water supply installations including treatment plants.
- (ii) Drainage and Sanitary installations,- including sewage treatment plants and Disposal works.
- (iii) Electric Power plant and sub-station including grid sub-station.
- (iv) Gas installations and Gasworks.
- (v) Solid Waste Management sites.

VI. Public and Semi Public Uses Zone:

- (i) Government offices, Government Administration centres, secretariats and police station
- (ii) Educational, cultural and religious institutions
- (iii) Medical health institutions
- (iv) Civic/cultural and social institutions like theatres, opera houses etc. of predominantly non-commercial nature
- (v) Land belonging to Defence
- (vi) Dhabas, Restaurants as under:

Serial	Name of	Area		No. of	Commercial	Maximum	Floor	
number	Facility	Minimum	Maximum	facilities in a sector	component	Ground Coverage	Area Ratio	
1	Dhabas	500 square metre	1000 square metre	2	50 square metre	50 %	40 %	
2	Restaurants	1000 square metre	2000 square metre	2	10 %	30 %	150 %	

- (vii) Communication Towers
- (viii) Fuel Stations
- (ix) Any other use, which the Government may in public interest decide.

VII. Open Spaces:

- (i) Sports ground, stadium and playgrounds
- (ii) Parks, greenbelts,garden, agro forestry/floriculture and other recreational uses
- (iii) Cemeteries crematories etc.
- (iv) Fuel stations, bus queue shelter along roads with the permission of Director
- (v) Public utility services like electric grid station, transmission lines communication lines, water supply lines, sewerage lines, drainage lines in the green belts along the scheduled roads and major roads
- (vi) Water bodies/lakes /water recharge zone.
- (vii) Communication Towers
- (viii) Mela Ground and Multipurpose Ground.
- (ix) Any other use, which the Government may in public interest decide.

VIII. Agriculture Zone:

- (i) Agricultural, Horticultural, dairy and poultry farming.
- (ii) Village houses within Abadi-deh
- (iii) Farm houses outside abadi-deh subject to restrictions as laid down in zoning regulation XIX
- (iv) Afforestation development of any of the part for recreation

- (v) Expansion of existing village contiguous to abadi-deh if undertaken as a project approved or sponsored by the Central Government or State Government.
- (vi) Milk chilling station and pasteurization plant
- (vii) Bus Stand and railway station
- (viii) Airports with necessary buildings
- (ix) Wireless stations
- (x) Grain godowns, storage space at sites approved by the Director
- (xi) Weather stations
- (xii) Land drainage and irrigation, hydroelectric works and tubewell for irrigation
- (xiii) Telephone and electric transmission lines and poles
- (xiv) Mining and extraction operations including lime and brick kilns, stones, quarries and crushing subject to the rules and at approved site
- (xv) Cremation and burial grounds
- (xvi) Fuel station and service garages
- (xvii) Renewable and non-renewable energy power plants
- (xviii) Liquid Petroleum Gas storage godowns with the approval of the Director
- (xix) Small Scale Industrial units shall be allowed subject to fulfillment of the following conditions, provided that the site should not fall within restricted belt notified under the 'Works Defence Act, 1903' around Defence installations, if any, and minimum 30 feet wide revenue rasta/public road other than scheduled roads, National Highway and State Highway:

A. Siting norms						
Zone	Norms					
Medium potential zone	Within 2 kilometres from Urbanisable Zone (excluding the peripheral roads, if proposed along urbansiable boundary)	Beyond 2 kilometres from Urbanisable Zone (excluding the peripheral roads, if proposed along urbansiable boundary)				
	SSI Non-polluting, green, orange category units upto 5 acres.	Green and orange category units of any area.				
B. Approach norms						
Medium & Low Potential zone	Minimum 30 feet wide revenue rasta/public road be considered for grant of CLU permission in agriculture zone for industrial use. However, in case industrial Change of Land Use permission stands granted on 5 karam (27.5 feet) wide revenue rasta/public road, then application for CLU permission on the said road, shall be considered subject to the condition that the project proponent donates 1 karam (5.5 feet) wide strip of the applied land to the Gram Panchayat/Local Authority through Hibbanama/gift deed so as to make the approach 6 karma (33 feet) in front of the applied site.					

(xx) Non polluting Medium and Large Scale Agro-based Industries on Public road/rasta not less than 30 feet wide other than scheduled roads, National Highway and State Highway subject to the condition that site should not fall within restricted belt around the defence installation as applicable for such installation if any.

(xxi) Dhabas, Restaurants, Motels, Resort and Amusement Park/Theme Park along National Highway/ Scheduled Roads in the area outside restricted/ green belt as under:-

Serial Number	Permissible	Aı	·ea	Commercial	Maximum	Floor
	Activity	Minimum	Maximum	Component	Ground Coverage	Area Ratio
1	Dhabas	1000square metre	1 acre	50 square metre	40%	40%
2	Restaurant	2000square metre	1 acre	15 %	30%	150%
3	Motel with banquet facilities	2.5 acres	5 acres	15%	30%	150%
4	Resort	4 acres	10 acres	15%	30%	150%
5	Amusement Park/Theme Park	2.5 acres	10 acres	15%	30%	50%

Provided the access permission is obtained from National Highway Authority of India if the site is located on National Highway, and from Executive Engineer, Public Works Department (Building and Roads) if the site is located on scheduled road.

(xxii) Banquet Hall:

Permissible Zone	Agriculture
Approach	 Minimum width of the approach road must be 18metres. The access permission is required from XEN, PWD (B&R) if the site is located on scheduled road. Approach from National Highways can be considered, if the site fulfills minimum distance norms from intersection/access and is located on minimum 7 metres wide service road or the applicant submits prior permission of access from NHAI.
Area Required	Minimum area :- 2.5 acres Maximum area :- 5.00 acres
FAR	0.5
Ground Coverage	30%
Conversion Charges	50% of the rates prescribed for commercial use
Permissible Ancillary uses within Floor Area Ratio	10% of the allowed FAR for Gift shop, STD Booth, Toy Centres and flowers shops etc.
Parking	Minimum 25% of the site area

- **Note.** The provision of marriage palace/Banquet Hall within the Municipal Limit shall be as per the policy approved by the Department of Urban Local Bodies and as amended from time to time.
 - (xxiii) Microwave Towers /Station, Seismic Centres and Telecommunication Centres
 - (xxiv) Communication Towers

(xxv) Ready Mix Concrete Plants, Wet mix plants, Hot Mix Plants connected with the projects for which contract or work is assigned by Government or Government agency and to be set up on short term basis.

(xxvi) Service Garage and Sale/display Centre-cum- Service Garage

Serial	Name of	Area (in acres)		Commercial	Maximum	Floor	Approach	Height
Number	Facilities	Minimum Maximum		Component	Ground Coverage	Area ratio	Road	
1	Service Garage	0.5	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/display Centre- cum- service garage	0.5	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

- The fee and charges on commercial component shall be levied on the commercial rates
- Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.

(xxvii) Weighing bridges.

(xxviii) Educational institutions.

(xxix) Any other use, which Government may in Public Interest, decide.

(IX) Special Zone

Wayside amenities including services like parking, fuelling, servicing and repairs, telephone and telecommunication, dhaba/restaurants and motels, medical, police, public conveniences, entertainment, banking (ATMs), and other needed services to facilitate highway traffic.

(X) Uses Strictly Prohibited:

Storage of petroleum and other inflammable material without proper license.

APPENDIX-1

Categories of Industries included in the scope / definition of Information Technology Industry

(A) Computing Devices including

Desktop

Personal Computer

Servers

Work-station

Nodes

Terminals

Network P.C

Home P.C.

Lap-top Computers

Note Book Computers

Palm top Computer/PDA

(B) Network Controller Card/ Memories including

Network Interface Card (NIC)

Adaptor Ethernet /PCI/EISA/Combo/PCMICA

SIMMs Memory

DIMMs Memory

Central Processing Unit (CPU)

Controller SCSI/Array

Processors Processor/Processor Power Module/Upgrade

(C) Storage Units including

Hard Disk Drives/Hard Drives

RAID Devices and their Controllers

Floppy Disk Drives

C.D. ROM Drives

Tape Drives DLT Drives/DAT

Optical Disk Drives

Other Digital Storage Devices

(D) Other

Key Board

Monitor

Mouse

Multi-media Kits

(E) Printers and Output Devices including

Dot matrix

Laserjet

Inkjet

Deskjet

LED Printers

Line Printers

Plotters

Pass-book Printers

(F) Networking products including

Hubs

Routers

Switches

Concentrators

Trans-receivers

(G) Software including

Application Software

Operating system

Middleware/Firmware

(H) Power supplies to Computer Systems including

Switch Mode Power Supplies

Uninterrupted Power supplies

(I) Networking/Cabling and related accessories

(related to IT Industry)

Fibre Cable

Copper Cable

Cables

Connectors, Terminal Blocks

Jack Panels, Patch Cord

Mounting Cord/Wiring Blocks

Surface Mount Boxes

(J) Consumables including

C.D.ROM /Compact Disk

Floppy Disk

Tapes DAT/DLT

Ribbons

Toners

Inkjet Cartridges

Inks for Output devices

(K) Electronic Components

Printed Circuit Board/Populated PCB

Printed Circuit Board/PCB

Transistors

Integrated Circuits/ICs

Diodes/Thyristor/LED

Resistors

Capacitors

Switches (On/Off, Push button, Rocker, etc.)

Plugs/sockets/relays

Magnetic heads, Print heads

Connectors

Microphones/Speakers

Fuses

(L) Telecommunication Equipment including:

Telephones

Videophones

Fascimile machines/Fax cards

Tele-Printers/Telex machine

PABX/EPABX/ RAX/MAX Telephone Exchange

Multiplexers/Muxes

Modems

Telephone answering machines

Telecommunication Switching Apparatus

Anetna and Mast

Wireless datacom equipment

Receiving equipments like Pagers, mobile/Cellular Phones, etc.

VSATs

Video Conferencing Equipments

* Including Set Top Boxes for both Video and Digital Signaling.

(M) IT Enabled Services are business processes and services, the end products/services of which are:-

- Delivered outside India.
- Delivered over communication network., and

• Either externally contracted (out-sourced) or provided by a remote subsidiary of the same company (out-located).


Note: Services which would not be included are:-


- Remote production/manufacturing units
- The Corporate offices of companies or their local branches
- Virtual business on Internet.


The following services which meet the above criteria would be included:-

- (i) Back-Office Operations
- (ii) Call Centres
- (iii) Content Development or Animation
- (iv) Data Processing
- (v) Engineering and Design
- (vi) Geographic Information System Services
- (vii) Human Resource Services
- (viii) Insurance Claim Processing
- (ix) Legal Database
- (x) Medical Transcription
- (xi) Payroll
- (xii) Remote Maintenance
- (xiii) Revenue Accounting
- (xiv) Supports Centres and
- (xv) Web-site Services.

S. N. ROY, Additional Chief Secretary to Government, Haryana, Urban Local Bodies Department. A.K. SINGH, Principal Secretary to Government, Haryana, Town and Country Planning Department.







8971—C.S.—H.G.P. Pkl.